

Addendum #3
Project #2767A
Brown County Port Development Project
Port & Resource Recovery
October 27, 2025
Request for Bid

See original specification packet for addresses

THIS ADDENDUM IS ISSUED TO MODIFY, EXPLAIN OR CORRECT THE ORIGINAL DRAWINGS AND SPECIFICATIONS AND IS HEREBY MADE PART OF THE CONTRACT DOCUMENTS. THIS ADDENDUM MUST BE ACKNOWLEDGED ON THE ADDENDUM RECEIPT SCHEDULE, WHICH WAS INCLUDED IN THE ORIGINAL DOCUMENT PACKAGE.

Vendors are required to read entire addendum to determine requirements affecting their contract.

Addendum #3

This addendum is for the following:

- To provide revised pipe combi wall calc package

RFB DUE DATE
11/18/25 BY 11:00 A.M. CST

	CALCULATION COVER PAGE			Page	
				Rev. No.	
	Client	BROWN COUNTY WI			
Project	Port Property Development				
Project No.	2201593	Document No.	N/A		
Calc. Title	Port Property Development - Dock Wall Design				
Summary This submission provides the 90% design demands to be used in the design of the structural components for the Brown County Port Property Development dock wall for the support of a multi-use port facility by handling a range of dry cargoes and provide a berthing face to be used by large cargo ships, located in Green Bay, Wisconsin.					
The major components of the dock wall design include: - Dock Wall: 54" x 11/16" pipe & NZ-26 (ASTM A572, Gr. 60) Pipe-Combined Wall System , king piles spaced 9.3-ft O.C., I = 4,607 in4/ft, S.x = 170.6 in3/ft, All. Moment = 510.8 k-ft/ft - Deadman Sheets: NZ-19 (ASTM A572, Gr. 60), I = 283.1 in4/ft, S.x = 35.08 in3/ft, All. Moment = 105.2 k-ft/ft - Deadman Tierod: No. 28 (ASTM A615, Gr. 75/80), tierods spacing: 9.3-ft O.C.					
Signature Block & Record of Revisions					
Rev.	Description	Code	Pages/Sections	Signature	Date
0	90% Design	P	All	E. Burton/A. Gradeski	10/22/25
		C	All	C. Englert	08/25/25
		A	All	A. Pepin	
<i>Codes: P = Prepared; C = Checked; A = Approved</i>					

GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Table of Contents

Section	Pg. #
Design Purpose	
Soil Properties	
Analysis & Design Methodology	
Construction Sequence	
Summary of Results	
Conclusion	
Appendix A: Dock Wall Calculations	
Dock Wall WALLAP Analysis	
Deadman Sheeting WALLAP Analysis	
Tierod Structural Design	
Tierod Connection Design	
Appendix B: Borings Considered for Dock Wall Analysis	
Appendix C: Brown County Port Property Geotechnical Data Report	
Appendix D: Brown County Dock Wall Global Stability Analysis	
Appendix E: Settlement Analysis	
Appendix F: Seismic Evaluation	
Attachment 1: Nucor Skyline Steel Cutsheet	
Attachment 2: AISC, 14th Edition; Densities of Common Materials	
Attachment 3: WALLAP Analysis Input Parameters	
Attachment 4: Undrained and Drained Elastic Moduli	

GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Purpose

The purpose of this project is to analyze and design an anchored bulkhead wall to support operations at a bulk material handling marine terminal facility. Figures 1 - 4 provide the existing and proposed site conditions of the property. The proposed dock wall will retain fill and material stockpiles on the site and provide a berthing face for bulk carrier ships. At the time of this report, the extent of the stockpile area on the landside of the dock wall is unknown, therefore the material stockpile was conservatively considered at each analysis section. A generalized section of the waterside dock wall system is provided as Figure 5. The dock wall will be a combined wall system consisting of steel pipe king piles and steel sheet piling. The proposed berth depth will be consistent with the Fox River navigation channel, with a minimum draft of 26 feet relative to low water datum (LWD). Including a 2-foot over-dredge results in a maximum dredge depth of 28 feet relative to LWD (El. -550 NAVD88). Proposed site grades along the proposed dock wall will be no greater than +591.0 NAVD88 and pitch down moving away from the wall. To support this exposed wall height, a tie rod and anchor wall system was designed to restrain the proposed wall.




Figure 1: Generalized Dock Wall Cross-Section

GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Vertical Datum

Unless otherwise stated, all datums refer to the North American Vertical Datum of 1988 (NAVD88) which is approximately 0.44-feet below the low water datum IGLD85 (i.e. IGLD85 + 0.44' = NAVD88).

Soil Properties

We selected soil properties developed in GEI's Geotechnical Data Report, dated March 2023, to analyze the various sections of the dock wall. Thicknesses of each considered soil layer were informed by soil borings nearest the considered sections and borings selected for design have been included in Appendix B. A summary of the soil properties used for analysis can be seen in Table 1.

TABLE 1. SOIL PROPERTIES

Name	Total Unit Weight (pcf)	Undrained Strength Parameters		Effective Stress Strength Parameters (drained)		†Undrained Elastic Modulus (psf)	Coefficient of Consolidation, C_c (-)	Initial Void Ratio, e_0 (-)	†Drained Elastic Modulus (psf)	Rankine Earth Pressures Coefficient, Drained		
		Su (psf)	ϕ (deg)	c' (psf)	ϕ' (deg)					Ko	Ka	Kp
Marine Stone Fill ⁸ (AASHTO No. 67)	120				36				3,000,000	0.41	0.26	3.85
Granular Fill (Above Water)	130	-	—	-	32	-	-	-	(42,000)	0.47	0.31	3.25
Granular Fill (Below Water)	125	-	-	-	30	-	-	-	(15,000)	0.50	0.33	3.00
Sediment - CA-94 and CB-60	80	60	-	-	24	-	-	-	(36,000)	0.59	0.42	2.37
(Existing) Fill: Sand/Clay	130	2000	-	-	30	1,200,000	0.33	2.0	28,527	0.50	0.33	3.00
CLAY I	130	2000	-	-	28	1,200,000	0.33	0.9	43,889	0.53	0.36	2.77
CLAY IIA	130	1000	-	-	26	600,000	0.44	1.0	47,151	0.56	0.39	2.56
CLAY III	130	2500	-	-	26	1,500,000	0.47	1.2	68,650	0.56	0.39	2.56
Coal (Stockpile)	60	0	36	-	36	-	-	-	-	0.41	0.26	3.85
Limestone (Stockpile)	100		45		45	-	-	-	-	0.29	0.17	5.83
Sand and Gravel (sediment capping materials)	125	0	35	-	35	-	-	-	-	0.43	0.27	3.69

Notes:

1. Clay I corresponds to Clay - Very Stiff from Geotechnical Data Report (GDR) dated March 2023, Clay IIA to Clay - Soft, Clay IIB to Clay - Soft (NE Corner) and Clay III to Clay - Stiff
 2. Soils below the continuous wall (depth at which sheeting concludes and king piles continue to max embedment depth) are considered using Ka and Kp values for design in WALLAP based on guidance from AASTHO 2012, Section 3.11.5.6. Ka and Kp values are modified to develop and equivalent continous wall lateral earth pressure coefficient for consideration in WALLAP.
 3. 54" Pipe at 112" on-center
 4. Fill considered granular
 5. For long-term, drained conditions, Kpc and Kac = 0
 6. Undrained Elastic Modulus is based on Duncan and Buchignani (1987) conservatively considering $E = 600 * Su$ for clays and dE/dy (psf/ft) for granular soils varies based on soil density and N-value.
 7. Drained Elastic Modulus is based on consolidation parameters presented in Section 4.7 of the GDR dated March 2023
 8. Marine Stone Fill produces an angle of internal friction of 40 degrees, however we've assumed that the stone fill will be placed through the water column which reduces the friction angle to approximately 36 deg based on USACE EM 1110-2-2503, Table 4-2
- †: Moduli that vary with depth (dE/dy) are shown in parantheses

GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Because we are considering a combi-wall system with the king piles extending beyond the sheet piles, we used the methodology described in AASHTO (2012) Section 3.11.5.6 to model equivalent, continuous active and passive lateral earth pressures along the embedded length of the king piles. Continuous, equivalent lateral earth pressure coefficients can be seen in Table 2.

Name	Equivalent Continuous Wall LEP Coefficients (based on AASHTO 2012) (Short-Term, Undrained $\phi=0$)				Equivalent Continuous Wall LEP Coefficients (based on AASHTO 2012) (Long-Term, Drained $S_u=0$)			
	Equiv. K_a	Equiv. K_{ac}	Equiv. K_p	Equiv. K_{pc}	Equiv. K_a	Equiv. K_{ac}	Equiv. K_p	Equiv. K_{pc}
Granular Fill (Above Water)	-	-	-	-	-	-	-	-
Granular Fill (Below Water)	-	-	-	-	-	-	-	-
Sediment - CA-94 and CB-60	0.484	0.968	-	2.00	0.204	0	2.371	-
(Existing) Fill: Sand/Clay	0.484	0.968	-	2.00	0.161	0	3.000	-
CLAY I	0.484	0.968	-	2.00	0.175	0	2.770	-
CLAY IIA	0.484	0.968	-	2.00	0.189	0	2.561	-
CLAY III	0.484	0.968	-	2.00	0.189	0	2.561	-


Table 2: Equivalent, Continuous Lateral Earth Pressure Coefficients

General Dock Wall Design Criteria

- Top of Wall Elevation: 591.0
- Maximum Berth Elevation: 552.0
- Minimum Berth Elevation: 550.0 which includes a 2-foot over-dredge tolerance
- Maximum Deflection: 6-inches (<1 degree out of plumb)
- Design Life: 50 years

Structural Material Properties

- King Piles: Grade 60 ksi
- Steel Sheet Piles: Grade 60 ksi
- Tiebacks: Grade 75/80 ksi
- Rolled Shapes and miscellaneous metals: 50 ksi
- Welding Consumables: E70XX Electrodes
- Bolts: ASTM F1325 (Grade A325)



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Loading Conditions

Uniform Live Loads:

Where stockpile loads were not present, a 500 psf uniform surcharge load was modeled.

Bulk Material Stockpiling Loads:

The dock wall analysis includes trapezoidal stockpile loads to model 60-foot-high coal and 40-foot-high limestone piles. Maximum stockpile heights and minimum setbacks from the dock wall are based on the global slope stability analysis performed by GEI under a separate cover. A summary of the modeled stockpiles is provided as Table 3. Although the top of the stockpiles will extend several hundred feet inland of the wall, we only modeled the lateral extent of stockpile that would intersect the retained height of wall of 41-ft at an angle of 45 degrees from design dredge elevation (El. 550-ft). For the dock wall analysis, we assumed that the effect of the stockpile surcharge beyond the retained height of the wall would have a negligible effect on dock wall, therefore a limited portion of the stockpile was modeled.

Stockpile Material Considered for Design	Bulk Unit Weight (pcf)	Maximum Angle of Repose (degrees)	Minimum Wall Setback (ft)	Maximum Stockpile Height (ft)
Coal	60	36	15	60 (3,600 psf)
Limestone	100	45	50	40 (4,000 psf)

Table 3: Stockpile Material Properties

Fender Loads:

Fender loads from ship berthing would counteract the driving earth pressure loads therefore no fender loads were considered for the dock wall analysis.

Mooring Loads:

Mooring fixtures will be supported on an independent foundation system, however we considered a 100-ton horizontal load on the dock wall as well as a 10psf/ft of dead load in our WALLAP analyses.

Groundwater:

Water levels at the site are influenced by variations in lake level and storm surges. Water level data was obtained from the U.S. Department of Commerce, NOAA, and the National Ocean Services (NOS) Tides and Currents website. Green Bay East gauge (Station ID 9087077) data shows current water levels but historic

GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

data only extends back to 2020 and no extreme water levels are provided. Menominee gauge (Station ID 9087088) provides maximum and minimum water levels as follows:

Water Elevations NOAA STA ID 9087088 Menominee (ft - NAVD88)	
Water Level Max	583.24
Water Level Min	574.84
<u>Water Elevations NOAA STA ID 9087077 Green Bay East (ft - NAVD88)</u>	
Water Level Max (8/2/2020)	583.20
Water Level Min (12/23/2022)	578.09
Design Low Water Datum	577.94
Current Water Level (6/21/2024)	580.11

Table 4: NOAA Station Data

According to NOAA, the average daily water elevation is about 580.2-ft NAVD88. However, this elevation fluctuates daily - typically fluctuations in elevation range from 1 to 2 feet around the lake's average elevation. Though not as predictable as tidal cycles, the time between local minima and maxima was found to vary between 2 to 8 hours.

Water levels assumed on the riverside were assumed to be near the low water level and were modeled at El. 576.0. Water levels in front and behind the wall are anticipated to closely correlate with each other however we included a differential head of 1-foot between the river water and groundwater elevation (i.e. groundwater is 1-foot above the river elevation).

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
Earthquake: The following parameters were used to develop seismic loading for the dock wall. Unmodified ground motion parameters are from the ASCE Hazard Mapping tool and based on the values published in ASCE7-10. Risk Category: II Site Class: E Peak Ground Acceleration: 0.024g Peak Ground Acceleration modified for Site Class: 0.061g Design Peak Ground Acceleration: 0.041g We estimated seismic loads for the retained fill and reductions in waterside earth pressures using the methods developed by Mononobe-Okabe and Westergaard, respectively. Seismic activity at the site is minimal therefore we compared the seismic load to the driving load resulting from the 500 psf live load. Since the uniform live load is a transient load, it is considered to not be present during the design earthquake. Comparing the total seismic load to the driving load due to the 500 psf live load, it was determined that the live load imparted a significantly larger load on the wall and bounds the seismic effects. Similarly, by inspection, the coal and limestone stockpile loads will impart a significantly larger load on the wall. Therefore, seismic loads were not considered further for the wall analysis. Load Cases Three (3) load cases were analyzed for each wall section as described below. LC1. Coal surcharge (3600 psf) with a 15-ft wide, 500 psf uniform live load behind the dock wall. (See Figure 5) LC2. Limestone surcharge (4000 psf) with a 50-ft wide, 500 psf uniform live load behind the dock wall. (See Figure 6) LC3. Limestone surcharge (4,000 psf) setback 75-feet inland from the wall (toe of material stockpile is at the anchor wall) with a 50-ft wide, 500 psf uniform live load on the landside of the dock wall. A 25-foot width on the waterside of the anchor wall was left unloaded since this would apply additional passive resistance to the anchor wall. This condition is considered a short-term condition but will likely occur on a regular basis based on offloading operations (fill is anticipated to offloaded via a ship-mounted stacker working inland towards dock wall). (See Figure 7)						



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	
By	E. Burton	Chk.	C. Englert	App.	A. Pepin
Date	10/22/2025	Date	8/25/2025	Date	

Project No.	2201593	Document No.	N/A
Subject	Port Property Development – Dock Wall Design		




Figure 5: Load Case 1 Loading Diagram




Figure 6: Load Case 2 Loading Diagram



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	
By	E. Burton	Chk.	C. Englert	App.	A. Pepin
Date	10/22/2025	Date	8/25/2025	Date	

Project No.	2201593	Document No.	N/A
--------------------	---------	---------------------	-----

Subject	Port Property Development – Dock Wall Design
----------------	--





Figure 7: Load Case 3 Loading Diagram



GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Dock Wall Analysis Sections

We considered four (4) sections for analysis along the dock wall alignment. General locations for each section considered can be seen in Figure 8. Cross-sections, general descriptions, and anticipated construction sequence are described on the following pages. Final construction sequencing will be determined by the Contractor.




Figure 8: Sections Considered for Analysis

GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Section A

Section A is located near the northern return of dock wall in an area that is currently water. Based on the boring in this area, there are considerable deposits of soft sediments which will need to be removed and replaced with granular fill. The sediments cannot remain in place due to excessive settlements which would occur to fill the area to final grade and considerable stresses it would impart on the dock wall system. Ground improvement was not considered for this analysis.




Figure 9: Section A cross-section

Anticipated Construction Sequence:

1. Pre-dredge as required to minimize cantilevered height as required for stability during sediment removal.
2. Drive king piles and sheets to respective required embedment depth.
3. Excavate Sediment layer to top of Clay 1 in area of driveline.
4. Place first lift of Granular Fill to El. 580 to facilitate installation of tierods and anchor wall.
5. Drive anchor wall sheets and install tierods/wales.
6. Place second lift of Granular Fill to El. 591 (Top of Wall).
7. Dredge to Elevation 552.0 (no deeper than 550).

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Section C

Section C is located at the historic boat slip. Mudline in this area is deep and is approximately 1-foot above the required dredge elevation. A temporary work platform will be required to facilitate construction of the tieback system.




Figure 11: Section C cross-section

Anticipated Construction Sequence:

1. Drive king piles and sheets to respective required embedment depth.
2. Place Granular Fill on the landside to construct temporary construction platform. For the purposes of this analysis, we assumed the first lift of Granular Fill would go up to EL. 565 at the dock wall and slope up at a 2H:1V. We conservatively assumed an infinite slope condition rather than modeling a berm to convince ourselves this approach would be viable. Fill operations during construction will ultimately be determined by the Contractor based on his means and methods. The Contractor will need to minimize the deflection at the top of the wall prior to installation of the tieback system.
3. Once the construction platform is built, install anchor wall sheets and tiebacks. Temporary supports may be required for tiebacks prior to final backfilling.
4. Place second lift of Granular Fill to Top of Wall at EL. 591.
5. Dredge to Elevation 552.0 (no deeper than 550).

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Section D

Section D is located at the historic discharge slip. The existing mudline is approximately El. 570 with an approximately 4-foot-thick layer of sediment.




Figure 12: Section D cross-section

Anticipated Construction Sequence:

1. Drive king piles and sheets to respective required embedment depth
2. Place lift of Granular Fill to El. 580. Note, wall is cantilevered 10' in temporary condition.
3. Remove sediments from influence zones of anchor wall.
4. Drive anchor wall sheets and install tiebacks.
5. Place lift of Granular Fill to Top of Wall at El. 591.
6. Dredge to Elevation 552.0 (no deeper than 550).



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	
By	E. Burton	Chk.	C. Englert	App.	A. Pepin
Date	10/22/2025	Date	8/25/2025	Date	

Project No.	2201593	Document No.	N/A
--------------------	---------	---------------------	-----

Subject	Port Property Development – Dock Wall Design
----------------	--

DEADMAN
LOAD CASE: X.3




Figure 13: Deadman Load Case X.3 cross-section

GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					

Summary of Results

Initially, a wide-flange, beam-combined system was selected for the design of the dock wall. Four wall cross sections were analyzed; each section was analyzed for the three load cases referenced herein. For this assessment, in which we have selected a pipe-combined wall system, we have only evaluated the critical live load condition for each wall cross section. Please note that the critical live load condition was the same for each wall cross section: LC1. For the deadman analyses, the loading conditions of LC1 and LC3 were considered, however only the maximum tierod load was used.

Results of the previous, wide-flanged, beam-combined dock wall WALLAP analyses are summarized in Table 5.

Analysis Section	Dockwall Construction Details					Load Case ID	Dockwall Loads				
	Top of Wall Elevation (ft)	Beam-Combined Wall System (-)	Tip of Sheets Elevation (ft)	Tip of King Piles Elevation (ft)	Tierod Elevation at Wall Face (ft)		Tieback Load (kip/ft of wall)	Moment Demand (kip-ft/ft of wall)	Shear Demand (kip/ft of wall)	Deflection (ft)	Critical Toe FS (-)
A	591	W40x199 & NZ-14	540	515	584	A.1	27.8	344	24	0.386	2.16
						A.1-W	24.9	316.4	24.1	0.52	2.3
						A.2	27.6	339	23.8	0.381	2.19
						A.3	27	327.3	23.3	0.371	2.25
						B.1	29.1	402.1	26.8	0.253	1.54
B	591	W44x230 & NZ-14	540	520	584	B.1-W	24.6	342.7	23.3	0.221	1.74
						B.2	28.9	395.3	26.5	0.248	1.56
						B.3	28.2	379	25.9	0.237	1.61
						C.1	26.8	354.8	24.1	0.233	1.66
						C.1-W	24.9	348.9	23.7	0.23	1.73
C	591	W44x230 & NZ-14	540	520	584	C.2	26.6	350	23.9	0.229	1.69
						C.3	26	333.9	23.2	0.219	1.74
						D.1	28.1	375.8	25.4	0.248	1.63
						D.1-W	24.9	350.2	23.6	0.259	1.74
						D.2	28.1	372.2	25.3	0.247	1.65
D	591	W44x230 & NZ-14	540	520	584	D.3	27.4	358.7	24.7	0.238	1.7

Notes:

1. The low water datum (LWD) for the Fox River is +577.5 (IGLD85) or 577.9 (NAVD88). The authorized dredge depth for the Port is 26.0 feet; EL +551.9 (NAVD88). Considering a 2-ft overdredge allowance, design dredge = EL +550.0 (NAVD88).
2. The coal stockpile assumes an angle of repose of 36 degrees, a unit weight of 60 pcf, a maximum allowable stockpile height of 60 ft (3600 psf) and a minimum setback of 15 ft from the face of the wall.
3. The limestone stockpile assumes an angle of repose of 45 degrees, a unit weight of 100 pcf, a maximum allowable stockpile height of 40 ft (4000 psf) and a minimum setback of 50 ft from the face of the wall.
4. An undrained shear strength for Clay IIA in* 1,500 psf was assumed for this analysis only based on the average undrained strength measured at BW-3-22 about equal to 1,550 psf.

Table 5: Dock Wall WALLAP Results

Similar soil properties were used, however for this analysis we considered drained as well as undrained elastic moduli values based on laboratory test results provided in the Geotechnical Data Report (Appendix C) and the active and passive pressure coefficients for the embedded length of the king piles were updated for the new effective pile width.

The previous dock wall analysis used the approach produced by Brom's (1965) for the king piles in which the active pressure on the embedded length of the king piles is considered negligible and can be neglected. However, while the approach produced by Brom's could be valid, we've conservatively selected the methodologies described in AASHTO (2012) Section 3.11.5.6 for the development of equivalent,

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
continuous lateral earth pressure coefficients - which no longer neglects active pressures on the embedded length of the king piles. In keeping with the assumptions of the previous analysis, wall friction has been neglected. Results of the critical load case for each wall cross section of the pipe-combined dock wall WALLAP analyses are summarized in Table 6.						

Analysis Section	Dockwall Construction Details					Load Case ID	Dockwall Loads				
	Top of Wall Elevation (ft)	Beam-Combined Wall System (-)	Tip of Sheets Elevation (ft)	Tip of King Piles Elevation (ft)	Tierod Elevation at Wall Face (ft)		Tierod Load (kip/ft of wall)	Moment Demand (kip-ft/ft of wall)	Shear Demand (kip/ft of wall)	Deflection (ft)	Critical Toe FS ⁵ (-)
A	591	P54"x11/16" &NZ26	540	509	584	A.1	27.4	303.3	25.7	0.242	2.2
B	591	P54"x11/16" &NZ26	540	509	584	B.1	34.5	470.4	30.0	0.303	2.3
C	591	P54"x11/16" &NZ26	540	509	584	C.1	31.2	393.4	26.2	0.293	2.4
D	591	P54"x11/16" &NZ26	540	509	584	D.1	28.7	331.4	24.4	0.204	2.4

Notes:

1. The low water datum (LWD) for the Fox River is +577.5 (IGLD85) or 577.9 (NAVD88). The authorized dredge depth for the Port is 26.0 feet; El. +551.9 (NAVD88). Considering a 2-ft overdredge allowance, design dredge = El. +550.0 (NAVD88).
2. The coal stockpile assumes an angle of repose of 36 degrees, a unit weight of 60 pcf, a maximum allowable stockpile height of 60 ft (3600 psf) and a minimum setback of 15 ft from the face of the wall.
3. The limestone stockpile assumes an angle of repose of 45 degrees, a unit weight of 100 pcf, a maximum allowable stockpile height of 40 ft (4000 psf) and a minimum setback of 50 ft from the face of the wall.
4. An undrained shear strength for Clay IIA in= 1,500 psf was assumed for this analysis only based on the average undrained strength measured at BW-3-22 about equal to 1,550 psf.
5. Critical Toe FS is 1.5 when considering FS = 1.5 applied to Passive term in Wallap analyses. This run in Wallap pproduces required minimum toe embedment for FS = 1.5. A subsequent wallap run without FS applied to passive Kp produces max moment, max deflection, shear and deflection. Therefore, the FS presented is misleading despite correpsonding to the FS of the wall in the second Wallap run.

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
Results of the deadman WALLAP analyses are also provided in Appendix A and summarized below in Table 7.						

TABLE 7. DEADMAN WALLAP ANALYSIS RESULTS

Analysis Section	Deadman Construction Details					Surface Live Loads					Deadman Loads				
						Load Case ID	Parent Dockwall Analysis Section(s)	Water Elevation (ft)	Stockpile ¹						
	Top of Deadman Elevation (ft)	Beam- Combined Wall System (-)	Tip of Sheets Elevation (ft)	Sheet Pile Length (ft)	Tierod Elevation at Deadman (ft)				Type (-)	Location (P or A)	Tieback Load (kip/ft of wall)	Moment Demand (kip-ft/ft of wall)	Shear Demand (kip/ft of wall)	Deflection (ft)	Critical Toe FS (-)
BL-14-22	585	NZ-14	555	30	581.5	X.1	B.1/D.1	577	Coal	P&A	31.8	53.9	25.8	0.21	2.12
						X.3	B.3/D.3	577	Limestone	A	31.8	58.6	23.8	0.23	1.65
Fill	585	NZ-19	555	30	581.5	X.1	A.1/C.1/D.1	577	Coal	P&A	31.8	62.9	20	0.31	1.70
						X.3	A.3/C.3/D.3	577	Limestone	A	31.8	65.0	20.5	0.46	1.58

Notes:

1. P = Passive Side; A = Active Side

2. A high groundwater condition equal to the extreme high lake levels was assumed. Groundwater is anticipated to closely correlate with the lake levels however precipitation may result in a greater differential. Conservatively, the tieback loads for the low lake level condition were used for the analysis.

3. Considering the relatively high deflections noted, we've assumed that the tierods will be post-tensioned to mitigate deflections at deadman sheeting which will translate to movement at the dockwall.

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	10/22/2025	Date	8/25/2025	Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
Conclusion The controlling tierod load from the pipe-combined wall was used for design of the tierod and deadman system, however a 30% increase in tierod load (1.30 x 34.5 k-ft/ft of wall = 44.9 k-ft/ft) was used to specify the required size of tierod as well as evaluated in the associated structural connections. We conservatively assumed this increase in tierod load for evaluation and sizing due to the uncertainty in the loading conditions of the anchored bulkhead wall over its design life. Additionally, due to the deflections estimated in our deadman system analysis, which assumes a passive anchorage system, we've conservatively assumed that the tierods will be pre-stressed. Pre-stressing the tierods will mitigate deflections at the dockwall face in keeping with the maximum allowable deflection of 6-inches. We have also assumed that the tierods will be protected against corrosion with double corrosion protection and, to mitigate the negative effects of settlement beneath the tierods, a 12" diameter PVC conduit will be installed around the tierods such that when the ground around the tierod settles, the PVC may settle, but the tierods will remain unaffected. The allowable capacity of the pipe system at the end of its service life is $0.94 * 510.8 \text{ kip*ft/ft} = 480 \text{ kip*ft/ft}$ which is greater than the maximum moment demand of 470 kip*ft/ft. Use 54"x11/16" king piles with NZ26 intermediate sheet piles. Minimum king pile tip elevation is El. 509 and intermediate sheeting tip elevation is El. 540. For the deadman wall, use NZ19 sheet piles. Minimum sheet pile tip elevation is El. 555. The allowable capacity of the deadman sheeting at the end of its service life is $0.85 * 91.2 \text{ kip*ft/ft} = 77.5 \text{ kip*ft/ft}$ which is greater than the maximum moment demand of 65 kip*ft/ft. Considering a 30% increase in tierod load, use #28, 3.5" diameter tierods with double corrosion protection and a 12" diameter PVC pipe for mitigation of additional tensile stresses due to settlement beneath the tierods.						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
APPENDIX A: DOCK WALL CALCULATIONS						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
DOCK WALL WALLAP ANALYSIS						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
WALLAP ANALYSIS: A.1 – EMBEDMENT CHECK						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecA-A-1 EmbedmentCheck

Pulliam Dock Wall - Section A - Pipe 54x5/8 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : AJG

|

| Date:15-07-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	575.00	12 Sediment	12 Sediment
2	547.00	3 Clay I	3 Clay I
3	540.00	17 KP - Clay I	17 KP - Clay I
4	532.00	7 KP - Clay IIA	7 KP - Clay IIA
5	517.00	8 KP - Clay III	8 KP - Clay III

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft3	Eh, lb/ft2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	lb/ft2 (dc/dy)
1 Not defined							
2 Existing Fill	130.0	1200000	0.500	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000u
3 Clay I	130.0	1200000	0.531	NC (0.490)	1.000 (2.000)	1.000 (1.330)	2000d
4 Clay I - L. Term	130.0	43889	0.531	OC (0.490)	0.361 (0.000)	1.847 (0.000)	
5 Clay IIA	130.0	600000	0.561	NC (0.490)	1.000 (2.000)	1.000 (2.000)	1000d
6 Clay IIA - L.Term	130.0	600000	0.561	OC (0.490)	0.390 (0.000)	2.561 (0.000)	
7 KP - Clay IIA	130.0	600000	0.560	NC (0.490)	0.484 (0.968)	0.000 (1.330)	1000d
8 KP - Clay III	130.0	1500000	0.560	NC (0.490)	0.484 (0.968)	0.000 (1.330)	2500d
9 KP-ClayIIA. L.Term	130.0	47151	0.560	NC (0.330)	0.189 (0.000)	1.707 (0.000)	0.0d
10 KP-Clay III. LTerm	130.0	68650	0.560	NC (0.330)	0.189 (0.000)	1.707 (0.000)	0.0d
11 Exist. Fill - L.Term	130.0	1200000	0.500	NC (0.490)	0.333 (1.155)	3.000 (3.464)	0.0d
12 Sediment	80.00	36000	0.500	NC (0.490)	1.000 (2.000)	1.000 (1.330)	60.00d
13 Sediment - L.Term	80.00	0 (36000)	0.500	NC (0.490)	0.422 (0.000)	1.581 (0.000)	
14 Granular Fill - AW	130.0	0 (42000)	0.470	NC (0.330)	0.307 (0.000)	3.255 (0.000)	
15 Granular Fill - BW	125.0	0 (15000)	0.500	NC (0.330)	0.333 (0.000)	3.000 (0.000)	
16 Exist. Fill - Broms	130.0	1200000	0.500	NC (0.490)	0.000 (0.000)	0.000 (1.650)	2000d
17 KP - Clay I	130.0	1200000	0.531	NC (0.490)	0.484 (0.968)	0.000 (2.000)	2000d
18 KP - Clay I L.Term	130.0	1200000	0.531	NC (0.490)	0.175 (0.000)	2.770 (0.000)	0.0d
19 E. Fill - Broms L.Te	130.0	0 (1.20E+6)	0.500	NC (0.490)	0.000 (0.000)	1.650 (0.000)	

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---							--- parameters for Kp ---		
Soil friction angle							Soil friction angle		
Wall adhesion coeff.							Wall adhesion coeff.		
Back-fill angle							Back-fill angle		
No.	Description	angle	coeff.	angle	angle	coeff.	angle	coeff.	angle
1	Not defined								
2	Existing Fill	0.00	0.000	0.00	0.00	0.000	0.00	0.000	0.00
3	Clay I	0.00	0.000	0.00	0.00	-0.507	0.00	-0.507	0.00
4	Clay I - L.Term	28.00	0.000	0.00	17.31	0.000	0.00	0.000	0.00
5	Clay IIA	0.00	0.000	0.00	0.00	0.000	0.00	0.000	0.00
6	Clay IIA - L.Term	26.00	0.000	0.00	26.00	0.000	0.00	0.000	0.00
7	KP - Clay IIA	28.06	-0.627	0.00	Incompatible values				
8	KP - Clay III	28.06	-0.627	0.00	Incompatible values				
9	KP-ClayIIA.L.Term	43.01	0.000	0.00	15.14	0.000	0.00	0.000	0.00
10	KP-Clay III.LTerm	43.01	0.000	0.00	15.14	0.000	0.00	0.000	0.00
11	Exist. Fill - L.Term	30.00	0.000	0.00	30.00	0.000	0.00	0.000	0.00
12	Sediment	0.00	0.000	0.00	0.00	-0.507	0.00	-0.507	0.00
13	Sediment - L.Term	24.00	0.000	0.00	13.01	0.000	0.00	0.000	0.00
14	Granular Fill - AW	32.00	0.000	0.00	32.00	0.000	0.00	0.000	0.00
15	Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00	0.000	0.00
16	Exist. Fill - Broms	0.00	0.000	0.00	0.00	0.000	0.00	0.000	0.00
17	KP - Clay I	28.06	-0.627	0.00	Incompatible values				
18	KP - Clay I L.Term	44.60	0.000	0.00	Incompatible values				
19	E. Fill - Broms L.Te	0.00	0.000	0.00	14.20	0.000	0.00	0.000	0.00

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	576.00	576.00

Automatic water pressure balancing at toe of wall : No

Water press. profile no.	Left side				Right side			
	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	Water
	no.		elev.	press.	no.		elev.	press.
		ft	ft	lb/ft2		ft	ft	lb/ft2
1	1	577.00	577.00	0.0	1	576.00	576.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
Elevation of toe of wall = 480.00
Maximum finite element length = 6.00 ft
Youngs modulus of wall E = 4.1760E+09 lb/ft2
Moment of inertia of wall I = 0.22000 ft4/ft run
E.I = 9.1872E+08 lb.ft2/ft run
Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop	Prop	Cross-	Youngs	Free	Inclin	Pre-	Strut	Allow	
no.	Elev.	section	modulus	length	-ation	stress	or	tension	
		area			(degs)	/prop	Anchor	?	L/R
		sq.ft	lb/ft2	ft		lb			
1	584.00	9.30	0.066810	4.176E+09	75.00	0.00	0	Anchor	n/a R

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load no.	Elevation	Horizontal load lb/ft run	Moment load lb.ft/ft run	Moment restraint lb.ft/ft/rad	Partial factor (Category)
1	593.00	2000	0	0	N/A

SURCHARGE LOADS

Surch- arge no.	Elev.	Distance from wall	Length parallel to wall	Width perpend. to wall	Surcharge ----- lb/ft2 ----- Near edge Far edge		Equiv. soil type	Partial factor/ Category
1	591.00	0.00 (L)	1000.00	15.00	500.00	=	N/A	N/A
2	591.00	15.00 (L)	1000.00	84.00	0.00	3600.00	N/A	N/A
3	591.00	99.00 (L)	1000.00	150.00	3600.00	=	N/A	N/A
4	591.00	6.00 (L)	1000.00	15.00	10.00	=	N/A	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Change EI of wall to 8.0771E+08 lb.ft2/ft run From elevation 540.00 to 480.00 Yield moment not defined Reset wall displacements to zero at this stage
2	Excavate to elevation 547.00 on LEFT side
3	Fill to elevation 576.00 on LEFT side with soil type 15
4	Fill to elevation 581.00 on LEFT side with soil type 14
5	Install strut or anchor no.1 at elevation 584.00
6	Fill to elevation 591.00 on LEFT side with soil type 14
7	Excavate to elevation 550.00 on RIGHT side
8	Apply water pressure profile no.1
9	Apply surcharge no.1 at elevation 591.00
10	Apply surcharge no.4 at elevation 591.00
11	Apply load no.1 at elevation 593.00
12	Apply surcharge no.2 at elevation 591.00 No analysis at this stage
13	Apply surcharge no.3 at elevation 591.00
14	Change properties of soil type 12 to soil type 13 No analysis at this stage Ko pressures will not be reset
15	Change properties of soil type 3 to soil type 4 No analysis at this stage Ko pressures will not be reset
16	Change properties of soil type 17 to soil type 18 No analysis at this stage Ko pressures will not be reset
17	Change properties of soil type 7 to soil type 9 No analysis at this stage Ko pressures will not be reset
18	Change properties of soil type 8 to soil type 10 Ko pressures will be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 71.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft

Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Output options		
		Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Change EI of wall to 8.0771E+08lb.ft2/	No	No	No
2	Excav. to elev. 547.00 on LEFT side	No	No	No
3	Fill to elev. 576.00 on LEFT side	No	No	No
4	Fill to elev. 581.00 on LEFT side	No	No	No
5	Install prop no.1 at elev. 584.00	No	No	No
6	Fill to elev. 591.00 on LEFT side	Yes	Yes	Yes
7	Excav. to elev. 550.00 on RIGHT side	No	No	No
8	Apply water pressure profile no.1	No	No	No
9	Apply surcharge no.1 at elev. 591.00	No	No	No
10	Apply surcharge no.4 at elev. 591.00	Yes	Yes	Yes
11	Apply load no.1 at elev. 593.00	Yes	Yes	Yes
12	Apply surcharge no.2 at elev. 591.00	No	No	No
13	Apply surcharge no.3 at elev. 591.00	No	No	No
14	Change soil type 12 to soil type 13	No	No	No
15	Change soil type 3 to soil type 4	No	No	No
16	Change soil type 17 to soil type 18	No	No	No
17	Change soil type 7 to soil type 9	No	No	No
18	Change soil type 8 to soil type 10	No	No	No
*	Summary output	Yes	-	Yes

Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecA-A-1 EmbedmentCheck

Pulliam Dock Wall - Section A - Pipe 54x5/8 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : AJG


|

| Date:15-07-2025

| Checked :

Units: lb, ft

Stage No.18 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : AJG
 Data filename/Run ID: SecA-A-1 EmbedmentCheck |
 Pulliam Dock Wall - Section A - Pipe 54x5/8 & NZ26 | Date:15-07-2025
 Load Case A.1 - SSP Tip El. 540 | Checked :

Units: lb,ft

Stage No. 18 Change properties of soil type 8 to soil type 10
 Ko pressures will be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

				FoS for toe		Toe elev. for		
				elev. = 480.00		FoS = 1.500		
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>	
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>	
			<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>	
18	591.00	550.00	584.00	2.678	n/a	510.20	39.80	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached
 Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
 Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

*** Convergence failure - Out of balance shear force at elevation 480.00
 is 67.415% of the maximum shear force. see Note.

<u>Node</u>	<u>Y</u>	<u>Nett</u>	<u>Wall</u>	<u>Wall</u>	<u>Shear</u>	<u>Bending</u>	<u>Prop</u>	<u>EI of</u>
<u>no.</u>	<u>coord</u>	<u>pressure</u>	<u>disp.</u>	<u>rotation</u>	<u>force</u>	<u>moment</u>	<u>forces</u>	<u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.116	-1.12E-02	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.138	-1.12E-02	2000.0	4000.0		9.18E+08
		488.53	0.138	-1.12E-02	2000.0	4000.0		
3	587.50	786.46	0.178	-1.12E-02	4231.2	14430.9		9.18E+08
4	584.00	432.36	0.217	-1.13E-02	6364.2	34444.4	-31309.2	9.18E+08
		432.36	0.217	-1.13E-02	-24945.0	34444.4		
5	581.00	551.32	0.251	-1.13E-02	-23469.5	-38172.5		9.18E+08
6	577.00	711.58	0.296	-1.10E-02	-20943.7	-127242.2		9.18E+08
7	576.00	795.39	0.307	-1.08E-02	-20190.3	-147812.9		9.18E+08
		857.60	0.307	-1.08E-02	-20190.3	-147812.9		
8	575.00	879.42	0.318	-1.06E-02	-19321.7	-167563.3		9.18E+08
9	569.50	1004.25	0.373	-9.40E-03	-14141.6	-258951.1		9.18E+08
10	564.00	1136.31	0.420	-7.66E-03	-8255.1	-320079.3		9.18E+08
11	558.00	1286.24	0.460	-5.48E-03	-987.4	-348553.0		9.18E+08
12	554.00	1388.39	0.479	-3.98E-03	4361.8	-341496.4		9.18E+08
13	550.00	1491.61	0.492	-2.55E-03	10121.8	-312709.3		9.18E+08
14	547.00	1485.97	0.498	-1.60E-03	14588.2	-274608.4		9.18E+08
		1597.17	0.498	-1.60E-03	14588.2	-274608.4		
15	543.50	1265.10	0.502	-6.78E-04	19597.2	-209827.4		9.18E+08
16	540.00	933.12	0.503	-2.27E-05	23444.0	-134208.9		8.07E+08
		-501.65	0.503	-2.27E-05	23444.0	-134208.9		
17	536.00	-1192.55	0.502	4.28E-04	20055.6	-48179.6		8.07E+08
18	532.00	-1883.60	0.500	5.05E-04	13903.3	17161.7		8.07E+08
		-439.60	0.500	5.05E-04	13903.3	17161.7		
19	528.25	-340.02	0.499	3.14E-04	12441.6	65151.5		8.07E+08
20	524.50	-95.51	0.498	-6.74E-05	11624.9	99399.2		8.07E+08
21	520.75	125.88	0.499	-5.65E-04	11681.9	115286.1		8.07E+08
22	517.00	311.39	0.502	-1.09E-03	12501.8	110873.4		8.07E+08
		-17.56	0.502	-1.09E-03	12501.8	110873.4		

(continued)

Stage No.18 Change properties of soil type 8 to soil type 10

Ko pressures will be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
23	513.50	50.14	0.507	-1.53E-03	12558.8	95696.5		8.07E+08
24	510.00	73.43	0.513	-1.92E-03	12775.0	81195.6		8.07E+08
25	504.00	75.15	0.526	-2.44E-03	13220.8	58766.9		8.07E+08
26	498.00	79.40	0.542	-2.80E-03	13684.4	38806.8		8.07E+08
27	492.00	98.66	0.560	-3.02E-03	14218.6	21454.9		8.07E+08
28	486.00	192.00	0.578	-3.13E-03	15090.6	6745.6		8.07E+08
29	480.00	383.32	0.597	-3.15E-03	16816.6	0.0		---
At elev. 584.00					Prop force = 31309.2 lb/ft run			

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Effective</u> <u>Active</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2	<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	488.53	488.53	4370
3	587.50	0.00	954.67	293.33	3107.07	786.46	786.46	26221
4	584.00	0.00	1407.14	432.36	4579.66	432.36	432.36a	6785
5	581.00	0.00	1794.30	551.32	5839.72	551.32	551.32a	9693
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	13571
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	14540
		62.40	2385.59	795.20	7156.77	795.20	857.60a	5193
8	575.00	124.80	2451.06	817.02	7353.17	817.02	941.82a	5539
9	569.50	468.00	2825.56	941.85	8476.68	941.85	1409.85a	7443
10	564.00	811.20	3221.74	1073.91	9665.22	1073.91	1885.11a	9347
11	558.00	1185.60	3671.52	1223.84	11014.55	1223.84	2409.44a	11424
12	554.00	1435.20	3977.96	1325.99	11933.89	1325.99	2761.19a	12809
13	550.00	1684.80	4287.63	1429.21	12862.88	1429.21	3114.01a	14194
14	547.00	1872.00	4521.15	1507.05	13563.46	1507.05	3379.05a	15232
		1872.00	4521.15	1632.29	8350.57	1632.29	3504.29a	1456
15	543.50	2090.40	4811.81	1737.23	8887.42	1737.23	3827.63a	1456
16	540.00	2308.80	5102.68	1842.24	9424.65	1842.24	4151.04a	1456
		2308.80	5102.68	892.97	14134.42	892.97	3201.77a	39814
17	536.00	2558.40	5434.74	951.08	15054.24	951.08	3509.48a	39814
18	532.00	2808.00	5765.91	1009.03	15971.58	1009.03	3817.03a	39814
		2808.00	5765.91	1089.76	9842.42	1319.03	4127.03	1088
19	528.25	3042.00	6075.20	1148.21	10370.36	1462.22	4504.22	1088
20	524.50	3276.00	6383.05	1206.40	10895.87	1605.90	4881.90	1088
21	520.75	3510.00	6689.29	1264.28	11418.62	1748.99	5258.99	1088
22	517.00	3744.00	6993.75	1321.82	11938.33	1890.69	5634.69	1088
		3744.00	6993.75	1321.82	11938.33	3150.25	6894.25	1584
23	513.50	3962.40	7276.22	1375.21	12420.51	3299.48	7261.88	1584
24	510.00	4180.80	7556.99	1428.27	12899.78	3446.25	7627.05	1584
25	504.00	4555.20	8034.24	1518.47	13714.44	3691.89	8247.09	1584
26	498.00	4929.60	8506.29	1607.69	14520.23	3930.36	8859.96	1584
27	492.00	5304.00	8973.15	1695.93	15317.17	4162.75	9466.75	1584
28	486.00	5678.40	9434.92	1783.20	16105.41	4390.48	10068.88	1584
29	480.00	6052.80	9891.74	1869.54	16885.19	4614.81	10667.61	1584

(continued)


Stage No.18 Change properties of soil type 8 to soil type 10
 Ko pressures will be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u> <u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	575.00	62.40	0.00	0.00	0.00	0.00	62.40	0.0
9	569.50	405.60	0.00	0.00	0.00	0.00	405.60	0.0
10	564.00	748.80	-0.00	0.00	0.00	0.00	748.80	0.0
11	558.00	1123.20	-0.00	0.00	0.00	0.00	1123.20	0.0
12	554.00	1372.80	-0.00	0.00	0.00	0.00	1372.80	0.0
13	550.00	1622.40	-0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	-0.00	0.00	-0.00	-0.00	1622.40	617
14	547.00	1809.60	52.80	22.27	83.48	83.48	1893.08p	3703
		1809.60	52.80	19.06	97.52	97.52	1907.12p	1505
15	543.50	2028.00	289.40	104.48	534.52	534.52	2562.52p	1505
16	540.00	2246.40	526.00	189.90	971.52	971.52	3217.92p	1505
		2246.40	526.00	92.05	1457.02	1457.02	3703.42p	41141
17	536.00	2496.00	796.40	139.37	2206.03	2206.03	4702.03p	41141
18	532.00	2745.60	1066.80	186.69	2955.04	2955.04	5700.64p	41141
		2745.60	1066.80	201.63	1821.03	1821.03	4566.63p	1140
19	528.25	2979.60	1320.30	249.54	2253.76	1864.64	4844.24	1140
20	524.50	3213.60	1573.80	297.45	2686.48	1763.81	4977.41	1140
21	520.75	3447.60	1827.30	345.36	3119.21	1685.51	5133.11	1140
22	517.00	3681.60	2080.81	393.27	3551.94	1641.70	5323.30	1140
		3681.60	2080.81	393.27	3551.94	3230.21	6911.81	1660
23	513.50	3900.00	2317.41	437.99	3955.82	3311.74	7211.74	1660
24	510.00	4118.40	2554.01	482.71	4359.70	3435.22	7553.62	1660
25	504.00	4492.80	2959.62	559.37	5052.07	3679.14	8171.94	1660
26	498.00	4867.20	3365.23	636.03	5744.44	3913.36	8780.56	1660
27	492.00	5241.60	3770.84	712.69	6436.82	4126.49	9368.09	1660
28	486.00	5616.00	4176.45	789.35	7129.20	4260.88	9876.88	1660
29	480.00	5990.40	4582.06	866.01	7821.58	4293.89	10284.29	1660


Note: 3817.03a Soil pressure at active limit
 4566.63p Soil pressure at passive limit

Units: lb, ft

Stage No.18 Change soil type 8 to soil type 10



Stage No.18 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecA-A-1 EmbedmentCheck

Pulliam Dock Wall - Section A - Pipe 54x5/8 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : AJG

|

| Date:15-07-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 480.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
1	575.00	575.00	Cant.	15.734	499.45	***	***	L to R
2	575.00	547.00	Cant.	12.829	499.63	533.51	13.49	R to L
3	576.00	575.00	Cant.	5.334	495.97	537.83	37.17	L to R
4	581.00	575.00	Cant.	3.045	496.02	510.01	64.99	L to R
5	581.00	575.00		No analysis at this stage				
6	591.00	575.00	584.00	2.632	n/a	541.13	33.87	L to R
7	591.00	550.00	584.00	2.568	n/a	538.83	11.17	L to R
8	591.00	550.00	584.00	2.485	n/a	538.45	11.55	L to R
9	591.00	550.00	584.00	2.348	n/a	516.14	33.86	L to R
10	591.00	550.00	584.00	2.344	n/a	516.09	33.91	L to R
11	591.00	550.00	584.00	2.351	n/a	516.25	33.75	L to R
12	591.00	550.00		No analysis at this stage				
13	591.00	550.00	584.00	1.568	n/a	502.45	47.55	L to R
14	591.00	550.00		No analysis at this stage				
15	591.00	550.00		No analysis at this stage				
16	591.00	550.00		No analysis at this stage				
17	591.00	550.00		No analysis at this stage				
18	591.00	550.00	584.00	2.678	n/a	510.20	39.80	L to R

Legend: *** Result not found

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecA-A-1 EmbedmentCheck

Pulliam Dock Wall - Section A - Pipe 54x5/8 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : AJG

|

| Date:15-07-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	593.00	0.203	-0.047	0.0	-0.0	2000.0	0.0
2	591.00	0.199	-0.046	4000.0	-0.0	2000.0	0.0
3	587.50	0.195	-0.043	14430.9	-0.0	4231.2	0.0
4	584.00	0.217	-0.040	34444.4	-0.0	6364.2	-24945.0
5	581.00	0.251	-0.037	0.0	-38172.5	0.0	-23469.5
6	577.00	0.296	-0.034	426.1	-127242.2	319.5	-20943.7
7	576.00	0.307	-0.033	832.2	-147812.9	499.3	-20190.3
8	575.00	0.318	-0.032	1443.3	-167563.3	726.4	-19321.7
9	569.50	0.373	-0.027	8428.0	-258951.1	1643.3	-14141.6
10	564.00	0.420	-0.023	20125.0	-320079.3	3318.6	-8255.1
11	558.00	0.460	-0.018	40377.5	-348553.0	9208.2	-987.4
12	554.00	0.479	-0.014	58491.1	-341496.4	13962.0	-1818.4
13	550.00	0.492	-0.011	81438.2	-312709.3	19222.7	-2957.6
14	547.00	0.498	-0.009	103330.7	-274608.4	23702.0	-3996.8
15	543.50	0.502	-0.007	142646.7	-209827.4	19597.2	-1040.0
16	540.00	0.503	-0.005	172392.5	-134208.9	23444.0	-4021.4
17	536.00	0.502	-0.004	165205.4	-48179.6	20055.6	-5738.6
18	532.00	0.500	-0.003	145854.4	-18585.2	13903.3	-9215.8
19	528.25	0.499	-0.003	125337.7	-8978.5	12441.6	-8295.9
20	524.50	0.498	-0.003	106922.5	-2467.3	11624.9	-6792.9
21	520.75	0.499	-0.003	115286.1	-0.0	11681.9	-4743.8
22	517.00	0.502	-0.003	110873.4	-0.0	12501.8	-3785.7
23	513.50	0.507	-0.002	95696.5	-2363.9	12558.8	-2335.7
24	510.00	0.513	-0.002	81195.6	-8316.1	12775.0	-1268.4
25	504.00	0.526	-0.002	58766.9	-18097.5	16058.4	-270.9
26	498.00	0.542	-0.002	38806.8	-16409.6	17796.3	0.0
27	492.00	0.560	-0.002	21454.9	-8993.1	18291.4	0.0
28	486.00	0.578	-0.002	6745.6	-2329.2	17847.6	0.0
29	480.00	0.597	-0.002	0.0	-0.0	16816.6	-0.0

Summary of results (continued)**Maximum and minimum bending moment and shear force at each stage**

Stage	Bending moment				Shear force			
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	0.0	486.00	-0.0	498.00	0.0	540.00	0.0	593.00
2	758.7	520.75	-37105.5	540.00	2921.7	532.00	-3996.8	547.00
3	30183.9	543.50	-3757.8	504.00	2794.7	547.00	-1607.8	536.00
4	118683.5	543.50	-11313.8	504.00	7511.3	547.00	-5463.1	536.00
5	No calculation at this stage							
6	141061.5	540.00	-68735.1	569.50	15700.3	547.00	-8450.2	584.00
7	158206.8	540.00	-104179.5	564.00	20212.7	547.00	-10807.9	584.00
8	159102.1	540.00	-112698.8	564.00	20785.3	547.00	-11344.1	584.00
9	172392.5	540.00	-136411.1	564.00	22726.2	547.00	-15190.0	584.00
10	169405.5	540.00	-138480.3	564.00	22666.1	547.00	-15291.9	584.00
11	165578.6	540.00	-131106.2	564.00	22179.7	547.00	-15249.2	584.00
12	No calculation at this stage							
13	165205.4	536.00	-163774.1	564.00	23702.0	547.00	-17049.5	584.00
14	No calculation at this stage							
15	No calculation at this stage							
16	No calculation at this stage							
17	No calculation at this stage							
18	115286.1	520.75	-348553.0	558.00	23444.0	540.00	-24945.0	584.00

Maximum and minimum displacement at each stage

Stage	Displacement				
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>Stage description</u>
	ft		ft		
1	0.000	480.00	-0.000	593.00	Change EI of wall to 8.0771E+08lb.ft2/ft run
2	0.000	593.00	-0.047	593.00	Excav. to elev. 547.00 on LEFT side
3	0.037	593.00	0.000	593.00	Fill to elev. 576.00 on LEFT side
4	0.169	593.00	0.000	593.00	Fill to elev. 581.00 on LEFT side
5	No calculation at this stage				Install prop no.1 at elev. 584.00
6	0.182	593.00	0.000	593.00	Fill to elev. 591.00 on LEFT side
7	0.181	593.00	0.000	593.00	Excav. to elev. 550.00 on RIGHT side
8	0.182	593.00	0.000	593.00	Apply water pressure profile no.1
9	0.195	593.00	0.000	593.00	Apply surcharge no.1 at elev. 591.00
10	0.195	593.00	0.000	593.00	Apply surcharge no.4 at elev. 591.00
11	0.203	593.00	0.000	593.00	Apply load no.1 at elev. 593.00
12	No calculation at this stage				Apply surcharge no.2 at elev. 591.00
13	0.200	593.00	0.000	593.00	Apply surcharge no.3 at elev. 591.00
14	No calculation at this stage				Change soil type 12 to soil type 13
15	No calculation at this stage				Change soil type 3 to soil type 4
16	No calculation at this stage				Change soil type 17 to soil type 18
17	No calculation at this stage				Change soil type 7 to soil type 9
18	0.597	480.00	0.000	593.00	Change soil type 8 to soil type 10

Summary of results (continued)

Prop forces at each stage (horizontal components)

Stage	--	Anchor no. 1	---
no.		at elev. 584.00	
		lb/ft run	lb/prop
6		9428.84	87688.23
7		11786.54	109614.79
8		12322.69	114600.99
9		17885.12	166331.63
10		17984.82	167258.82
11		19570.40	182004.70
13		21346.74	198524.70
18		31309.20	291175.60

*** [Convergence errors](#) have occurred in at least one Construction Stage.
The errors are cumulative, and the results of all stages must be inspected for significant out of balance moment or shear at the toe of the wall.

Failure of the iterative procedure to converge to an equilibrium solution may be due to a very high ratio of soil stiffness to wall stiffness. The data should be reviewed to see if realistic values have been specified

[Out of balance shear forces.](#)


Percentage Error	Interpretation
< 2%	Generally acceptable
2% to 4%	Use with caution
> 4%	Should not be used

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: SecA-A-1 EmbedmentCheck
Pulliam Dock Wall - Section A - Pipe 54x5/8 & NZ26
Load Case A.1 - SSP Tip El. 540

| Sheet No.
| Job No. 2201593
| Made by : AJG
|
| Date:15-07-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
WALLAP ANALYSIS: A.1						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	575.00	12 Sediment	12 Sediment
2	547.00	3 Clay I	3 Clay I
3	540.00	17 KP - Clay I	17 KP - Clay I
4	532.00	7 KP - Clay IIA	7 KP - Clay IIA
5	517.00	8 KP - Clay III	8 KP - Clay III

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft3	Eh, lb/ft2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	lb/ft2 (dc/dy)
1 Not defined							
2 Existing Fill	130.0	1200000	0.500	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000u
3 Clay I	130.0	1200000	0.531	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000d
4 Clay I - L. Term	130.0	1200000	0.531	OC (0.490)	0.361 (0.000)	2.770 (0.000)	
5 Clay IIA	130.0	600000	0.561	NC (0.490)	1.000 (2.000)	1.000 (2.000)	1000d
6 Clay IIA - L.Term	130.0	600000	0.561	OC (0.490)	0.390 (0.000)	2.561 (0.000)	
7 KP - Clay IIA	130.0	600000	0.560	NC (0.490)	0.484 (0.968)	0.000 (2.000)	1000d
8 KP - Clay III	130.0	1500000	0.560	NC (0.490)	0.484 (0.968)	0.000 (2.000)	2500d
9 KP-ClayIIA. L.Term	130.0	600000	0.560	NC (0.490)	0.189 (0.000)	2.561 (0.000)	0.0d
10 KP-Clay III. LTerm	130.0	1500000	0.560	NC (0.490)	0.189 (0.000)	2.561 (0.000)	0.0d
11 Exist. Fill - L.Term	130.0	1200000	0.500	NC (0.490)	0.333 (1.155)	3.000 (3.464)	0.0d
12 Sediment	80.00	36000	0.500	NC (0.490)	1.000 (2.000)	1.000 (2.000)	60.00d
13 Sediment - L.Term	80.00	0 (36000)	0.500	NC (0.490)	0.422 (0.000)	2.371 (0.000)	
14 Granular Fill - AW	130.0	0 (42000)	0.470	NC (0.330)	0.307 (0.000)	3.255 (0.000)	
15 Granular Fill - BW	125.0	0 (15000)	0.500	NC (0.330)	0.333 (0.000)	3.000 (0.000)	
16 Exist. Fill - Broms	130.0	1200000	0.500	NC (0.490)	0.000 (0.000)	0.000 (1.650)	2000d
17 KP - Clay I	130.0	1200000	0.531	NC (0.490)	0.484 (0.968)	0.000 (2.000)	2000d
18 KP - Clay I L.Term	130.0	1200000	0.531	NC (0.490)	0.175 (0.000)	2.770 (0.000)	0.0d
19 E. Fill - Broms L.Te	130.0	0 (1.20E+6)	0.500	NC (0.490)	0.000 (0.000)	1.650 (0.000)	

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---							--- parameters for Kp ---		
Soil friction angle							Soil friction angle		
Wall adhesion coeff.							Wall adhesion coeff.		
Back-fill angle							Back-fill angle		
No.	Description	angle	coeff.	angle	angle	coeff.	angle	coeff.	angle
1	Not defined								
2	Existing Fill	0.00	0.000	0.00	0.00	0.000	0.00	0.000	0.00
3	Clay I	0.00	0.000	0.00	0.00	0.000	0.00	0.000	0.00
4	Clay I - L.Term	28.00	0.000	0.00	28.00	0.000	0.00	0.000	0.00
5	Clay IIA	0.00	0.000	0.00	0.00	0.000	0.00	0.000	0.00
6	Clay IIA - L.Term	26.00	0.000	0.00	26.00	0.000	0.00	0.000	0.00
7	KP - Clay IIA	28.06	-0.627	0.00	Incompatible values				
8	KP - Clay III	28.06	-0.627	0.00	Incompatible values				
9	KP-ClayIIA.L.Term	43.01	0.000	0.00	26.00	0.000	0.00		
10	KP-Clay III.LTerm	43.01	0.000	0.00	26.00	0.000	0.00		
11	Exist. Fill - L.Term	30.00	0.000	0.00	30.00	0.000	0.00		
12	Sediment	0.00	0.000	0.00	0.00	0.000	0.00		
13	Sediment - L.Term	24.00	0.000	0.00	24.00	0.000	0.00		
14	Granular Fill - AW	32.00	0.000	0.00	32.00	0.000	0.00		
15	Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00		
16	Exist. Fill - Broms	0.00	0.000	0.00	0.00	0.000	0.00		
17	KP - Clay I	28.06	-0.627	0.00	Incompatible values				
18	KP - Clay I L.Term	44.60	0.000	0.00	Incompatible values				
19	E. Fill - Broms L.Te	0.00	0.000	0.00	14.20	0.000	0.00		

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	576.00	576.00

Automatic water pressure balancing at toe of wall : No

Water press. profile no.	Left side				Right side			
	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	Water
	no.		elev.	press.	no.		elev.	press.
		ft	ft	lb/ft2		ft	ft	lb/ft2
1	1	577.00	577.00	0.0	1	576.00	576.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
Elevation of toe of wall = 509.00
Maximum finite element length = 5.00 ft
Youngs modulus of wall E = 4.1760E+09 lb/ft2
Moment of inertia of wall I = 0.22000 ft4/ft run
E.I = 9.1872E+08 lb.ft2/ft run
Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop	Prop	Cross-	Youngs	Free	Inclin	Pre-	Strut	Allow	
no.	Elev.	section	modulus	length	-ation	stress	or	tension	
		area			(degs)	/prop	Anchor	?	L/R
		sq.ft	lb/ft2	ft		lb			
1	584.00	9.30	0.066810	4.176E+09	75.00	0.00	0	Anchor	n/a R

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load no.	Elevation	Horizontal load lb/ft run	Moment load lb.ft/ft run	Moment restraint lb.ft/ft/rad	Partial factor (Category)
1	593.00	2000	0	0	N/A

SURCHARGE LOADS

Surch- arge no.	Elev.	Distance from wall	Length parallel to wall	Width perpend. to wall	Surcharge ----- lb/ft2 ----- Near edge Far edge		Equiv. soil type	Partial factor/ Category
1	591.00	0.00 (L)	1000.00	15.00	500.00	=	N/A	N/A
2	591.00	15.00 (L)	1000.00	84.00	0.00	3600.00	N/A	N/A
3	591.00	99.00 (L)	1000.00	150.00	3600.00	=	N/A	N/A
4	591.00	6.00 (L)	1000.00	15.00	10.00	=	N/A	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Change EI of wall to 8.0771E+08 lb.ft2/ft run From elevation 540.00 to 509.00 Yield moment not defined Reset wall displacements to zero at this stage
2	Excavate to elevation 547.00 on LEFT side
3	Fill to elevation 576.00 on LEFT side with soil type 15
4	Fill to elevation 581.00 on LEFT side with soil type 14
5	Install strut or anchor no.1 at elevation 584.00
6	Fill to elevation 591.00 on LEFT side with soil type 14
7	Excavate to elevation 550.00 on RIGHT side
8	Apply water pressure profile no.1
9	Apply surcharge no.1 at elevation 591.00
10	Apply surcharge no.4 at elevation 591.00
11	Apply load no.1 at elevation 593.00
12	Apply surcharge no.2 at elevation 591.00 No analysis at this stage
13	Apply surcharge no.3 at elevation 591.00
14	Change properties of soil type 12 to soil type 13 No analysis at this stage Ko pressures will not be reset
15	Change properties of soil type 3 to soil type 4 No analysis at this stage Ko pressures will not be reset
16	Change properties of soil type 17 to soil type 18 No analysis at this stage Ko pressures will not be reset
17	Change properties of soil type 7 to soil type 9 No analysis at this stage Ko pressures will not be reset
18	Change properties of soil type 8 to soil type 10 Ko pressures will be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 71.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft

Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Output options		
		Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Change EI of wall to 8.0771E+08lb.ft2/	No	No	No
2	Excav. to elev. 547.00 on LEFT side	No	No	No
3	Fill to elev. 576.00 on LEFT side	No	No	No
4	Fill to elev. 581.00 on LEFT side	No	No	No
5	Install prop no.1 at elev. 584.00	No	No	No
6	Fill to elev. 591.00 on LEFT side	Yes	Yes	Yes
7	Excav. to elev. 550.00 on RIGHT side	No	No	No
8	Apply water pressure profile no.1	No	No	No
9	Apply surcharge no.1 at elev. 591.00	No	No	No
10	Apply surcharge no.4 at elev. 591.00	Yes	Yes	Yes
11	Apply load no.1 at elev. 593.00	Yes	Yes	Yes
12	Apply surcharge no.2 at elev. 591.00	No	No	No
13	Apply surcharge no.3 at elev. 591.00	No	No	No
14	Change soil type 12 to soil type 13	No	No	No
15	Change soil type 3 to soil type 4	No	No	No
16	Change soil type 17 to soil type 18	No	No	No
17	Change soil type 7 to soil type 9	No	No	No
18	Change soil type 8 to soil type 10	No	No	No
*	Summary output	Yes	-	Yes

Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.6 Fill to elev. 591.00 on LEFT side



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 6 Fill to elevation 591.00 on LEFT side with soil type 14

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
6	591.00	575.00	584.00	3.091	n/a	542.86	32.14	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
1	593.00	0.00	0.162	1.80E-03	0.0	-0.0		9.18E+08
2	591.00	0.00	0.159	1.80E-03	0.0	0.0		9.18E+08
3	587.50	139.80	0.153	1.80E-03	244.7	285.4		9.18E+08
4	584.00	279.61	0.146	1.79E-03	978.6	2283.4	-9381.5	9.18E+08
		279.61	0.146	1.79E-03	-8402.9	2283.4		
5	581.00	399.44	0.141	1.82E-03	-7384.3	-21487.2		9.18E+08
6	577.00	559.21	0.133	1.97E-03	-5467.0	-47402.8		9.18E+08
7	576.00	599.15	0.131	2.03E-03	-4887.8	-52583.5		9.18E+08
		776.52	0.131	2.03E-03	-4887.8	-52583.5		
8	575.00	789.02	0.129	2.09E-03	-4105.1	-57077.9		9.18E+08
		669.02	0.129	2.09E-03	-4105.1	-57077.9		
9	570.00	642.10	0.118	2.43E-03	-827.3	-69013.4		9.18E+08
10	565.00	623.83	0.105	2.79E-03	2337.5	-64397.0		9.18E+08
11	560.00	652.41	0.090	3.09E-03	5528.1	-44456.9		9.18E+08
12	555.00	732.68	0.074	3.23E-03	8990.8	-8375.8		9.18E+08
13	550.00	849.83	0.058	3.13E-03	12947.1	46022.4		9.18E+08
14	547.00	934.90	0.049	2.91E-03	15624.2	89768.4		9.18E+08
		-3538.33	0.049	2.91E-03	15624.2	89768.4		
15	543.50	-2549.18	0.039	2.50E-03	4971.1	126798.3		9.18E+08
16	540.00	-1369.32	0.031	2.01E-03	-1886.3	128154.4		8.07E+08
17	536.00	-459.57	0.025	1.42E-03	-5544.1	110016.6		8.07E+08
18	532.00	7.95	0.020	9.47E-04	-6447.3	84031.4		8.07E+08
		291.29	0.020	9.47E-04	-6447.3	84031.4		
19	528.50	284.68	0.017	6.28E-04	-5439.4	62938.5		8.07E+08
20	525.00	235.38	0.015	3.94E-04	-4529.3	45355.6		8.07E+08
21	521.00	139.97	0.014	2.10E-04	-3778.6	28707.4		8.07E+08
22	517.00	16.52	0.014	1.04E-04	-3465.6	14305.2		8.07E+08
		403.08	0.014	1.04E-04	-3465.6	14305.2		
23	513.00	436.18	0.013	5.98E-05	-1787.1	3662.5		8.07E+08
24	509.00	457.36	0.013	5.07E-05	-0.0	-0.0		---
At elev. 584.00			Prop force = 9381.5 lb/ft run					

(continued)

Stage No.6 Fill to elevation 591.00 on LEFT side with soil type 14

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	0.00	0.00	0.00	683
3	587.50	0.00	455.00	139.80	1480.84	139.80	139.80a	4101
4	584.00	0.00	910.00	279.61	2961.68	279.61	279.61a	8201
5	581.00	0.00	1300.00	399.44	4230.96	399.44	399.44a	11716
6	577.00	0.00	1820.00	559.21	5923.35	559.21	559.21a	16403
7	576.00	0.00	1950.00	599.15	6346.45	599.15	599.15a	17575
		0.00	1950.00	650.00	5850.00	776.52	776.52	6277
8	575.00	62.40	2012.60	670.87	6037.80	789.02	851.42	6695
9	570.00	374.40	2325.60	775.20	6976.80	850.10	1224.50	8787
10	565.00	686.40	2638.60	879.53	7915.80	919.83	1606.23	10880
11	560.00	998.40	2951.60	983.87	8854.80	1012.43	2010.83	12972
12	555.00	1310.40	3264.60	1088.20	9793.80	1138.61	2449.01	15064
13	550.00	1622.40	3577.60	1192.53	10732.80	1302.81	2925.21	17156
14	547.00	1809.60	3765.40	1255.13	11296.20	1418.02	3227.62	18411
		1809.60	3765.40	0.00	7765.40	138.94	1948.54	46003
15	543.50	2028.00	4002.00	2.00	8002.00	354.98	2382.98	46003
16	540.00	2246.40	4238.60	238.60	8238.60	1059.69	3306.09	46003
		2246.40	4238.60	115.48	4000.00	1059.69	3306.09	46003
17	536.00	2496.00	4509.00	246.36	4000.00	1681.98	4177.98	46003
18	532.00	2745.60	4779.40	377.23	4000.00	2006.92	4752.52	46003
		2745.60	4779.40	1345.23	2000.00	1734.53	4480.13	23002
19	528.50	2964.00	5016.00	1459.74	2000.00	1780.25	4744.25	23002
20	525.00	3182.40	5252.60	1574.26	2000.00	1813.13	4995.53	23002
21	521.00	3432.00	5523.00	1705.13	2000.00	1836.36	5268.36	23002
22	517.00	3681.60	5793.40	1836.01	2000.00	1847.80	5529.40	23002
		3681.60	5793.40	384.01	5000.00	2863.80	6545.40	57504
23	513.00	3931.20	6063.80	514.88	5000.00	3027.25	6958.45	57504
24	509.00	4180.80	6334.20	645.75	5000.00	3185.26	7366.06	57504

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	575.00	62.40	0.00	0.00	0.00	0.00	62.40	0.0
		62.40	0.00	0.00	120.00	120.00	182.40p	1569
9	570.00	374.40	88.00	0.00	208.00	208.00	582.40p	1569
10	565.00	686.40	176.00	56.00	296.00	296.00	982.40p	1569
11	560.00	998.40	264.00	144.00	384.00	360.02	1358.42	1569
12	555.00	1310.40	352.00	232.00	472.00	405.93	1716.33	1569
13	550.00	1622.40	440.00	320.00	560.00	452.98	2075.38	1569
14	547.00	1809.60	492.80	372.80	612.80	483.12	2292.72	1569
		1809.60	492.80	0.00	4492.80	3677.27	5486.87	52304
15	543.50	2028.00	729.40	0.00	4729.40	2904.16	4932.16	52304
16	540.00	2246.40	966.00	0.00	4966.00	2429.01	4675.41	52304
		2246.40	966.00	0.00	4000.00	2429.01	4675.41	52304

(continued)

Stage No.6 Fill to elevation 591.00 on LEFT side with soil type 14

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Effective stresses</u> <u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2		
17	536.00	2496.00	1236.40	0.00	4000.00	2141.55	4637.55	52304
18	532.00	2745.60	1506.80	0.00	4000.00	1998.97	4744.57	52304
		2745.60	1506.80	0.00	2000.00	1443.24	4188.84	26152
19	528.50	2964.00	1743.40	0.00	2000.00	1495.57	4459.57	26152
20	525.00	3182.40	1980.00	0.00	2000.00	1577.75	4760.15	26152
21	521.00	3432.00	2250.40	121.19	2000.00	1696.39	5128.39	26152
22	517.00	3681.60	2520.80	252.07	2000.00	1831.28	5512.88	26152
		3681.60	2520.80	0.00	5000.00	2460.72	6142.32	65380
23	513.00	3931.20	2791.20	0.00	5000.00	2591.06	6522.26	65380
24	509.00	4180.80	3061.60	0.00	5000.00	2727.91	6908.71	65380

Note: 599.15a Soil pressure at active limit
982.40p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.6 Fill to elev. 591.00 on LEFT side



Stage No.6 Fill to elev. 591.00 on LEFT side



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.10 Apply surcharge no.4 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 10 Apply surcharge no.4 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
10	591.00	550.00	584.00	2.612	n/a	539.95	10.05	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.176	1.09E-03	0.0	0.0		9.18E+08
2	591.00	0.00	0.174	1.09E-03	0.0	0.0		9.18E+08
		225.26	0.174	1.09E-03	0.0	-0.0		
3	587.50	389.04	0.170	1.09E-03	1075.0	1815.1		9.18E+08
4	584.00	536.77	0.167	1.07E-03	2695.2	8386.6	-17576.1	9.18E+08
		536.77	0.167	1.07E-03	-14880.9	8386.6		
5	581.00	656.20	0.163	1.11E-03	-13091.4	-33580.1		9.18E+08
6	577.00	735.53	0.159	1.35E-03	-10308.0	-80288.8		9.18E+08
7	576.00	790.12	0.157	1.45E-03	-9545.1	-90216.8		9.18E+08
		1048.94	0.157	1.45E-03	-9545.1	-90216.8		
8	575.00	1035.48	0.156	1.55E-03	-8502.9	-99234.1		9.18E+08
9	570.00	1039.23	0.146	2.17E-03	-3316.2	-128692.2		9.18E+08
10	565.00	1078.99	0.134	2.88E-03	1979.4	-131227.6		9.18E+08
11	560.00	1138.10	0.118	3.53E-03	7522.1	-107224.6		9.18E+08
12	555.00	1217.53	0.099	3.97E-03	13411.2	-55126.6		9.18E+08
13	550.00	1315.37	0.079	4.04E-03	19743.4	27277.9		9.18E+08
		1230.32	0.079	4.04E-03	19743.4	27277.9		
14	547.00	1273.62	0.067	3.85E-03	23499.3	93027.0		9.18E+08
		-3990.40	0.067	3.85E-03	23499.3	93027.0		
15	543.50	-3559.82	0.054	3.38E-03	10286.4	154737.4		9.18E+08
16	540.00	-2337.57	0.043	2.76E-03	-34.0	169209.0		8.07E+08
17	536.00	-1077.99	0.034	1.97E-03	-6865.1	150702.7		8.07E+08
18	532.00	-367.98	0.027	1.31E-03	-9757.1	114458.0		8.07E+08
		395.00	0.027	1.31E-03	-9757.1	114458.0		
19	528.50	455.78	0.023	8.89E-04	-8268.2	82399.5		8.07E+08
20	525.00	453.10	0.021	5.89E-04	-6677.7	55948.6		8.07E+08
21	521.00	397.54	0.019	3.70E-04	-4976.4	32428.1		8.07E+08
22	517.00	410.09	0.018	2.52E-04	-3361.1	15324.8		8.07E+08
		301.67	0.018	2.52E-04	-3361.1	15324.8		
23	513.00	423.61	0.017	2.03E-04	-1910.6	4272.2		8.07E+08
24	509.00	531.67	0.016	1.93E-04	-0.0	-0.0		---
At elev. 584.00					Prop force = 17576.1 lb/ft run			

(continued)

Stage No.10 Apply surcharge no.4 at elevation 591.00

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	225.26	225.26	701
3	587.50	0.00	953.04	292.83	3101.75	389.04	389.04	4203
4	584.00	0.00	1395.20	428.69	4540.80	536.77	536.77	8407
5	581.00	0.00	1763.13	541.74	5738.28	656.20	656.20	12009
6	577.00	0.00	2244.06	689.51	7303.48	735.53	735.53	16813
7	576.00	62.40	2301.20	707.06	7489.45	727.72	790.12	18014
		62.40	2301.20	767.07	6903.59	986.54	1048.94	6434
8	575.00	124.80	2353.30	784.43	7059.91	973.08	1097.88	6862
9	570.00	436.80	2615.91	871.97	7847.73	976.83	1413.63	9007
10	565.00	748.80	2885.14	961.71	8655.42	1016.59	1765.39	11152
11	560.00	1060.80	3161.79	1053.93	9485.37	1075.70	2136.50	13296
12	555.00	1372.80	3444.92	1148.31	10334.76	1155.13	2527.93	15441
13	550.00	1684.80	3733.30	1244.43	11199.91	1252.97	2937.77	17585
14	547.00	1872.00	3908.39	1302.80	11725.16	1318.63	3190.63	18872
		1872.00	3908.39	0.00	7908.39	0.00	1872.00a	46957
15	543.50	2090.40	4131.77	131.77	8131.77	131.77	2222.17a	46957
16	540.00	2308.80	4356.65	356.65	8356.65	616.09	2924.89	46957
		2308.80	4356.65	172.62	4000.00	616.09	2924.89	46957
17	536.00	2558.40	4615.21	297.76	4000.00	1351.25	3909.65	46957
18	532.00	2808.00	4875.15	423.57	4000.00	1753.10	4561.10	46957
		2808.00	4875.15	1391.57	2000.00	1656.72	4464.72	23478
19	528.50	3026.40	5103.57	1502.13	2000.00	1720.48	4746.88	23478
20	525.00	3244.80	5332.76	1613.05	2000.00	1764.91	5009.71	23478
21	521.00	3494.40	5595.51	1740.23	2000.00	1797.87	5292.27	23478
22	517.00	3744.00	5859.02	1867.76	2000.00	1919.89	5663.89	23478
		3744.00	5859.02	415.76	5000.00	2686.41	6430.41	58696
23	513.00	3993.60	6123.17	543.62	5000.00	2879.29	6872.89	58696
24	509.00	4243.20	6387.90	671.74	5000.00	3066.36	7309.56	58696

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	575.00	62.40	0.00	0.00	0.00	0.00	62.40	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	555.00	1310.40	0.00	0.00	0.00	0.00	1310.40	0.0
13	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	120.00	85.04	1707.44	2820
14	547.00	1809.60	52.80	0.00	172.80	107.42	1917.02	2820
		1809.60	52.80	0.00	4052.80	4052.80	5862.40p	93997
15	543.50	2028.00	289.40	0.00	4289.40	3753.99	5781.99	93997
16	540.00	2246.40	526.00	0.00	4526.00	3016.07	5262.47	93997
		2246.40	526.00	0.00	4000.00	3016.07	5262.47	93997

(continued)

Stage No.10 Apply surcharge no.4 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
17	536.00	2496.00	796.40	0.00	4000.00	2491.65	4987.65	93997
18	532.00	2745.60	1066.80	0.00	4000.00	2183.48	4929.08	93997
		2745.60	1066.80	0.00	2000.00	1324.12	4069.72	46999
19	528.50	2964.00	1303.40	0.00	2000.00	1327.10	4291.10	46999
20	525.00	3182.40	1540.00	0.00	2000.00	1374.21	4556.61	46999
21	521.00	3432.00	1810.40	0.00	2000.00	1462.72	4894.72	46999
22	517.00	3681.60	2080.81	39.11	2000.00	1572.20	5253.80	46999
		3681.60	2080.81	0.00	5000.00	2447.14	6128.74	117496
23	513.00	3931.20	2351.21	0.00	5000.00	2518.08	6449.28	117496
24	509.00	4180.80	2621.61	0.00	5000.00	2597.09	6777.89	117496

Note: 2222.17a Soil pressure at active limit
5862.40p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB



|

| Date:22-10-2025



| Checked :

Units: lb, ft

Stage No.10 Apply surcharge no.4 at elev. 591.00



Stage No.10 Apply surcharge no.4 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.11 Apply load no.1 at elev. 593.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 11 Apply load no.1 at elevation 593.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
11	591.00	550.00	584.00	2.629	n/a	540.11	9.89	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.184	1.54E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.181	1.54E-03	2000.0	4000.0		9.18E+08
		212.95	0.181	1.54E-03	2000.0	4000.0		
3	587.50	332.05	0.176	1.51E-03	2953.8	12739.7		9.18E+08
4	584.00	453.37	0.170	1.43E-03	4328.2	25537.7	-19090.2	9.18E+08
		453.37	0.170	1.43E-03	-14762.0	25537.7		
5	581.00	569.12	0.166	1.42E-03	-13228.3	-16447.8		9.18E+08
6	577.00	689.51	0.160	1.60E-03	-10711.0	-64523.1		9.18E+08
7	576.00	769.46	0.159	1.67E-03	-9981.5	-74873.0		9.18E+08
		1024.78	0.159	1.67E-03	-9981.5	-74873.0		
8	575.00	1013.57	0.157	1.76E-03	-8962.4	-84338.7		9.18E+08
9	570.00	1030.36	0.147	2.30E-03	-3852.5	-116367.8		9.18E+08
10	565.00	1081.16	0.134	2.95E-03	1426.3	-121696.0		9.18E+08
11	560.00	1145.57	0.117	3.56E-03	6993.1	-100431.4		9.18E+08
12	555.00	1227.63	0.098	3.97E-03	12926.1	-50885.1		9.18E+08
13	550.00	1325.47	0.078	4.03E-03	19308.8	29220.0		9.18E+08
		1241.69	0.078	4.03E-03	19308.8	29220.0		
14	547.00	1283.81	0.066	3.83E-03	23097.1	93716.5		9.18E+08
		-3933.15	0.066	3.83E-03	23097.1	93716.5		
15	543.50	-3516.64	0.054	3.35E-03	10059.9	154369.6		9.18E+08
16	540.00	-2307.82	0.043	2.74E-03	-132.9	168312.7		8.07E+08
17	536.00	-1060.99	0.034	1.95E-03	-6870.5	149648.8		8.07E+08
18	532.00	-360.23	0.027	1.30E-03	-9712.9	113518.6		8.07E+08
		398.87	0.027	1.30E-03	-9712.9	113518.6		
19	528.50	456.92	0.023	8.81E-04	-8215.3	81638.2		8.07E+08
20	525.00	452.53	0.021	5.85E-04	-6623.8	55379.5		8.07E+08
21	521.00	395.95	0.019	3.68E-04	-4926.8	32070.2		8.07E+08
22	517.00	408.07	0.018	2.51E-04	-3318.8	15152.5		8.07E+08
		296.62	0.018	2.51E-04	-3318.8	15152.5		
23	513.00	418.25	0.017	2.03E-04	-1889.0	4228.9		8.07E+08
24	509.00	526.26	0.016	1.93E-04	-0.0	-0.0		---
At elev. 584.00					Prop force =	19090.2 lb/ft run		

(continued)

Stage No.11 Apply load no.1 at elevation 593.00

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	212.95	212.95	1836
3	587.50	0.00	953.04	292.83	3101.75	332.05	332.05	11017
4	584.00	0.00	1395.20	428.69	4540.80	453.37	453.37	22034
5	581.00	0.00	1763.13	541.74	5738.28	569.12	569.12	31477
6	577.00	0.00	2244.06	689.51	7303.48	689.51	689.51a	44068
7	576.00	62.40	2301.20	707.06	7489.45	707.06	769.46a	47215
		62.40	2301.20	767.07	6903.59	962.38	1024.78	16863
8	575.00	124.80	2353.30	784.43	7059.91	951.17	1075.97	17987
9	570.00	436.80	2615.91	871.97	7847.73	967.96	1404.76	23608
10	565.00	748.80	2885.14	961.71	8655.42	1018.76	1767.56	16430
11	560.00	1060.80	3161.79	1053.93	9485.37	1083.17	2143.97	19590
12	555.00	1372.80	3444.92	1148.31	10334.76	1165.23	2538.03	22750
13	550.00	1684.80	3733.30	1244.43	11199.91	1263.07	2947.87	25909
14	547.00	1872.00	3908.39	1302.80	11725.16	1327.76	3199.76	27805
		1872.00	3908.39	0.00	7908.39	21.74	1893.74	66240
15	543.50	2090.40	4131.77	131.77	8131.77	148.17	2238.57	66240
16	540.00	2308.80	4356.65	356.65	8356.65	627.39	2936.19	66240
		2308.80	4356.65	172.62	4000.00	627.39	2936.19	66240
17	536.00	2558.40	4615.21	297.76	4000.00	1357.71	3916.11	66240
18	532.00	2808.00	4875.15	423.57	4000.00	1756.04	4564.04	66240
		2808.00	4875.15	1391.57	2000.00	1658.19	4466.19	33120
19	528.50	3026.40	5103.57	1502.13	2000.00	1720.91	4747.31	33120
20	525.00	3244.80	5332.76	1613.05	2000.00	1764.62	5009.42	42267
21	521.00	3494.40	5595.51	1740.23	2000.00	1797.07	5291.47	42267
22	517.00	3744.00	5859.02	1867.76	2000.00	1918.88	5662.88	42267
		3744.00	5859.02	415.76	5000.00	2683.88	6427.88	105668
23	513.00	3993.60	6123.17	543.62	5000.00	2876.61	6870.21	105668
24	509.00	4243.20	6387.90	671.74	5000.00	3063.66	7306.86	105668

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	575.00	62.40	0.00	0.00	0.00	0.00	62.40	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	555.00	1310.40	0.00	0.00	0.00	0.00	1310.40	0.0
13	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	120.00	83.78	1706.18	3245
14	547.00	1809.60	52.80	0.00	172.80	106.35	1915.95	3245
		1809.60	52.80	0.00	4052.80	4017.30	5826.90	108156
15	543.50	2028.00	289.40	0.00	4289.40	3727.22	5755.22	108156
16	540.00	2246.40	526.00	0.00	4526.00	2997.62	5244.02	108156
		2246.40	526.00	0.00	4000.00	2997.62	5244.02	108156

(continued)

Stage No.11 Apply load no.1 at elevation 593.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
17	536.00	2496.00	796.40	0.00	4000.00	2481.10	4977.10	108156
18	532.00	2745.60	1066.80	0.00	4000.00	2178.67	4924.27	108156
		2745.60	1066.80	0.00	2000.00	1321.72	4067.32	54078
19	528.50	2964.00	1303.40	0.00	2000.00	1326.39	4290.39	54078
20	525.00	3182.40	1540.00	0.00	2000.00	1374.49	4556.89	42267
21	521.00	3432.00	1810.40	0.00	2000.00	1463.52	4895.52	42267
22	517.00	3681.60	2080.81	39.11	2000.00	1573.21	5254.81	42267
		3681.60	2080.81	0.00	5000.00	2449.66	6131.26	105668
23	513.00	3931.20	2351.21	0.00	5000.00	2520.76	6451.96	105668
24	509.00	4180.80	2621.61	0.00	5000.00	2599.80	6780.60	105668

Note: 769.46a Soil pressure at active limit
 123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.11 Apply load no.1 at elev. 593.00



Stage No.11 Apply load no.1 at elev. 593.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.13 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 13 Apply surcharge no.3 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
13	591.00	550.00	584.00	1.845	n/a	514.97	35.03	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.182	8.10E-04	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.180	8.05E-04	2000.0	4000.0		9.18E+08
		224.98	0.180	8.05E-04	2000.0	4000.0		
3	587.50	327.17	0.177	7.73E-04	2966.3	12816.7		9.18E+08
4	584.00	433.77	0.175	7.00E-04	4297.9	25649.7	-20850.2	9.18E+08
		433.77	0.175	7.00E-04	-16552.3	25649.7		
5	581.00	551.32	0.173	6.94E-04	-15074.7	-21839.6		9.18E+08
6	577.00	711.58	0.170	9.10E-04	-12548.9	-77336.8		9.18E+08
7	576.00	795.39	0.169	1.00E-03	-11795.4	-89512.9		9.18E+08
		1053.56	0.169	1.00E-03	-11795.4	-89512.9		
8	575.00	1048.10	0.168	1.10E-03	-10744.6	-100775.8		9.18E+08
9	570.00	1098.76	0.161	1.76E-03	-5377.4	-140964.0		9.18E+08
10	565.00	1190.35	0.150	2.56E-03	345.3	-152692.5		9.18E+08
11	560.00	1302.72	0.135	3.34E-03	6578.0	-135071.9		9.18E+08
12	555.00	1442.14	0.117	3.94E-03	13440.1	-85229.0		9.18E+08
13	550.00	1609.16	0.096	4.17E-03	21068.4	537.2		9.18E+08
		1498.92	0.096	4.17E-03	21068.4	537.2		
14	547.00	1589.48	0.084	4.05E-03	25701.0	71557.6		9.18E+08
		-3469.25	0.084	4.05E-03	25701.0	71557.6		
15	543.50	-3415.19	0.070	3.64E-03	13653.2	143425.9		9.18E+08
16	540.00	-2591.29	0.058	3.04E-03	3141.9	171330.2		8.07E+08
		-2963.01	0.058	3.04E-03	3141.9	171330.2		
17	536.00	-1537.99	0.048	2.22E-03	-5860.1	160720.0		8.07E+08
18	532.00	-678.85	0.041	1.51E-03	-10293.8	125005.4		8.07E+08
		235.94	0.041	1.51E-03	-10293.8	125005.4		
19	528.50	387.30	0.036	1.05E-03	-9203.1	90251.3		8.07E+08
20	525.00	491.49	0.033	7.25E-04	-7665.3	60303.6		8.07E+08
21	521.00	573.46	0.031	4.93E-04	-5535.4	33475.2		8.07E+08
22	517.00	632.91	0.029	3.71E-04	-3122.6	15637.7		8.07E+08
		169.80	0.029	3.71E-04	-3122.6	15637.7		
23	513.00	403.63	0.028	3.21E-04	-1975.8	4640.2		8.07E+08
24	509.00	584.25	0.026	3.10E-04	-0.0	0.0		---
At elev. 584.00					Prop force = 20850.2 lb/ft run			

(continued)

Stage No.13 Apply surcharge no.3 at elevation 591.00

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	224.98	224.98	15747
3	587.50	0.00	954.67	293.33	3107.07	327.17	327.17	3584
4	584.00	0.00	1407.14	432.36	4579.66	433.77	433.77	7168
5	581.00	0.00	1794.30	551.32	5839.72	551.32	551.32a	10240
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	14336
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	15360
		62.40	2385.59	795.20	7156.77	991.16	1053.56	5486
8	575.00	124.80	2451.06	817.02	7353.17	985.70	1110.50	5851
9	570.00	436.80	2790.54	930.18	8371.61	1036.36	1473.16	7680
10	565.00	748.80	3148.36	1049.45	9445.08	1127.95	1876.75	9508
11	560.00	1060.80	3520.02	1173.34	10560.06	1240.32	2301.12	11337
12	555.00	1372.80	3900.99	1300.33	11702.97	1379.74	2752.54	13165
13	550.00	1684.80	4287.63	1429.21	12862.88	1546.76	3231.56	14994
14	547.00	1872.00	4521.15	1507.05	13563.46	1659.08	3531.08	16091
		1872.00	4521.15	521.15	8521.15	521.15	2393.15a	41383
15	543.50	2090.40	4811.81	811.81	8811.81	811.81	2902.21a	41383
16	540.00	2308.80	5102.68	1102.68	9102.68	1102.68	3411.48a	41383
		2308.80	5102.68	533.70	4000.00	730.97	3039.77	41383
17	536.00	2558.40	5434.74	694.42	4000.00	1582.79	4141.19	41383
18	532.00	2808.00	5765.91	854.70	4000.00	2092.30	4900.30	41383
		2808.00	5765.91	1822.70	2000.00	1822.70	4630.70a	20691
19	528.50	3026.40	6054.62	1962.44	2000.00	1962.44	4988.84a	20691
20	525.00	3244.80	6342.10	2101.57	2000.00	2101.57	5346.37a	20691
21	521.00	3494.40	6668.93	2259.76	2000.00	2259.76	5754.16a	20691
22	517.00	3744.00	6993.75	2416.98	2000.00	2416.98	6160.98a	20691
		3744.00	6993.75	964.98	5000.00	3240.20	6984.20	51729
23	513.00	3993.60	7316.43	1121.15	5000.00	3516.06	7509.66	51729
24	509.00	4243.20	7636.89	1276.25	5000.00	3747.09	7990.29	51729

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	575.00	62.40	0.00	0.00	0.00	0.00	62.40	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	555.00	1310.40	0.00	0.00	0.00	0.00	1310.40	0.0
13	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	120.00	110.24	1732.64	1466
14	547.00	1809.60	52.80	0.00	172.80	132.00	1941.60	1466
		1809.60	52.80	0.00	4052.80	4052.80	5862.40p	48875
15	543.50	2028.00	289.40	0.00	4289.40	4289.40	6317.40p	48875
16	540.00	2246.40	526.00	0.00	4526.00	3756.37	6002.77	48875
		2246.40	526.00	0.00	4000.00	3756.37	6002.77	48875

(continued)

Stage No.13 Apply surcharge no.3 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
17	536.00	2496.00	796.40	0.00	4000.00	3183.18	5679.18	48875
18	532.00	2745.60	1066.80	0.00	4000.00	2833.55	5579.15	48875
		2745.60	1066.80	0.00	2000.00	1649.16	4394.76	24437
19	528.50	2964.00	1303.40	0.00	2000.00	1637.54	4601.54	24437
20	525.00	3182.40	1540.00	0.00	2000.00	1672.49	4854.89	24437
21	521.00	3432.00	1810.40	0.00	2000.00	1748.70	5180.70	24437
22	517.00	3681.60	2080.81	39.11	2000.00	1846.46	5528.06	24437
		3681.60	2080.81	0.00	5000.00	3132.80	6814.40	61093
23	513.00	3931.20	2351.21	0.00	5000.00	3174.83	7106.03	61093
24	509.00	4180.80	2621.61	0.00	5000.00	3225.24	7406.04	61093

Note: 6160.98a Soil pressure at active limit
6317.40p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.13 Apply surcharge no.3 at elev. 591.00



Stage No.13 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.18 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 18 Change properties of soil type 8 to soil type 10
Ko pressures will be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
18	591.00	550.00	584.00	2.213	n/a	519.14	30.86	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
1	593.00	0.00	0.158	-3.61E-03	2000.0	-0.0	2000.0	9.18E+08
2	591.00	0.00	0.166	-3.61E-03	2000.0	4000.0		9.18E+08
		312.01	0.166	-3.61E-03	2000.0	4000.0		
3	587.50	323.73	0.178	-3.64E-03	3112.5	13349.8		9.18E+08
4	584.00	432.36	0.191	-3.72E-03	4435.7	26670.7	-27373.1	9.18E+08
		432.36	0.191	-3.72E-03	-22937.4	26670.7		
5	581.00	551.32	0.202	-3.70E-03	-21461.9	-39978.2		9.18E+08
6	577.00	711.58	0.217	-3.35E-03	-18936.1	-121024.3		9.18E+08
7	576.00	795.39	0.220	-3.21E-03	-18182.7	-139587.7		9.18E+08
		857.60	0.220	-3.21E-03	-18182.7	-139587.7		
8	575.00	879.42	0.223	-3.05E-03	-17314.1	-157331.3		9.18E+08
9	570.00	992.58	0.236	-1.99E-03	-12634.2	-232215.4		9.18E+08
10	565.00	1111.85	0.242	-5.92E-04	-7373.1	-281439.4		9.18E+08
11	560.00	1235.74	0.241	9.98E-04	-1504.1	-303344.0		9.18E+08
12	555.00	1362.73	0.232	2.62E-03	4992.1	-294800.6		9.18E+08
13	550.00	1491.61	0.215	4.11E-03	12127.9	-252426.1		9.18E+08
14	547.00	1444.25	0.202	4.86E-03	16531.7	-208466.8		9.18E+08
		1548.44	0.202	4.86E-03	16531.7	-208466.8		
15	543.50	998.04	0.184	5.53E-03	20988.1	-139191.7		9.18E+08
16	540.00	447.71	0.163	5.91E-03	23518.1	-61390.1		8.07E+08
		-501.65	0.163	5.91E-03	23518.1	-61390.1		
17	536.00	-1192.55	0.140	6.00E-03	20129.7	23553.0		8.07E+08
18	532.00	-1883.60	0.116	5.72E-03	13977.4	90427.3		8.07E+08
		-1579.92	0.116	5.72E-03	13977.4	90427.3		
19	528.50	-2131.29	0.097	5.25E-03	7482.8	128065.6		8.07E+08
20	525.00	-1916.17	0.079	4.66E-03	399.7	144390.9		8.07E+08
21	521.00	-1186.64	0.062	3.97E-03	-5805.9	132969.0		8.07E+08
22	517.00	-400.72	0.047	3.39E-03	-8980.6	99968.5		8.07E+08
		-1737.98	0.047	3.39E-03	-8980.6	99968.5		
23	513.00	-5.80	0.035	3.02E-03	-12468.2	50022.9		8.07E+08
24	509.00	6239.90	0.023	2.90E-03	-0.0	-0.0		---
At elev. 584.00				Prop force = 27373.1 lb/ft run				

(continued)

Stage No.18 Change properties of soil type 8 to soil type 10
 Ko pressures will be reset

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press.	Vertic -al	Active limit	Passive limit	Earth pressure		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	312.01	312.01	5937
3	587.50	0.00	954.67	293.33	3107.07	323.73	323.73	4199
4	584.00	0.00	1407.14	432.36	4579.66	432.36	432.36a	8398
5	581.00	0.00	1794.30	551.32	5839.72	551.32	551.32a	11997
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	16796
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	17995
		62.40	2385.59	795.20	7156.77	795.20	857.60a	6427
8	575.00	124.80	2451.06	817.02	7353.17	817.02	941.82a	6855
9	570.00	436.80	2790.54	930.18	8371.61	930.18	1366.98a	8998
10	565.00	748.80	3148.36	1049.45	9445.08	1049.45	1798.25a	11140
11	560.00	1060.80	3520.02	1173.34	10560.06	1173.34	2234.14a	13282
12	555.00	1372.80	3900.99	1300.33	11702.97	1300.33	2673.13a	15425
13	550.00	1684.80	4287.63	1429.21	12862.88	1429.21	3114.01a	17567
14	547.00	1872.00	4521.15	1507.05	13563.46	1507.05	3379.05a	18852
		1872.00	4521.15	1632.29	12522.81	1632.29	3504.29a	46916
15	543.50	2090.40	4811.81	1737.23	13327.89	1737.23	3827.63a	46916
16	540.00	2308.80	5102.68	1842.24	14133.53	1842.24	4151.04a	46916
		2308.80	5102.68	892.97	14134.42	892.97	3201.77a	46916
17	536.00	2558.40	5434.74	951.08	15054.24	951.08	3509.48a	46916
18	532.00	2808.00	5765.91	1009.03	15971.58	1009.03	3817.03a	46916
		2808.00	5765.91	1089.76	14766.51	1089.76	3897.76a	23458
19	528.50	3026.40	6054.62	1144.32	15505.88	1144.32	4170.72a	23458
20	525.00	3244.80	6342.10	1198.66	16242.11	1198.66	4443.46a	23458
21	521.00	3494.40	6668.93	1260.43	17079.12	1521.77	5016.17	23458
22	517.00	3744.00	6993.75	1321.82	17911.00	1983.59	5727.59	23458
		3744.00	6993.75	1321.82	17911.00	2833.03	6577.03	58645
23	513.00	3993.60	7316.43	1382.81	18737.39	3681.87	7675.47	58645
24	509.00	4243.20	7636.89	1443.37	19558.07	6839.70	11082.90	746608

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press.	Vertic -al	Active limit	Passive limit	Earth pressure		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	575.00	62.40	0.00	0.00	0.00	0.00	62.40	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	555.00	1310.40	0.00	0.00	0.00	0.00	1310.40	0.0
13	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	0.00	0.00	1622.40	975
14	547.00	1809.60	52.80	22.27	125.20	125.20	1934.80p	5848
		1809.60	52.80	19.06	146.25	146.25	1955.85p	64979
15	543.50	2028.00	289.40	104.48	801.59	801.59	2829.59p	64979

(continued)

Stage No.18 Change properties of soil type 8 to soil type 10

Ko pressures will be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u> <u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
16	540.00	2246.40	526.00	189.90	1456.93	1456.93	3703.33p	64979
		2246.40	526.00	92.05	1457.02	1457.02	3703.42p	64979
17	536.00	2496.00	796.40	139.37	2206.03	2206.03	4702.03p	64979
18	532.00	2745.60	1066.80	186.69	2955.04	2955.04	5700.64p	64979
		2745.60	1066.80	201.63	2732.08	2732.08	5477.68p	32490
19	528.50	2964.00	1303.40	246.34	3338.01	3338.01	6302.01p	32490
20	525.00	3182.40	1540.00	291.06	3943.95	3177.23	6359.63	32490
21	521.00	3432.00	1810.40	342.17	4636.45	2770.82	6202.82	32490
22	517.00	3681.60	2080.81	393.27	5328.95	2446.71	6128.31	32490
		3681.60	2080.81	393.27	5328.95	4633.41	8315.01	81224
23	513.00	3931.20	2351.21	444.38	6021.45	3750.07	7681.27	81224
24	509.00	4180.80	2621.61	495.48	6713.95	662.20	4843.00	746608

Note: 4443.46a Soil pressure at active limit
6302.01p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.18 Change soil type 8 to soil type 10



Stage No.18 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
1	575.00	575.00	Cant.	14.193	516.43	***	***	L to R
2	575.00	547.00	Cant.	10.729	516.80	535.96	11.04	R to L
3	576.00	575.00	Cant.	5.303	513.72	***	***	L to R
4	581.00	575.00	Cant.	2.888	514.84	518.91	56.09	L to R
5	581.00	575.00		No analysis at this stage				
6	591.00	575.00	584.00	3.091	n/a	542.86	32.14	L to R
7	591.00	550.00	584.00	2.941	n/a	541.05	8.95	L to R
8	591.00	550.00	584.00	2.829	n/a	540.72	9.28	L to R
9	591.00	550.00	584.00	2.616	n/a	539.97	10.03	L to R
10	591.00	550.00	584.00	2.612	n/a	539.95	10.05	L to R
11	591.00	550.00	584.00	2.629	n/a	540.11	9.89	L to R
12	591.00	550.00		No analysis at this stage				
13	591.00	550.00	584.00	1.845	n/a	514.97	35.03	L to R
14	591.00	550.00		No analysis at this stage				
15	591.00	550.00		No analysis at this stage				
16	591.00	550.00		No analysis at this stage				
17	591.00	550.00		No analysis at this stage				
18	591.00	550.00	584.00	2.213	n/a	519.14	30.86	L to R

Legend: *** Result not found

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	593.00	0.184	-0.047	0.0	-0.0	2000.0	0.0
2	591.00	0.181	-0.046	4000.0	-0.0	2000.0	0.0
3	587.50	0.178	-0.043	13349.8	-0.0	3112.5	0.0
4	584.00	0.191	-0.040	26670.7	-0.0	4435.7	-22937.4
5	581.00	0.202	-0.037	0.0	-39978.2	0.0	-21461.9
6	577.00	0.217	-0.034	426.1	-121024.3	319.5	-18936.1
7	576.00	0.220	-0.033	832.2	-139587.7	499.3	-18182.7
8	575.00	0.223	-0.032	1443.3	-157331.3	726.4	-17314.1
9	570.00	0.236	-0.028	6554.1	-232215.4	1354.9	-12634.2
10	565.00	0.242	-0.023	15680.3	-281439.4	2337.5	-7373.1
11	560.00	0.241	-0.019	28966.3	-303344.0	7522.1	-1504.1
12	555.00	0.232	-0.015	48416.5	-294800.6	13440.1	-1580.0
13	550.00	0.215	-0.011	75375.7	-252426.1	21068.4	-2960.0
14	547.00	0.202	-0.009	96788.1	-208466.8	25701.0	-3999.2
15	543.50	0.184	-0.007	154737.4	-139191.7	20988.1	-1044.7
16	540.00	0.163	-0.005	171330.2	-61390.1	23518.1	-4364.3
17	536.00	0.140	-0.004	160720.0	-29647.3	20129.7	-6870.5
18	532.00	0.116	-0.003	125005.4	-18603.8	13977.4	-10293.8
19	528.50	0.097	-0.003	128065.6	-9440.8	7482.8	-9203.1
20	525.00	0.079	-0.003	144390.9	-7973.3	1461.7	-7665.3
21	521.00	0.062	-0.003	132969.0	-8898.9	526.5	-5805.9
22	517.00	0.047	-0.003	99968.5	-4964.4	1468.3	-8980.6
23	513.00	0.035	-0.002	50022.9	-1003.8	607.8	-12468.2
24	509.00	0.026	-0.002	0.0	-0.0	0.0	-0.0

Summary of results (continued)**Maximum and minimum bending moment and shear force at each stage**

Stage	Bending moment				Shear force			
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	0.0	540.00	-0.0	513.00	0.0	540.00	-0.0	570.00
2	1289.8	517.00	-37212.2	540.00	2949.7	532.00	-3999.2	547.00
3	30293.6	543.50	-8898.9	521.00	2866.9	547.00	-3161.7	532.00
4	112213.8	543.50	-0.0	581.00	7384.6	547.00	-7569.3	532.00
5	No calculation at this stage							
6	128154.4	540.00	-69013.4	570.00	15624.2	547.00	-8402.9	584.00
7	146427.8	540.00	-102544.1	565.00	20456.5	547.00	-10638.6	584.00
8	149872.1	540.00	-109240.1	565.00	21132.2	547.00	-11094.9	584.00
9	168976.7	540.00	-130805.8	565.00	23460.2	547.00	-14837.0	584.00
10	169209.0	540.00	-131227.6	565.00	23499.3	547.00	-14880.9	584.00
11	168312.7	540.00	-121696.0	565.00	23097.1	547.00	-14762.0	584.00
12	No calculation at this stage							
13	171330.2	540.00	-152692.5	565.00	25701.0	547.00	-16552.3	584.00
14	No calculation at this stage							
15	No calculation at this stage							
16	No calculation at this stage							
17	No calculation at this stage							
18	144390.9	525.00	-303344.0	560.00	23518.1	540.00	-22937.4	584.00

Maximum and minimum displacement at each stage

Stage	Displacement				
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>Stage description</u>
	ft		ft		
1	0.000	593.00	-0.000	536.00	Change EI of wall to 8.0771E+08lb.ft ² /ft run
2	0.000	593.00	-0.047	593.00	Excav. to elev. 547.00 on LEFT side
3	0.029	593.00	0.000	593.00	Fill to elev. 576.00 on LEFT side
4	0.149	593.00	0.000	593.00	Fill to elev. 581.00 on LEFT side
5	No calculation at this stage				Install prop no.1 at elev. 584.00
6	0.162	593.00	0.000	593.00	Fill to elev. 591.00 on LEFT side
7	0.163	593.00	0.000	593.00	Excav. to elev. 550.00 on RIGHT side
8	0.163	593.00	0.000	593.00	Apply water pressure profile no.1
9	0.176	593.00	0.000	593.00	Apply surcharge no.1 at elev. 591.00
10	0.176	593.00	0.000	593.00	Apply surcharge no.4 at elev. 591.00
11	0.184	593.00	0.000	593.00	Apply load no.1 at elev. 593.00
12	No calculation at this stage				Apply surcharge no.2 at elev. 591.00
13	0.182	593.00	0.000	593.00	Apply surcharge no.3 at elev. 591.00
14	No calculation at this stage				Change soil type 12 to soil type 13
15	No calculation at this stage				Change soil type 3 to soil type 4
16	No calculation at this stage				Change soil type 17 to soil type 18
17	No calculation at this stage				Change soil type 7 to soil type 9
18	0.242	565.00	0.000	593.00	Change soil type 8 to soil type 10

Run ID. 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Date:22-10-2025

| Checked :

Summary of results (continued)

Prop forces at each stage (horizontal components)

Stage -- Anchor no. 1 ---
no. at elev. 584.00
lb/ft run lb/prop
6 9381.48 87247.73
7 11617.26 108040.49
8 12073.50 112283.57
9 17529.57 163025.04
10 17576.08 163457.54
11 19090.24 177539.23
13 20850.24 193907.23
18 27373.14 254570.23

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecA-A.1

Pulliam Dock Wall - Section A - Pipe 54x11/16 & NZ26

Load Case A.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
WALLAP ANALYSIS: B.1 – EMBEDMENT CHECK						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecB-B-1 EmbedmentCheck

Pulliam Dock Wall - Section B - P54x0.625 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:15-07-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	584.00	2 Existing Fill	2 Existing Fill
2	577.00	3 Clay I	3 Clay I
3	554.00	5 Clay IIA	5 Clay IIA
4	540.00	7 KP - Clay IIA	7 KP - Clay IIA
5	535.00	8 KP-Clay III	8 KP-Clay III

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description	lb/ft3	Eh, lb/ft2	Ko	NC/OC	Ka	Kp	lb/ft2
(Datum elev.)		(dEh/dy)	(dKo/dy)	(Nu)	(Kac)	(Kpc)	(dc/dy)
1 Not defined							
2 Existing ..	130.0	1200000	0.500	NC	1.000	1.000	2000u
(584.00)		(15000)		(0.490)	(2.000)	(2.000)	
3 Clay I	130.0	1200000	0.531	NC	1.000	1.000	2000d
				(0.490)	(2.000)	(2.000)	
4 Clay I - L.	130.0	0	0.531	NC	0.361	2.770	
Term		(43889)		(0.490)	(0.000)	(0.000)	
5 Clay IIA	130.0	600000	0.561	NC	1.000	1.000	1000d
				(0.490)	(2.000)	(1.330)	
6 Clay IIA -	130.0	47151	0.561	OC	0.390	1.707	
L.Term				(0.490)	(0.000)	(0.000)	
7 KP - Clay	130.0	600000	0.561	NC	0.484	0.000	1000d
IIA				(0.490)	(0.968)	(1.330)	
8 KP-Clay III	130.0	1500000	0.561	NC	0.484	0.000	2500d
				(0.490)	(0.968)	(1.330)	
9 KP-ClayIIA.	130.0	47151	0.561	OC	0.189	1.707	
L.Term				(0.490)	(0.000)	(0.000)	
10 KP-Clay III.	130.0	68650	0.561	OC	0.189	1.707	
LTerm				(0.490)	(0.000)	(0.000)	
11 Exist. Fi..	130.0	1200000	0.500	NC	0.333	3.000	0.0d
(584.00)		(15000)		(0.490)	(1.155)	(3.464)	
12 Granular	125.0	0	0.500	NC	0.333	3.000	
Fill - BW		(15000)		(0.330)	(0.000)	(0.000)	
13 Granular	130.0	0	0.470	NC	0.307	3.255	
Fill - AW		(42000)		(0.330)	(0.000)	(0.000)	

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---				--- parameters for Kp ---		
Soil	Wall	Back-		Soil	Wall	Back-
friction	adhesion	fill		friction	adhesion	fill
angle	coeff.	angle		angle	coeff.	angle
1 Not defined						
2 Existing Fill	0.00	0.000	0.00	0.00	0.000	0.00
3 Clay I	0.00	0.000	0.00	0.00	0.000	0.00
4 Clay I - L.Term	28.00	0.000	0.00	28.00	0.000	0.00
5 Clay IIA	0.00	0.000	0.00	0.00	-0.507	0.00
6 Clay IIA - L.Term	26.00	0.000	0.00	15.14	0.000	0.00
7 KP - Clay IIA	28.20	-0.622	0.00	Incompatible values		
8 KP-Clay III	28.20	-0.622	0.00	Incompatible values		
9 KP-ClayIIA.L.Term	43.01	0.000	0.00	15.14	0.000	0.00
10 KP-Clay III.LTerm	42.90	0.000	0.00	23.35	-0.384	0.00
11 Exist. Fill - L.Term	30.00	0.000	0.00	30.00	0.000	0.00
12 Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00
13 Granular Fill - AW	32.00	0.000	0.00	32.00	0.000	0.00

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	576.00	576.00

Automatic water pressure balancing at toe of wall : No

Water		Left side			Right side			
press.	-----				-----			
profile	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	
no.	no.		elev.	press.	no.		elev.	
		ft	ft	lb/ft2		ft	ft	
							lb/ft2	
1	1	577.00	577.00	0.0	1	576.00	576.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
 Elevation of toe of wall = 490.00
 Maximum finite element length = 6.00 ft
 Youngs modulus of wall E = 4.1760E+09 lb/ft2
 Moment of inertia of wall I = 0.22000 ft4/ft run
 E.I = 9.1872E+08 lb.ft2/ft run
 Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop	Prop	Cross-	Youngs	Free	Inclin	Pre-	Strut	Allow	
no.	Elev.	section	modulus	length	-ation	stress	or	tension	
		area			(degs)	/prop	Anchor	?	L/R
		sq.ft	lb/ft2	ft		lb			
1	584.00	9.30	0.066810	4.176E+09	75.00	0.00	0	Anchor	n/a R

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load	Horizontal	Moment	Moment	Partial
no.	Elevation	load	load	factor
		lb/ft run	lb.ft/ft run	lb.ft/ft/rad (Category)
1	593.00	2000	0	0
				N/A

SURCHARGE LOADS

Surch	Distance	Length	Width	Surcharge		Equiv.	Partial
-arge	from	parallel	perpend.	-----	lb/ft2 -----	soil	factor/
no.	Elev.	wall	to wall	Near edge	Far edge	type	Category
1	591.00	0.00 (L)	1000.00	15.00	500.00	=	N/A
2	591.00	15.00 (L)	1000.00	84.00	0.00	3600.00	N/A
3	591.00	99.00 (L)	1000.00	150.00	3600.00	=	N/A
4	591.00	6.00 (L)	1000.00	15.00	10.00	=	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Change EI of wall to 8.0771E+08 lb.ft2/ft run From elevation 540.00 to 490.00 Yield moment not defined Reset wall displacements to zero at this stage
2	Install strut or anchor no.1 at elevation 584.00
3	Fill to elevation 591.00 on LEFT side with soil type 13
4	Excavate to elevation 550.00 on RIGHT side
5	Apply water pressure profile no.1
6	Apply surcharge no.4 at elevation 591.00
7	Apply surcharge no.1 at elevation 591.00
8	Apply surcharge no.2 at elevation 591.00 No analysis at this stage
9	Apply surcharge no.3 at elevation 591.00
10	Apply load no.1 at elevation 593.00
11	Change properties of soil type 2 to soil type 11 No analysis at this stage Ko pressures will not be reset
12	Change properties of soil type 3 to soil type 4 No analysis at this stage Ko pressures will not be reset
13	Change properties of soil type 5 to soil type 6 No analysis at this stage Ko pressures will not be reset
14	Change properties of soil type 7 to soil type 9 No analysis at this stage Ko pressures will not be reset
15	Change properties of soil type 8 to soil type 10 Ko pressures will not be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 69.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 500.00 ft

Distance to rigid boundary on Right side = 500.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Output options		
		Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Change EI of wall to 8.0771E+08lb.ft2/	No	No	No
2	Install prop no.1 at elev. 584.00	No	No	No
3	Fill to elev. 591.00 on LEFT side	Yes	Yes	Yes
4	Excav. to elev. 550.00 on RIGHT side	No	No	No
5	Apply water pressure profile no.1	No	No	No
6	Apply surcharge no.4 at elev. 591.00	Yes	Yes	Yes
7	Apply surcharge no.1 at elev. 591.00	No	No	No
8	Apply surcharge no.2 at elev. 591.00	No	No	No
9	Apply surcharge no.3 at elev. 591.00	No	No	No
10	Apply load no.1 at elev. 593.00	Yes	Yes	Yes
11	Change soil type 2 to soil type 11	No	No	No
12	Change soil type 3 to soil type 4	No	No	No
13	Change soil type 5 to soil type 6	No	No	No
14	Change soil type 7 to soil type 9	No	No	No
15	Change soil type 8 to soil type 10	No	No	No
*	Summary output	Yes	-	Yes

Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecB-B-1 EmbedmentCheck

Pulliam Dock Wall - Section B - P54x0.625 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593


| Made by : EQB

| Date:15-07-2025

| Checked :

Units: lb, ft

Stage No.15 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : EQB
 Data filename/Run ID: SecB-B-1_EmbedmentCheck |
 Pulliam Dock Wall - Section B - P54x0.625 & NZ26 | Date:15-07-2025
 Load Case B.1 - SSP EL. 540 | Checked :

Units: lb,ft

Stage No. 15 Change properties of soil type 8 to soil type 10
 Ko pressures will not be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe		Toe elev. for			
			elev. = 490.00		FoS = 1.500			
Stage	Ground level	Prop	Factor	Moment	Toe	Wall	Direction	
No.	Act.	Pass.	of	at equilib.	elev.	Penetr	of	
			Safety	at elev.		-ation	failure	
15	591.00	550.00	584.00	2.314	n/a	509.14	40.86	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached
 Open Tension Crack analysis - No

Rigid boundaries: Left side 500.00 from wall
 Right side 500.00 from wall

*** Wall displacements reset to zero at stage 1

*** Convergence failure - Out of balance shear force at elevation 490.00
 is 5.363% of the maximum shear force. see Note.

Node	Y	Nett	Wall	Wall	Shear	Bending	Prop	EI of
no.	coord	pressure	disp.	rotation	force	moment	forces	wall
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	-0.025	-1.28E-02	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.000	-1.28E-02	2000.0	4000.0		9.18E+08
		403.44	0.000	-1.28E-02	2000.0	4000.0		
3	587.50	293.08	0.046	-1.29E-02	3218.9	13783.8		9.18E+08
4	584.00	431.99	0.091	-1.30E-02	4487.8	27524.4	-36399.8	9.18E+08
		469.05	0.091	-1.30E-02	-31912.0	27524.4		
5	580.50	619.68	0.136	-1.29E-02	-30006.7	-80416.6		9.18E+08
6	577.00	771.97	0.181	-1.24E-02	-27571.3	-180692.5		9.18E+08
		836.12	0.181	-1.24E-02	-27571.3	-180692.5		
7	576.00	923.68	0.193	-1.21E-02	-26691.4	-207831.3		9.18E+08
8	570.00	1080.71	0.261	-1.03E-02	-20678.3	-350411.8		9.18E+08
9	564.00	1247.22	0.316	-7.74E-03	-13694.5	-456046.3		9.18E+08
10	559.00	1391.22	0.348	-5.11E-03	-7098.4	-508347.1		9.18E+08
11	554.00	1538.29	0.367	-2.30E-03	225.4	-525798.3		9.18E+08
		1685.28	0.367	-2.30E-03	225.4	-525798.3		
12	550.00	2008.03	0.372	-4.59E-05	7612.0	-510521.4		9.18E+08
13	545.00	1849.06	0.365	2.54E-03	17254.8	-441574.7		9.18E+08
14	540.00	1703.00	0.347	4.64E-03	26134.9	-331866.1		8.07E+08
		0.39	0.347	4.64E-03	26134.9	-331866.1		
15	535.00	-346.30	0.319	6.32E-03	25270.1	-207878.1		8.07E+08
		-598.27	0.319	6.32E-03	25270.1	-207878.1		
16	531.50	-947.42	0.296	7.05E-03	22565.2	-129544.9		8.07E+08
17	528.00	-1296.77	0.270	7.46E-03	18637.8	-62572.5		8.07E+08
18	522.00	-1442.55	0.225	7.64E-03	10419.9	14997.7		8.07E+08
19	516.00	-628.07	0.179	7.43E-03	4208.0	41505.7		8.07E+08
20	510.00	-315.87	0.136	7.11E-03	1376.2	44176.3		8.07E+08
21	504.00	-204.15	0.094	6.82E-03	-183.8	34739.7		8.07E+08
22	498.00	-33.29	0.054	6.62E-03	-896.2	19528.8		8.07E+08

(continued)

Stage No.15 Change properties of soil type 8 to soil type 10

Ko pressures will not be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
23	494.00	117.41	0.027	6.55E-03	-727.9	8813.9		8.07E+08
24	490.00	1102.29	0.001	6.52E-03	1711.5	0.0		---
At elev. 584.00		Prop force = 36399.8 lb/ft run						

LEFT side								
Effective stresses								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2	<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.50	1627.50	403.44	403.44	14089
3	587.50	0.00	954.67	293.08	3107.46	293.08	293.08a	3824
4	584.00	0.00	1407.14	431.99	4580.24	431.99	431.99a	7647
		0.00	1407.14	469.05	4221.42	469.05	469.05a	43783
5	580.50	0.00	1859.04	619.68	5577.11	619.68	619.68a	45699
6	577.00	0.00	2315.91	771.97	6947.73	771.97	771.97a	47615
		0.00	2315.91	836.12	6414.67	836.12	836.12a	22419
7	576.00	62.40	2385.59	861.28	6607.67	861.28	923.68a	24020
8	570.00	436.80	2820.54	1018.31	7812.40	1018.31	1455.11a	33628
9	564.00	811.20	3281.74	1184.82	9089.85	1184.82	1996.02a	43236
10	559.00	1123.20	3680.60	1328.82	10194.62	1328.82	2452.02a	51243
11	554.00	1435.20	4087.96	1475.89	11322.95	1475.89	2911.09a	59250
		1435.20	4087.96	1596.19	6978.15	1622.88	3058.08	1720
12	550.00	1684.80	4417.63	1724.91	7540.89	1945.63	3630.43	1720
13	545.00	1996.80	4832.19	1886.78	8248.55	2363.63	4360.43	1720
14	540.00	2308.80	5247.68	2049.02	8957.79	2794.53	5103.33	1720
		2308.80	5247.68	991.81	8957.79	1091.92	3400.72	1720
15	535.00	2620.80	5662.64	1070.24	9666.13	1322.20	3943.00	1720
		2620.80	5662.64	1070.24	9666.13	1070.24	3691.04a	2505
16	531.50	2839.20	5952.23	1124.97	10160.45	1124.97	3964.17a	2505
17	528.00	3057.60	6240.77	1179.50	10652.99	1179.50	4237.10a	2505
18	522.00	3432.00	6732.40	1272.42	11492.21	1723.82	5155.82	2505
19	516.00	3806.40	7219.63	1364.51	12323.90	2330.64	6137.04	2505
20	510.00	4180.80	7701.99	1455.68	13147.29	2607.15	6787.95	2505
21	504.00	4555.20	8179.24	1545.88	13961.96	2702.69	7257.89	2505
22	498.00	4929.60	8651.29	1635.09	14767.75	2790.79	7720.39	2505
23	494.00	5179.20	8963.10	1694.03	15300.02	2871.25	8050.45	16782
24	490.00	5428.80	9272.63	1752.53	15828.39	3300.03	8728.83	16782

RIGHT side								
Effective stresses								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2	<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
9	564.00	748.80	0.00	0.00	0.00	0.00	748.80	0.0
10	559.00	1060.80	0.00	0.00	0.00	0.00	1060.80	0.0

(continued)

Stage No.15 Change properties of soil type 8 to soil type 10
 Ko pressures will not be reset

		RIGHT side					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Effective stresses</u> <u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2		
11	554.00	1372.80	0.00	0.00	0.00	0.00	1372.80	0.0
12	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	0.00	0.00	1622.40	2101
13	545.00	1934.40	338.00	131.98	576.97	576.97	2511.37p	2101
14	540.00	2246.40	676.00	263.95	1153.93	1153.93	3400.33p	2101
		2246.40	676.00	127.76	1153.93	1153.93	3400.33p	2101
15	535.00	2558.40	1014.00	191.65	1730.90	1730.90	4289.30p	2101
		2558.40	1014.00	191.65	1730.90	1730.90	4289.30p	3058
16	531.50	2776.80	1250.61	236.36	2134.79	2134.79	4911.59p	3058
17	528.00	2995.20	1487.21	281.08	2538.67	2538.67	5533.87p	3058
18	522.00	3369.60	1892.83	357.74	3231.05	3228.78	6598.38	3058
19	516.00	3744.00	2298.45	434.41	3923.45	3021.10	6765.10	3058
20	510.00	4118.40	2704.08	511.07	4615.86	2985.43	7103.83	3058
21	504.00	4492.80	3109.72	587.74	5308.28	2969.24	7462.04	3058
22	498.00	4867.20	3515.37	664.40	6000.73	2886.47	7753.67	3058
23	494.00	5116.80	3785.81	715.52	6462.37	2816.23	7933.03	16782
24	490.00	5366.40	4056.26	766.63	6924.03	2260.15	7626.55	16782

Note: 4237.10a Soil pressure at active limit
 5533.87p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecB-B-1 EmbedmentCheck

Pulliam Dock Wall - Section B - P54x0.625 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593


| Made by : EQB

| Date:15-07-2025


| Checked :

Units: lb, ft

Stage No.15 Change soil type 8 to soil type 10



Stage No.15 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecB-B-1 EmbedmentCheck

Pulliam Dock Wall - Section B - P54x0.625 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:15-07-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe elev. = 490.00		Toe elev. for FoS = 1.500			
<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u>	<u>Pass.</u>	<u>Prop</u> <u>Elev.</u>	<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u> <u>of equilib.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	<u>Direction</u> <u>of</u> <u>failure</u>
1	584.00	584.00	---	<u>Conditions not suitable for FoS calc.</u>				
2	584.00	584.00		No analysis at this stage				
3	591.00	584.00	584.00	<u>Conditions not suitable for FoS calc.</u>				
4	591.00	550.00	584.00	3.343	n/a	529.34	20.66	L to R
5	591.00	550.00	584.00	3.209	n/a	528.90	21.10	L to R
6	591.00	550.00	584.00	3.204	n/a	528.89	21.11	L to R
7	591.00	550.00	584.00	2.969	n/a	***	***	L to R
8	591.00	550.00		No analysis at this stage				
9	591.00	550.00	584.00	1.870	n/a	520.67	29.33	L to R
10	591.00	550.00	584.00	1.876	n/a	520.93	29.07	L to R
11	591.00	550.00		No analysis at this stage				
12	591.00	550.00		No analysis at this stage				
13	591.00	550.00		No analysis at this stage				
14	591.00	550.00		No analysis at this stage				
15	591.00	550.00	584.00	2.314	n/a	509.14	40.86	L to R

Legend: *** Result not found

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecB-B-1 EmbedmentCheck

Pulliam Dock Wall - Section B - P54x0.625 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:15-07-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 500.00 from wall

Right side 500.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	593.00	0.008	-0.025	0.0	-0.0	2000.0	0.0
2	591.00	0.012	-0.000	4000.0	-0.0	2000.0	0.0
3	587.50	0.046	-0.000	13783.8	0.0	3218.9	0.0
4	584.00	0.091	-0.000	27524.4	0.0	4639.0	-31912.0
5	580.50	0.136	0.000	2470.6	-80416.6	0.0	-30006.7
6	577.00	0.181	0.000	1224.0	-180692.5	777.7	-27571.3
7	576.00	0.193	0.000	1959.1	-207831.3	692.8	-26691.4
8	570.00	0.261	0.000	4594.0	-350411.8	183.1	-20678.3
9	564.00	0.316	0.000	4156.0	-456046.3	0.0	-13694.5
10	559.00	0.348	0.000	1051.8	-508347.1	0.0	-7098.4
11	554.00	0.367	0.000	0.0	-525798.3	225.4	-5173.4
12	550.00	0.372	0.000	0.0	-510521.4	7612.0	-806.6
13	545.00	0.365	0.000	0.0	-441574.7	17254.8	0.0
14	540.00	0.347	0.000	0.0	-331866.1	26134.9	0.0
15	535.00	0.319	0.000	26087.7	-207878.1	25270.1	0.0
16	531.50	0.296	0.000	71794.0	-129544.9	22565.2	0.0
17	528.00	0.270	0.000	91464.5	-62572.5	18637.8	0.0
18	522.00	0.225	0.000	78436.5	-1274.0	10419.9	-3554.6
19	516.00	0.179	0.000	49549.4	-1052.6	4208.0	-4316.6
20	510.00	0.136	0.000	44176.3	0.0	1376.2	-2965.7
21	504.00	0.094	0.000	34739.7	0.0	192.4	-1666.0
22	498.00	0.054	0.000	19528.8	0.0	906.6	-896.2
23	494.00	0.029	0.000	8813.9	0.0	1239.1	-727.9
24	490.00	0.029	-0.000	0.0	-0.0	1711.5	-0.0

Summary of results (continued)**Maximum and minimum bending moment and shear force at each stage**

Stage	Bending moment				Shear force			
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	0.0	504.00	-0.0	545.00	0.0	580.50	-0.0	490.00
2	No calculation at this stage							
3	4594.0	570.00	-11473.0	545.00	1356.4	540.00	-1584.7	554.00
4	47282.3	528.00	-106962.1	550.00	11393.7	535.00	-4651.9	584.00
5	50664.6	528.00	-110012.5	554.00	11606.7	535.00	-5013.3	584.00
6	50789.7	528.00	-110207.4	554.00	11625.4	535.00	-5028.0	584.00
7	59839.2	528.00	-120203.0	554.00	12618.7	535.00	-6285.9	584.00
8	No calculation at this stage							
9	91464.5	528.00	-174929.5	550.00	18701.3	535.00	-7062.4	584.00
10	90231.2	528.00	-171950.8	550.00	19320.7	535.00	-7102.4	584.00
11	No calculation at this stage							
12	No calculation at this stage							
13	No calculation at this stage							
14	No calculation at this stage							
15	44176.3	510.00	-525798.3	554.00	26134.9	540.00	-31912.0	584.00

Maximum and minimum displacement at each stage

Stage	Displacement				Stage description
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	
	ft		ft		
1	0.000	490.00	-0.000	593.00	Change EI of wall to 8.0771E+08lb.ft2/ft run
2	No calculation at this stage				Install prop no.1 at elev. 584.00
3	0.008	550.00	-0.000	490.00	Fill to elev. 591.00 on LEFT side
4	0.054	554.00	-0.002	593.00	Excav. to elev. 550.00 on RIGHT side
5	0.056	554.00	-0.002	593.00	Apply water pressure profile no.1
6	0.056	554.00	-0.002	593.00	Apply surcharge no.4 at elev. 591.00
7	0.062	554.00	0.000	593.00	Apply surcharge no.1 at elev. 591.00
8	No calculation at this stage				Apply surcharge no.2 at elev. 591.00
9	0.085	554.00	-0.000	593.00	Apply surcharge no.3 at elev. 591.00
10	0.084	554.00	0.000	593.00	Apply load no.1 at elev. 593.00
11	No calculation at this stage				Change soil type 2 to soil type 11
12	No calculation at this stage				Change soil type 3 to soil type 4
13	No calculation at this stage				Change soil type 5 to soil type 6
14	No calculation at this stage				Change soil type 7 to soil type 9
15	0.372	550.00	-0.025	593.00	Change soil type 8 to soil type 10

Prop forces at each stage (horizontal components)

Stage -- Anchor no. 1 --
no. at elev. 584.00

	lb/ft run	lb/prop
3	2738.58	25468.80
4	5849.97	54404.69
5	6190.18	57568.65
6	6209.52	57748.53
7	9187.20	85440.95
9	10085.02	93790.73
10	11741.38	109194.87
15	36399.77	338517.87

*** Convergence errors have occurred in at least one Construction Stage.

The errors are cumulative, and the results of all stages must be inspected for significant out of balance moment or shear at the toe of the wall.

Failure of the iterative procedure to converge to an equilibrium solution may be due to a very high ratio of soil stiffness to wall stiffness. The data should be reviewed to see if realistic values have been specified

Out of balance shear forces.


<u>Percentage Error</u>	<u>Interpretation</u>
< 2%	Generally acceptable
2% to 4%	Use with caution
> 4%	Should not be used

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: SecB-B-1_EmbedmentCheck
Pulliam Dock Wall - Section B - P54x0.625 & NZ26
Load Case B.1 - SSP EL. 540

| Sheet No.
| Job No. 2201593
| Made by : EQB
|
| Date:15-07-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
WALLAP ANALYSIS: B.1						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Left side	Soil types	Right side
1	584.00	2 Existing Fill	2	Existing Fill
2	577.00	3 Clay I	3	Clay I
3	554.00	5 Clay IIA	5	Clay IIA
4	540.00	7 KP - Clay IIA	7	KP - Clay IIA
5	535.00	8 KP-Clay III	8	KP-Clay III

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol. state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft3	Eh, lb/ft2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	lb/ft2 (dc/dy)
1 Not defined							
2 Existing .. (584.00)	130.0	1200000 (15000)	0.500	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000u
3 Clay I	130.0	1200000	0.531	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000d
4 Clay I - L. Term	130.0	0 (43889)	0.531	NC (0.490)	0.361 (0.000)	2.770 (0.000)	
5 Clay IIA	130.0	600000	0.561	NC (0.490)	1.000 (2.000)	1.000 (2.000)	1000d
6 Clay IIA - L.Term	130.0	47151	0.561	OC (0.490)	0.390 (0.000)	2.561 (0.000)	
7 KP - Clay IIA	130.0	600000	0.561	NC (0.490)	0.484 (0.968)	0.000 (2.000)	1000d
8 KP-Clay III	130.0	1500000	0.561	NC (0.490)	0.484 (0.968)	0.000 (2.000)	2500d
9 KP-ClayIIA. L.Term	130.0	47151	0.561	OC (0.490)	0.189 (0.000)	2.561 (0.000)	
10 KP-Clay III. LTerm	130.0	68650	0.561	OC (0.490)	0.189 (0.000)	2.561 (0.000)	
11 Exist. Fi.. (584.00)	130.0	1200000 (15000)	0.500	NC (0.490)	0.333 (1.155)	3.000 (3.464)	0.0d
12 Granular Fill - BW	125.0	0 (15000)	0.500	NC (0.330)	0.333 (0.000)	3.000 (0.000)	
13 Granular Fill - AW	130.0	0 (42000)	0.470	NC (0.330)	0.307 (0.000)	3.255 (0.000)	

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---				--- parameters for Kp ---			
Soil	Wall	Back-		Soil	Wall	Back-	
friction	adhesion	fill		friction	adhesion	fill	
angle	coeff.	angle		angle	coeff.	angle	
1 Not defined							
2 Existing Fill	0.00	0.000	0.00	0.00	0.000	0.00	
3 Clay I	0.00	0.000	0.00	0.00	0.000	0.00	
4 Clay I - L.Term	28.00	0.000	0.00	28.00	0.000	0.00	
5 Clay IIA	0.00	0.000	0.00	0.00	0.000	0.00	
6 Clay IIA - L.Term	26.00	0.000	0.00	25.99	0.000	0.00	
7 KP - Clay IIA	28.20	-0.622	0.00	Incompatible values			
8 KP-Clay III	28.20	-0.622	0.00	Incompatible values			
9 KP-ClayIIA.L.Term	43.01	0.000	0.00	25.99	0.000	0.00	
10 KP-Clay III.LTerm	42.90	0.000	0.00	Incompatible values			
11 Exist. Fill - L.Term	30.00	0.000	0.00	30.00	0.000	0.00	
12 Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00	
13 Granular Fill - AW	32.00	0.000	0.00	32.00	0.000	0.00	

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	576.00	576.00

Automatic water pressure balancing at toe of wall : No

Water		Left side			Right side			
press.	-----				-----			
profile	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	
no.	no.		elev.	press.	no.		elev.	
		ft	ft	lb/ft2		ft	ft	
							lb/ft2	
1	1	577.00	577.00	0.0	1	576.00	576.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
 Elevation of toe of wall = 509.00
 Maximum finite element length = 5.00 ft
 Youngs modulus of wall E = 4.1760E+09 lb/ft2
 Moment of inertia of wall I = 0.22000 ft4/ft run
 E.I = 9.1872E+08 lb.ft2/ft run
 Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop	Prop	Cross-	Youngs	Free	Inclin	Pre-	Strut	Allow	
no.	Elev.	section	modulus	length	-ation	stress	or	tension	
		area			(degs)	/prop	Anchor	?	L/R
		sq.ft	lb/ft2	ft		lb			
1	584.00	9.30	0.066810	4.176E+09	75.00	0.00	0	Anchor	n/a R

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load	Horizontal	Moment	Moment	Partial
no.	Elevation	load	load	factor
		lb/ft run	lb.ft/ft run	lb.ft/ft/rad (Category)
1	593.00	2000	0	0
				N/A

SURCHARGE LOADS

Surch	Distance	Length	Width	Surcharge		Equiv.	Partial
-arge	from	parallel	perpend.	-----	lb/ft2 -----	soil	factor/
no.	Elev.	wall	to wall	Near edge	Far edge	type	Category
1	591.00	0.00 (L)	1000.00	15.00	500.00	=	N/A
2	591.00	15.00 (L)	1000.00	84.00	0.00	3600.00	N/A
3	591.00	99.00 (L)	1000.00	150.00	3600.00	=	N/A
4	591.00	6.00 (L)	1000.00	15.00	10.00	=	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Change EI of wall to 8.0771E+08 lb.ft2/ft run From elevation 540.00 to 509.00 Yield moment not defined Reset wall displacements to zero at this stage
2	Install strut or anchor no.1 at elevation 584.00
3	Fill to elevation 591.00 on LEFT side with soil type 13
4	Excavate to elevation 550.00 on RIGHT side
5	Apply water pressure profile no.1
6	Apply surcharge no.4 at elevation 591.00
7	Apply load no.1 at elevation 593.00
8	Apply surcharge no.1 at elevation 591.00
9	Apply surcharge no.2 at elevation 591.00 No analysis at this stage
10	Apply surcharge no.3 at elevation 591.00
11	Change properties of soil type 2 to soil type 11 No analysis at this stage Ko pressures will not be reset
12	Change properties of soil type 3 to soil type 4 No analysis at this stage Ko pressures will not be reset
13	Change properties of soil type 5 to soil type 6 No analysis at this stage Ko pressures will not be reset
14	Change properties of soil type 7 to soil type 9 No analysis at this stage Ko pressures will not be reset
15	Change properties of soil type 8 to soil type 10 Ko pressures will not be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 69.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 500.00 ft

Distance to rigid boundary on Right side = 500.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Output options		
		Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Change EI of wall to 8.0771E+08lb.ft2/	No	No	No
2	Install prop no.1 at elev. 584.00	No	No	No
3	Fill to elev. 591.00 on LEFT side	Yes	Yes	Yes
4	Excav. to elev. 550.00 on RIGHT side	No	No	No
5	Apply water pressure profile no.1	No	No	No
6	Apply surcharge no.4 at elev. 591.00	Yes	Yes	Yes
7	Apply load no.1 at elev. 593.00	Yes	Yes	Yes
8	Apply surcharge no.1 at elev. 591.00	No	No	No
9	Apply surcharge no.2 at elev. 591.00	No	No	No
10	Apply surcharge no.3 at elev. 591.00	Yes	Yes	Yes
11	Change soil type 2 to soil type 11	No	No	No
12	Change soil type 3 to soil type 4	No	No	No
13	Change soil type 5 to soil type 6	No	No	No
14	Change soil type 7 to soil type 9	No	No	No
15	Change soil type 8 to soil type 10	Yes	Yes	Yes
*	Summary output	Yes	-	Yes

Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593


| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.3 Fill to elev. 591.00 on LEFT side



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 3 Fill to elevation 591.00 on LEFT side with soil type 13

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

				FoS for toe elev. = 509.00		Toe elev. for FoS = 1.500		
<u>Stage</u>	<u>Ground level</u>		<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>
3	591.00	584.00	584.00	Conditions not suitable for FoS calc.				

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 500.00 from wall

Right side 500.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.007	2.66E-05	0.0	0.0		9.18E+08
2	591.00	0.00	0.007	2.66E-05	0.0	-0.0		9.18E+08
3	587.50	189.48	0.007	2.57E-05	331.6	436.6		9.18E+08
4	584.00	379.51	0.007	1.88E-05	1327.3	3194.3	-2799.3	9.18E+08
		335.99	0.007	1.88E-05	-1472.0	3194.3		
5	580.50	315.30	0.007	1.25E-05	-332.2	100.3		9.18E+08
6	577.00	294.09	0.007	1.07E-05	734.2	868.8		9.18E+08
		-83.14	0.007	1.07E-05	734.2	868.8		
7	576.00	-82.31	0.007	9.42E-06	651.5	1561.4		9.18E+08
8	573.00	-80.83	0.007	1.74E-06	406.8	3145.5		9.18E+08
9	570.00	-81.78	0.007	-9.92E-06	162.9	4002.1		9.18E+08
10	565.00	-90.24	0.007	-3.11E-05	-267.2	3794.1		9.18E+08
11	560.00	-106.33	0.007	-4.50E-05	-758.6	1330.3		9.18E+08
12	557.00	-117.59	0.007	-4.49E-05	-1094.5	-1424.0		9.18E+08
13	554.00	-127.56	0.007	-3.40E-05	-1462.2	-5236.5		9.18E+08
		205.13	0.007	-3.40E-05	-1462.2	-5236.5		
14	550.00	201.91	0.008	-2.09E-06	-648.1	-9444.2		9.18E+08
15	545.00	206.88	0.007	5.12E-05	373.9	-10160.9		9.18E+08
16	540.00	289.44	0.007	9.52E-05	1614.7	-6020.5		8.07E+08
		-142.75	0.007	9.52E-05	1614.7	-6020.5		
17	535.00	-131.84	0.006	1.13E-04	928.2	268.5		8.07E+08
		-154.96	0.006	1.13E-04	928.2	268.5		
18	530.00	-98.85	0.006	1.03E-04	293.7	2972.5		8.07E+08
19	525.00	-50.86	0.005	8.39E-05	-80.6	3205.3		8.07E+08
20	520.00	-12.36	0.005	6.73E-05	-238.6	2166.7		8.07E+08
21	515.00	19.42	0.005	5.80E-05	-221.0	819.0		8.07E+08
22	512.00	36.92	0.005	5.60E-05	-136.5	243.4		8.07E+08
23	509.00	54.08	0.004	5.56E-05	-0.0	-0.0		---
At elev. 584.00					Prop force =	2799.3 lb/ft run		

(continued)

Stage No.3 Fill to elevation 591.00 on LEFT side with soil type 13

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	0.00	0.00	0.00	574
3	587.50	0.00	455.00	139.68	1481.03	189.48	189.48	3443
4	584.00	0.00	910.00	279.37	2962.05	379.51	379.51	6886
		Total>	910.00	0.00	4910.00	625.70	625.70	40625
5	580.50	Total>	1365.00	0.00	5365.00	842.95	842.95	42402
6	577.00	Total>	1820.00	0.00	5820.00	1059.94	1059.94	44180
		0.00	1820.00	0.00	5820.00	685.91	685.91	40625
7	576.00	0.00	1950.00	0.00	5950.00	755.35	755.35	40625
8	573.00	187.20	2152.80	0.00	6152.80	863.77	1050.97	40625
9	570.00	374.40	2355.60	0.00	6355.60	970.99	1345.39	40625
10	565.00	686.40	2693.60	0.00	6693.60	1146.28	1832.68	40625
11	560.00	998.40	3031.60	0.00	7031.60	1317.79	2316.19	40625
12	557.00	1185.60	3234.40	0.00	7234.40	1419.90	2605.50	40625
13	554.00	1372.80	3437.20	0.00	7437.20	1522.64	2895.44	40625
		1372.80	3437.20	1437.20	5437.20	1777.01	3149.81	20313
14	550.00	1622.40	3707.60	1707.60	5707.60	1927.12	3549.52	20313
15	545.00	1934.40	4045.60	2045.60	6045.60	2119.20	4053.60	20313
16	540.00	2246.40	4383.60	2383.60	6383.60	2383.60	4630.00a	20313
		2246.40	4383.60	1153.66	2000.00	1857.25	4103.65	20313
17	535.00	2558.40	4721.60	1317.25	2000.00	1868.16	4426.56	20313
		2558.40	4721.60	0.00	5000.00	2319.21	4877.61	50781
18	530.00	2870.40	5059.60	28.85	5000.00	2536.63	5407.03	50781
19	525.00	3182.40	5397.60	192.44	5000.00	2750.01	5932.41	50781
20	520.00	3494.40	5735.60	356.03	5000.00	2958.70	6453.10	50781
21	515.00	3806.40	6073.60	519.62	5000.00	3164.05	6970.45	50781
22	512.00	3993.60	6276.40	617.78	5000.00	3286.49	7280.09	50781
23	509.00	4180.80	6479.20	715.93	5000.00	3408.76	7589.56	50781

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		Total>	0.00	0.00	4000.00	289.71	289.71	41397
5	580.50	Total>	455.00	0.00	4455.00	527.65	527.65	43208
6	577.00	Total>	910.00	0.00	4910.00	765.85	765.85	45020
		0.00	910.00	0.00	4910.00	769.05	769.05	41397
7	576.00	0.00	1040.00	0.00	5040.00	837.66	837.66	41397
8	573.00	187.20	1242.80	0.00	5242.80	944.60	1131.80	41397
9	570.00	374.40	1445.60	0.00	5445.60	1052.77	1427.17	41397
10	565.00	686.40	1783.60	0.00	5783.60	1236.52	1922.92	41397
11	560.00	998.40	2121.60	0.00	6121.60	1424.11	2422.51	41397
12	557.00	1185.60	2324.40	0.00	6324.40	1537.48	2723.08	41397
13	554.00	1372.80	2527.20	0.00	6527.20	1650.20	3023.00	41397
		1372.80	2527.20	527.20	4527.20	1571.89	2944.69	20699
14	550.00	1622.40	2797.60	797.60	4797.60	1725.21	3347.61	20699
15	545.00	1934.40	3135.60	1135.60	5135.60	1912.31	3846.71	20699
16	540.00	2246.40	3473.60	1473.60	5473.60	2094.16	4340.56	20699
		2246.40	3473.60	713.22	2000.00	2000.00	4246.40p	20699

(continued)

Stage No.3 Fill to elevation 591.00 on LEFT side with soil type 13

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
17	535.00	2558.40	3811.60	876.81	2000.00	2000.00	4558.40p	20699
		2558.40	3811.60	0.00	5000.00	2474.18	5032.58	51747
18	530.00	2870.40	4149.60	0.00	5000.00	2635.47	5505.87	51747
19	525.00	3182.40	4487.60	0.00	5000.00	2800.87	5983.27	51747
20	520.00	3494.40	4825.60	0.00	5000.00	2971.06	6465.46	51747
21	515.00	3806.40	5163.60	79.18	5000.00	3144.64	6951.04	51747
22	512.00	3993.60	5366.40	177.34	5000.00	3249.58	7243.18	51747
23	509.00	4180.80	5569.20	275.49	5000.00	3354.69	7535.49	51747

Note: 4630.00a Soil pressure at active limit

4558.40p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.3 Fill to elev. 591.00 on LEFT side



Stage No.3 Fill to elev. 591.00 on LEFT side



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593


| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.6 Apply surcharge no.4 at elev. 591.00



GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : EQB
 Data filename/Run ID: 25-10.22_SecB-B.1 |
 Pulliam Dock Wall - Section B - P54x11/16 & NZ26 | Date:22-10-2025
 Load Case B.1 - SSP EL. 540 | Checked :

Units: lb,ft

Stage No. 6 Apply surcharge no.4 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

				FoS for toe		Toe elev. for		
				elev. = 509.00		FoS = 1.500		
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>		<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>
6	591.00	550.00	584.00	4.926	n/a	***	***	L to R

Legend: *** Result not found

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached
 Open Tension Crack analysis - No

Rigid boundaries: Left side 500.00 from wall
 Right side 500.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u>	<u>Y</u>	<u>Nett</u>	<u>Wall</u>	<u>Wall</u>	<u>Shear</u>	<u>Bending</u>	<u>Prop</u>	<u>EI of</u>
<u>no.</u>	<u>coord</u>	<u>pressure</u>	<u>disp.</u>	<u>rotation</u>	<u>force</u>	<u>moment</u>	<u>forces</u>	<u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	-0.002	-1.93E-03	0.0	-0.0		9.18E+08
2	591.00	0.00	0.002	-1.93E-03	0.0	-0.0		9.18E+08
3	587.50	183.61	0.009	-1.93E-03	321.3	437.8		9.18E+08
4	584.00	312.96	0.015	-1.94E-03	1190.3	3127.0	-6153.9	9.18E+08
		239.81	0.015	-1.94E-03	-4963.6	3127.0		
5	580.50	113.14	0.022	-1.92E-03	-4345.9	-12288.2		9.18E+08
6	577.00	0.92	0.029	-1.85E-03	-4146.3	-26420.5		9.18E+08
		1.20	0.029	-1.85E-03	-4146.3	-26420.5		
7	576.00	63.45	0.031	-1.81E-03	-4114.0	-30555.9		9.18E+08
8	573.00	63.38	0.036	-1.70E-03	-3923.8	-42614.3		9.18E+08
9	570.00	63.20	0.041	-1.54E-03	-3733.9	-54098.8		9.18E+08
10	565.00	62.83	0.048	-1.19E-03	-3418.8	-71943.5		9.18E+08
11	560.00	62.52	0.053	-7.63E-04	-3105.4	-88186.1		9.18E+08
12	557.00	62.41	0.054	-4.61E-04	-2918.0	-97204.5		9.18E+08
13	554.00	62.40	0.055	-1.29E-04	-2730.8	-105668.8		9.18E+08
		1441.19	0.055	-1.29E-04	-2730.8	-105668.8		
14	550.00	1709.41	0.055	3.27E-04	3570.4	-104334.0		9.18E+08
		267.01	0.055	3.27E-04	3570.4	-104334.0		
15	545.00	700.50	0.052	8.33E-04	5989.2	-81757.4		9.18E+08
16	540.00	1187.50	0.047	1.17E-03	10709.2	-42307.1		8.07E+08
		-11.63	0.047	1.17E-03	10709.2	-42307.1		
17	535.00	328.35	0.041	1.26E-03	11501.0	11728.7		8.07E+08
		-2187.21	0.041	1.26E-03	11501.0	11728.7		
18	530.00	-1241.21	0.035	1.09E-03	2929.9	42564.7		8.07E+08
19	525.00	-559.42	0.030	8.36E-04	-1571.7	41916.7		8.07E+08
20	520.00	-90.69	0.026	6.22E-04	-3197.0	27065.0		8.07E+08
21	515.00	269.09	0.023	5.08E-04	-2751.0	9945.9		8.07E+08
22	512.00	459.83	0.022	4.84E-04	-1657.6	2903.7		8.07E+08
23	509.00	645.24	0.021	4.79E-04	-0.0	-0.0		---
At elev. 584.00					Prop force =	6153.9 lb/ft run		

(continued)

Stage No.6 Apply surcharge no.4 at elevation 591.00

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	0.00	0.00	0.00	683
3	587.50	0.00	455.57	139.86	1482.89	183.61	183.61	4099
4	584.00	0.00	912.20	280.05	2969.23	312.96	312.96	8199
		Total>	912.20	0.00	4912.20	239.81	239.81	46258
5	580.50	Total>	1368.55	0.00	5368.55	113.14	113.14	48282
6	577.00	Total>	1824.31	0.00	5824.31	0.92	0.92	50306
		0.00	1824.31	0.00	5824.31	1.20	1.20	46258
7	576.00	62.40	1892.04	0.00	5892.04	1.05	63.45	46258
8	573.00	249.60	2095.08	0.00	6095.08	0.98	250.58	46258
9	570.00	436.80	2297.93	0.00	6297.93	0.80	437.60	46258
10	565.00	748.80	2635.80	0.00	6635.80	0.43	749.23	46258
11	560.00	1060.80	2973.54	0.00	6973.54	0.12	1060.92	46258
12	557.00	1248.00	3176.17	0.00	7176.17	0.01	1248.01	46258
13	554.00	1435.20	3378.79	0.00	7378.79	0.00	1435.20a	46258
		1435.20	3378.79	1378.79	5378.79	1378.79	2813.99a	23129
14	550.00	1684.80	3646.97	1646.97	5646.97	1647.01	3331.81	23129
15	545.00	1996.80	3986.69	1986.69	5986.69	1986.69	3983.49a	23129
16	540.00	2308.80	4324.44	2324.44	6324.44	2324.44	4633.24a	23129
		2308.80	4324.44	1125.03	2000.00	1125.31	3434.11	23129
17	535.00	2620.80	4662.22	1288.52	2000.00	1288.99	3909.79	23129
		2620.80	4662.22	0.00	5000.00	308.00	2928.80	57822
18	530.00	2932.80	4999.57	0.00	5000.00	837.58	3770.38	57822
19	525.00	3244.80	5337.85	163.52	5000.00	1301.03	4545.83	57822
20	520.00	3556.80	5675.69	327.03	5000.00	1696.42	5253.22	57822
21	515.00	3868.80	6013.55	490.56	5000.00	2044.78	5913.58	57822
22	512.00	4056.00	6216.27	588.68	5000.00	2242.66	6298.66	57822
23	509.00	4243.20	6419.00	686.79	5000.00	2438.19	6681.39	57822

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	557.00	1185.60	0.00	0.00	0.00	0.00	1185.60	0.0
13	554.00	1372.80	-0.00	0.00	0.00	0.00	1372.80	0.0
14	550.00	1622.40	-0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	-0.00	0.00	2000.00	1442.40	3064.80	38540
15	545.00	1934.40	338.00	0.00	2338.00	1348.59	3282.99	38540
16	540.00	2246.40	676.00	0.00	2676.00	1199.34	3445.74	38540
		2246.40	676.00	0.00	2000.00	1199.34	3445.74	38540
17	535.00	2558.40	1014.00	0.00	2000.00	1023.04	3581.44	38540
		2558.40	1014.00	0.00	5000.00	2557.61	5116.01	96349

(continued)

Stage No.6 Apply surcharge no.4 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
18	530.00	2870.40	1352.01	0.00	5000.00	2141.20	5011.60	96349
19	525.00	3182.40	1690.02	0.00	5000.00	1922.85	5105.25	96349
20	520.00	3494.40	2028.03	0.00	5000.00	1849.52	5343.92	96349
21	515.00	3806.40	2366.05	0.00	5000.00	1838.10	5644.50	96349
22	512.00	3993.60	2568.87	0.00	5000.00	1845.24	5838.84	96349
23	509.00	4180.80	2771.68	0.00	5000.00	1855.35	6036.15	96349

Note: 4633.24a Soil pressure at active limit
 123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.6 Apply surcharge no.4 at elev. 591.00



Stage No.6 Apply surcharge no.4 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.7 Apply load no.1 at elev. 593.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 7 Apply load no.1 at elevation 593.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
7	591.00	550.00	584.00	4.972	n/a	***	***	L to R

Legend: *** Result not found

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 500.00 from wall

Right side 500.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
1	593.00	0.00	0.006	-1.48E-03	2000.0	-0.0	2000.0	9.18E+08
2	591.00	0.00	0.008	-1.49E-03	2000.0	4000.0		9.18E+08
3	587.50	139.86	0.014	-1.52E-03	2244.8	11348.4		9.18E+08
4	584.00	280.05	0.019	-1.58E-03	2979.6	20523.8	-7672.3	9.18E+08
		0.00	0.019	-1.58E-03	-4692.7	20523.8		
5	580.50	0.00	0.025	-1.63E-03	-4692.7	4846.6		9.18E+08
6	577.00	0.00	0.031	-1.61E-03	-4692.7	-10963.2		9.18E+08
7	576.00	62.40	0.032	-1.60E-03	-4661.5	-15645.6		9.18E+08
8	573.00	62.40	0.037	-1.53E-03	-4474.3	-29351.1		9.18E+08
9	570.00	62.40	0.041	-1.41E-03	-4287.1	-42491.4		9.18E+08
10	565.00	63.15	0.048	-1.12E-03	-3973.2	-63108.8		9.18E+08
11	560.00	79.63	0.052	-7.31E-04	-3616.3	-82119.6		9.18E+08
12	557.00	84.07	0.054	-4.46E-04	-3370.7	-92593.5		9.18E+08
13	554.00	85.65	0.055	-1.27E-04	-3116.1	-102318.3		9.18E+08
		1452.81	0.055	-1.27E-04	-3116.1	-102318.3		
14	550.00	1720.47	0.055	3.17E-04	3230.4	-102431.8		9.18E+08
		294.32	0.055	3.17E-04	3230.4	-102431.8		
15	545.00	722.36	0.052	8.17E-04	5772.1	-81213.6		9.18E+08
16	540.00	1202.52	0.047	1.15E-03	10584.3	-42575.1		8.07E+08
		3.39	0.047	1.15E-03	10584.3	-42575.1		
17	535.00	337.04	0.041	1.25E-03	11435.4	11024.2		8.07E+08
		-2165.49	0.041	1.25E-03	11435.4	11024.2		
18	530.00	-1231.31	0.035	1.08E-03	2943.4	41803.8		8.07E+08
19	525.00	-556.84	0.030	8.31E-04	-1527.0	41346.9		8.07E+08
20	520.00	-92.45	0.026	6.20E-04	-3150.2	26750.7		8.07E+08
21	515.00	264.76	0.023	5.07E-04	-2719.5	9843.2		8.07E+08
22	512.00	454.55	0.022	4.83E-04	-1640.5	2876.1		8.07E+08
23	509.00	639.11	0.021	4.78E-04	-0.0	-0.0		---

At elev. 584.00

Prop force = 7672.3 lb/ft run

(continued)

Stage No.7 Apply load no.1 at elevation 593.00

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	0.00	0.00	0.00	1831
3	587.50	0.00	455.57	139.86	1482.89	139.86	139.86a	10988
4	584.00	0.00	912.20	280.05	2969.23	280.05	280.05a	21976
		Total>	912.20	0.00	4912.20	0.00	0.00a	114139
5	580.50	Total>	1368.55	0.00	5368.55	0.00	0.00a	119133
6	577.00	Total>	1824.31	0.00	5824.31	0.00	0.00a	124126
		0.00	1824.31	0.00	5824.31	0.00	0.00a	114139
7	576.00	62.40	1892.04	0.00	5892.04	0.00	62.40a	114139
8	573.00	249.60	2095.08	0.00	6095.08	0.00	249.60a	114139
9	570.00	436.80	2297.93	0.00	6297.93	0.00	436.80a	114139
10	565.00	748.80	2635.80	0.00	6635.80	0.75	749.55	65414
11	560.00	1060.80	2973.54	0.00	6973.54	17.23	1078.03	65414
12	557.00	1248.00	3176.17	0.00	7176.17	21.67	1269.67	65414
13	554.00	1435.20	3378.79	0.00	7378.79	23.25	1458.45	65414
		1435.20	3378.79	1378.79	5378.79	1390.41	2825.61	32707
14	550.00	1684.80	3646.97	1646.97	5646.97	1658.07	3342.87	32707
15	545.00	1996.80	3986.69	1986.69	5986.69	1995.54	3992.34	32707
16	540.00	2308.80	4324.44	2324.44	6324.44	2330.52	4639.32	32707
		2308.80	4324.44	1125.03	2000.00	1131.39	3440.19	32707
17	535.00	2620.80	4662.22	1288.52	2000.00	1292.51	3913.31	32707
		2620.80	4662.22	0.00	5000.00	316.79	2937.59	81768
18	530.00	2932.80	4999.57	0.00	5000.00	841.59	3774.39	81768
19	525.00	3244.80	5337.85	163.52	5000.00	1302.07	4546.87	81768
20	520.00	3556.80	5675.69	327.03	5000.00	1695.54	5252.34	143253
21	515.00	3868.80	6013.55	490.56	5000.00	2042.62	5911.42	143253
22	512.00	4056.00	6216.27	588.68	5000.00	2240.02	6296.02	143253
23	509.00	4243.20	6419.00	686.79	5000.00	2435.12	6678.32	143253

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	557.00	1185.60	0.00	0.00	0.00	0.00	1185.60	0.0
13	554.00	1372.80	-0.00	0.00	0.00	0.00	1372.80	0.0
14	550.00	1622.40	-0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	-0.00	0.00	2000.00	1426.15	3048.55	48097
15	545.00	1934.40	338.00	0.00	2338.00	1335.57	3269.97	48097
16	540.00	2246.40	676.00	0.00	2676.00	1190.40	3436.80	48097
		2246.40	676.00	0.00	2000.00	1190.40	3436.80	48097
17	535.00	2558.40	1014.00	0.00	2000.00	1017.87	3576.27	48097
		2558.40	1014.00	0.00	5000.00	2544.68	5103.08	120242

(continued)

Stage No.7 Apply load no.1 at elevation 593.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective stresses</u>		<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	lb/ft2	lb/ft2	lb/ft3
18	530.00	2870.40	1352.01	0.00	5000.00	2135.31	5005.71	120242
19	525.00	3182.40	1690.02	0.00	5000.00	1921.31	5103.71	120242
20	520.00	3494.40	2028.03	0.00	5000.00	1850.39	5344.79	143253
21	515.00	3806.40	2366.05	0.00	5000.00	1840.26	5646.66	143253
22	512.00	3993.60	2568.87	0.00	5000.00	1847.88	5841.48	143253
23	509.00	4180.80	2771.68	0.00	5000.00	1858.41	6039.21	143253


Note: 436.80a Soil pressure at active limit
 123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: 25-10.22_SecB-B.1
 Pulliam Dock Wall - Section B - P54x11/16 & NZ26
 Load Case B.1 - SSP EL. 540


| Sheet No.
 | Job No. 2201593
 | Made by : EQB
 |
 | Date:22-10-2025
 | Checked :

Units: lb, ft

Stage No.7 Apply load no.1 at elev. 593.00



Stage No.7 Apply load no.1 at elev. 593.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.10 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 10 Apply surcharge no.3 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act. Pass.</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
				<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u> <u>equilib.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
10	591.00	550.00	584.00	2.819	n/a	528.66	21.34	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 500.00 from wall

Right side 500.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
1	593.00	0.00	0.010	-2.01E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.014	-2.02E-03	2000.0	4000.0		9.18E+08
		242.61	0.014	-2.02E-03	2000.0	4000.0		
3	587.50	436.15	0.021	-2.05E-03	3187.8	12986.9		9.18E+08
4	584.00	591.33	0.028	-2.13E-03	4985.9	27436.9	-11288.2	9.18E+08
		66.23	0.028	-2.13E-03	-6302.2	27436.9		
5	580.50	0.00	0.036	-2.19E-03	-6186.3	6274.7		9.18E+08
6	577.00	0.00	0.043	-2.17E-03	-6186.3	-14754.2		9.18E+08
7	576.00	62.40	0.046	-2.16E-03	-6155.1	-20930.8		9.18E+08
8	573.00	62.40	0.052	-2.06E-03	-5967.9	-39129.6		9.18E+08
9	570.00	62.40	0.058	-1.90E-03	-5780.7	-56763.8		9.18E+08
10	565.00	62.40	0.067	-1.51E-03	-5468.7	-86200.2		9.18E+08
11	560.00	62.40	0.073	-9.75E-04	-5156.7	-112766.6		9.18E+08
12	557.00	62.40	0.075	-5.83E-04	-4969.5	-127539.2		9.18E+08
13	554.00	150.36	0.076	-1.42E-04	-4650.4	-142054.4		9.18E+08
		2150.36	0.076	-1.42E-04	-4650.4	-142054.4		
14	550.00	2480.03	0.076	4.76E-04	4610.4	-142559.1		9.18E+08
		480.03	0.076	4.76E-04	4610.4	-142559.1		
15	545.00	1002.18	0.072	1.16E-03	8315.9	-110221.3		9.18E+08
16	540.00	1628.24	0.064	1.61E-03	14891.9	-55030.8		8.07E+08
		46.29	0.064	1.61E-03	14891.9	-55030.8		
17	535.00	398.74	0.056	1.72E-03	16004.5	19021.0		8.07E+08
		-3049.94	0.056	1.72E-03	16004.5	19021.0		
18	530.00	-1754.95	0.048	1.47E-03	3992.3	61905.5		8.07E+08
19	525.00	-795.34	0.041	1.09E-03	-2383.5	60452.8		8.07E+08
20	520.00	-121.26	0.037	7.88E-04	-4675.0	38886.4		8.07E+08
21	515.00	394.71	0.033	6.24E-04	-3991.3	14275.1		8.07E+08
22	512.00	667.40	0.031	5.90E-04	-2398.2	4135.2		8.07E+08
23	509.00	931.37	0.030	5.82E-04	-0.0	0.0		---
At elev. 584.00			Prop force = 11288.2 lb/ft run					

(continued)

Stage No.10 Apply surcharge no.3 at elevation 591.00

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.50	1627.50	242.61	242.61	4562
3	587.50	0.00	954.67	293.08	3107.46	436.15	436.15	27370
4	584.00	0.00	1407.14	431.99	4580.24	591.33	591.33	7471
		Total>1407.14		0.00	5407.14	66.23	66.23	43016
5	580.50	Total>1859.04		0.00	5859.04	0.00	0.00a	44898
6	577.00	Total>2315.91		0.00	6315.91	0.00	0.00a	46780
		0.00	2315.91	0.00	6315.91	0.00	0.00a	43016
7	576.00	62.40	2385.59	0.00	6385.59	0.00	62.40a	43016
8	573.00	249.60	2599.43	0.00	6599.43	0.00	249.60a	43016
9	570.00	436.80	2820.54	0.00	6820.54	0.00	436.80a	43016
10	565.00	748.80	3203.36	0.00	7203.36	0.00	748.80a	43016
11	560.00	1060.80	3600.02	0.00	7600.02	0.00	1060.80a	43016
12	557.00	1248.00	3842.74	0.00	7842.74	0.00	1248.00a	43016
13	554.00	1435.20	4087.96	87.96	8087.96	87.96	1523.16a	43016
		1435.20	4087.96	2087.96	6087.96	2087.96	3523.16a	21508
14	550.00	1684.80	4417.63	2417.63	6417.63	2417.63	4102.43a	21508
15	545.00	1996.80	4832.19	2832.19	6832.19	2832.19	4828.99a	21508
16	540.00	2308.80	5247.68	3247.68	7247.68	3247.68	5556.48a	21508
		2308.80	5247.68	1571.88	2000.00	1665.73	3974.53	21508
17	535.00	2620.80	5662.64	1772.72	2000.00	1772.72	4393.52a	21508
		2620.80	5662.64	320.72	5000.00	478.61	3099.41	53770
18	530.00	2932.80	6076.03	520.80	5000.00	1200.69	4133.49	53770
19	525.00	3244.80	6487.10	719.75	5000.00	1825.06	5069.86	53770
20	520.00	3556.80	6895.33	917.34	5000.00	2348.39	5905.19	53770
21	515.00	3868.80	7300.37	1113.38	5000.00	2801.50	6670.30	53770
22	512.00	4056.00	7541.76	1230.21	5000.00	3056.24	7112.24	53770
23	509.00	4243.20	7781.89	1346.43	5000.00	3306.44	7549.64	53770

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	557.00	1185.60	0.00	0.00	0.00	0.00	1185.60	0.0
13	554.00	1372.80	-0.00	0.00	0.00	0.00	1372.80	0.0
14	550.00	1622.40	-0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	-0.00	0.00	2000.00	2000.00	3622.40p	24893
15	545.00	1934.40	338.00	0.00	2338.00	1892.41	3826.81	24893
16	540.00	2246.40	676.00	0.00	2676.00	1681.84	3928.24	24893
		2246.40	676.00	0.00	2000.00	1681.84	3928.24	24893
17	535.00	2558.40	1014.00	0.00	2000.00	1436.38	3994.78	24893
		2558.40	1014.00	0.00	5000.00	3590.96	6149.36	62231

(continued)

Stage No.10 Apply surcharge no.3 at elevation 591.00

		RIGHT side						
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses		Earth pressure lb/ft2	Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
				Active limit lb/ft2	Passive limit lb/ft2			
18	530.00	2870.40	1352.01	0.00	5000.00	3018.05	5888.45	62231
19	525.00	3182.40	1690.02	0.00	5000.00	2682.80	5865.20	62231
20	520.00	3494.40	2028.03	0.00	5000.00	2532.05	6026.45	62231
21	515.00	3806.40	2366.05	0.00	5000.00	2469.19	6275.59	62231
22	512.00	3993.60	2568.87	0.00	5000.00	2451.24	6444.84	62231
23	509.00	4180.80	2771.68	0.00	5000.00	2437.47	6618.27	62231

Note: 4393.52a Soil pressure at active limit
 3622.40p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.10 Apply surcharge no.3 at elev. 591.00



Stage No.10 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.15 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : EQB
 Data filename/Run ID: 25-10.22_SecB-B.1 |
 Pulliam Dock Wall - Section B - P54x11/16 & NZ26 | Date:22-10-2025
 Load Case B.1 - SSP EL. 540 | Checked :

Units: lb,ft

Stage No. 15 Change properties of soil type 8 to soil type 10
 Ko pressures will not be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method
 Factor of safety on gross pressure (excluding water pressure)

Stage	Ground level	Prop	FoS for toe	Toe elev. for				
No.	Act.	Elev.	elev. = 509.00	FoS = 1.500				
	Pass.		Factor	Moment	Toe	Wall	Direction	
			of	at equil.	elev.	Penetr	of	
			Safety	at elev.		-ation	failure	
15	591.00	550.00	584.00	2.262	n/a	519.76	30.24	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall
Analysis options

Length of wall perpendicular to section = 1000.00ft
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached
 Open Tension Crack analysis - No

Rigid boundaries: Left side 500.00 from wall
 Right side 500.00 from wall

*** Wall displacements reset to zero at stage 1

Node	Y	Nett	Wall	Wall	Shear	Bending	Prop	EI of
no.	coord	pressure	disp.	rotation	force	moment	forces	wall
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	-0.010	-1.06E-02	2000.0	-0.0	2000.0	9.18E+08
2	591.00	0.00	0.011	-1.06E-02	2000.0	4000.0		9.18E+08
		285.68	0.011	-1.06E-02	2000.0	4000.0		
3	587.50	326.84	0.049	-1.06E-02	3071.9	13250.8		9.18E+08
4	584.00	431.99	0.086	-1.07E-02	4399.9	26300.3	-34456.4	9.18E+08
		469.05	0.086	-1.07E-02	-30056.5	26300.3		
5	580.50	619.68	0.124	-1.06E-02	-28151.2	-75091.7		9.18E+08
6	577.00	771.97	0.160	-1.01E-02	-25715.8	-168891.3		9.18E+08
		836.12	0.160	-1.01E-02	-25715.8	-168891.3		
7	576.00	923.68	0.170	-9.99E-03	-24835.9	-194175.0		9.18E+08
8	573.00	1000.88	0.199	-9.25E-03	-21949.1	-264424.7		9.18E+08
9	570.00	1080.71	0.226	-8.28E-03	-18826.7	-325659.4		9.18E+08
10	565.00	1218.92	0.262	-6.29E-03	-13077.6	-407020.8		9.18E+08
11	560.00	1362.13	0.288	-3.94E-03	-6625.0	-456578.5		9.18E+08
12	557.00	1449.76	0.298	-2.43E-03	-2407.2	-469775.7		9.18E+08
13	554.00	1538.29	0.303	-8.95E-04	2074.9	-470359.9		9.18E+08
		1751.85	0.303	-8.95E-04	2074.9	-470359.9		
14	550.00	2081.12	0.302	1.10E-03	9740.8	-447151.5		9.18E+08
15	545.00	1642.54	0.291	3.33E-03	19050.0	-373202.8		9.18E+08
16	540.00	1217.35	0.270	5.05E-03	26199.7	-260821.6		8.07E+08
		-364.59	0.270	5.05E-03	26199.7	-260821.6		
17	535.00	-351.19	0.241	6.28E-03	24410.2	-135161.3		8.07E+08
		-1464.23	0.241	6.28E-03	24410.2	-135161.3		
18	530.00	-2251.73	0.208	6.82E-03	15120.4	-39103.8		8.07E+08
19	525.00	-1574.88	0.174	6.91E-03	5553.8	10944.1		8.07E+08
20	520.00	-725.70	0.139	6.81E-03	-197.6	19319.8		8.07E+08
21	515.00	-30.60	0.105	6.72E-03	-2088.4	9539.8		8.07E+08
22	512.00	350.22	0.085	6.70E-03	-1608.9	3194.8		8.07E+08
23	509.00	722.40	0.065	6.69E-03	0.0	0.0		---
At elev. 584.00					Prop force =	34456.4 lb/ft run		

(continued)

Stage No.15 Change properties of soil type 8 to soil type 10

Ko pressures will not be reset

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.50	1627.50	285.68	285.68	17605
3	587.50	0.00	954.67	293.08	3107.46	326.84	326.84	3941
4	584.00	0.00	1407.14	431.99	4580.24	431.99	431.99a	7882
		0.00	1407.14	469.05	4221.42	469.05	469.05a	44822
5	580.50	0.00	1859.04	619.68	5577.11	619.68	619.68a	46783
6	577.00	0.00	2315.91	771.97	6947.73	771.97	771.97a	48744
		0.00	2315.91	836.12	6414.67	836.12	836.12a	22951
7	576.00	62.40	2385.59	861.28	6607.67	861.28	923.68a	24590
8	573.00	249.60	2599.43	938.48	7199.98	938.48	1188.08a	29508
9	570.00	436.80	2820.54	1018.31	7812.40	1018.31	1455.11a	34426
10	565.00	748.80	3203.36	1156.52	8872.75	1156.52	1905.32a	42623
11	560.00	1060.80	3600.02	1299.73	9971.43	1299.73	2360.53a	50819
12	557.00	1248.00	3842.74	1387.36	10643.72	1387.36	2635.36a	55737
13	554.00	1435.20	4087.96	1475.89	11322.95	1475.89	2911.09a	60655
		1435.20	4087.96	1596.19	10469.27	1689.45	3124.65	1761
14	550.00	1684.80	4417.63	1724.91	11313.54	2018.72	3703.52	1761
15	545.00	1996.80	4832.19	1886.78	12375.24	2445.75	4442.55	1761
16	540.00	2308.80	5247.68	2049.02	13439.30	2886.19	5194.99	1761
		2308.80	5247.68	991.81	13439.30	1304.24	3613.04	1761
17	535.00	2620.80	5662.64	1070.24	14502.02	1446.71	4067.51	1761
		2620.80	5662.64	1070.24	14502.02	1070.24	3691.04a	2564
18	530.00	2932.80	6076.03	1148.37	15560.71	1148.37	4081.17a	2564
19	525.00	3244.80	6487.10	1226.06	16613.46	1486.18	4730.98	2564
20	520.00	3556.80	6895.33	1303.22	17658.94	2085.62	5642.42	2564
21	515.00	3868.80	7300.37	1379.77	18696.24	2616.61	6485.41	2564
22	512.00	4056.00	7541.76	1425.39	19314.45	2918.35	6974.35	2564
23	509.00	4243.20	7781.89	1470.78	19929.41	3215.60	7458.80	2564

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	557.00	1185.60	0.00	0.00	0.00	0.00	1185.60	0.0
13	554.00	1372.80	-0.00	0.00	0.00	0.00	1372.80	0.0
14	550.00	1622.40	-0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	-0.00	0.00	-0.00	-0.00	1622.40	2290
15	545.00	1934.40	338.00	131.98	865.62	865.62	2800.02p	2290
16	540.00	2246.40	676.00	263.95	1731.24	1731.24	3977.64p	2290
		2246.40	676.00	127.76	1731.24	1731.24	3977.64p	2290

(continued)

Stage No.15 Change properties of soil type 8 to soil type 10

Ko pressures will not be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Effective stresses</u> <u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
17	535.00	2558.40	1014.00	191.65	2596.86	1860.29	4418.69	2290
		2558.40	1014.00	191.65	2596.86	2596.86	5155.26p	3334
18	530.00	2870.40	1352.01	255.53	3462.50	3462.50	6332.90p	3334
19	525.00	3182.40	1690.02	319.41	4328.14	3123.46	6305.86	3334
20	520.00	3494.40	2028.03	383.30	5193.79	2873.72	6368.12	3334
21	515.00	3806.40	2366.05	447.18	6059.46	2709.60	6516.00	3334
22	512.00	3993.60	2568.87	485.52	6578.86	2630.53	6624.13	3334
23	509.00	4180.80	2771.68	523.85	7098.28	2555.59	6736.39	3334

Note: 4081.17a Soil pressure at active limit

6332.90p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593


| Made by : EQB

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.15 Change soil type 8 to soil type 10



Stage No.15 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe		Toe elev. for			
			elev. = 509.00		FoS = 1.500			
<u>Stage</u>	<u>Ground level</u>		<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>
1	584.00	584.00	---	<u>Conditions not suitable for FoS calc.</u>				
2	584.00	584.00		No analysis at this stage				
3	591.00	584.00	584.00	<u>Conditions not suitable for FoS calc.</u>				
4	591.00	550.00	584.00	5.177	n/a	***	***	L to R
5	591.00	550.00	584.00	4.934	n/a	***	***	L to R
6	591.00	550.00	584.00	4.926	n/a	***	***	L to R
7	591.00	550.00	584.00	4.972	n/a	***	***	L to R
8	591.00	550.00	584.00	4.467	n/a	531.94	18.06	L to R
9	591.00	550.00		No analysis at this stage				
10	591.00	550.00	584.00	2.819	n/a	528.66	21.34	L to R
11	591.00	550.00		No analysis at this stage				
12	591.00	550.00		No analysis at this stage				
13	591.00	550.00		No analysis at this stage				
14	591.00	550.00		No analysis at this stage				
15	591.00	550.00	584.00	2.262	n/a	519.76	30.24	L to R

Legend: *** Result not found

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecB-B.1

Pulliam Dock Wall - Section B - P54x11/16 & NZ26

Load Case B.1 - SSP EL. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 500.00 from wall

Right side 500.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	593.00	0.014	-0.010	0.0	-0.0	2000.0	0.0
2	591.00	0.017	-0.000	4000.0	-0.0	2000.0	0.0
3	587.50	0.049	-0.000	13250.8	0.0	3187.8	0.0
4	584.00	0.086	-0.000	27436.9	0.0	4985.9	-30056.5
5	580.50	0.124	-0.000	7999.0	-75091.7	0.0	-28151.2
6	577.00	0.160	0.000	868.8	-168891.3	734.2	-25715.8
7	576.00	0.170	0.000	1561.4	-194175.0	651.5	-24835.9
8	573.00	0.199	0.000	3145.5	-264424.7	406.8	-21949.1
9	570.00	0.226	0.000	4002.1	-325659.4	162.9	-18826.7
10	565.00	0.262	0.000	3794.1	-407020.8	0.0	-13077.6
11	560.00	0.288	0.000	1330.3	-456578.5	0.0	-6625.0
12	557.00	0.298	0.000	0.0	-469775.7	0.0	-4969.5
13	554.00	0.303	0.000	0.0	-470359.9	2074.9	-4650.4
14	550.00	0.302	0.000	0.0	-447151.5	9740.8	-648.1
15	545.00	0.291	0.000	0.0	-373202.8	19050.0	-0.0
16	540.00	0.270	0.000	0.0	-260821.6	26199.7	-0.0
17	535.00	0.241	0.000	19021.0	-135161.3	24410.2	-0.0
18	530.00	0.208	0.000	61905.5	-39103.8	15120.4	-0.0
19	525.00	0.174	0.000	60452.8	-0.0	5553.8	-2383.5
20	520.00	0.139	0.000	38886.4	-0.0	0.0	-4675.0
21	515.00	0.105	0.000	14275.1	0.0	0.0	-3991.3
22	512.00	0.085	0.000	4135.2	0.0	0.0	-2398.2
23	509.00	0.065	0.000	0.0	-0.0	0.0	-0.0

Summary of results (continued)**Maximum and minimum bending moment and shear force at each stage**

Stage	Bending moment				Shear force			
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	0.0	573.00	-0.0	535.00	0.0	580.50	-0.0	525.00
2	No calculation at this stage							
3	4002.1	570.00	-10160.9	545.00	1614.7	540.00	-1472.0	584.00
4	39740.6	525.00	-103037.3	550.00	11331.3	535.00	-4622.5	584.00
5	42468.5	530.00	-105510.4	554.00	11484.6	535.00	-4948.4	584.00
6	42564.7	530.00	-105668.8	554.00	11501.0	535.00	-4963.6	584.00
7	41803.8	530.00	-102431.8	550.00	11435.4	535.00	-4692.7	584.00
8	48278.7	530.00	-107706.4	554.00	12229.6	535.00	-5823.0	584.00
9	No calculation at this stage							
10	61905.5	530.00	-142559.1	550.00	16004.5	535.00	-6302.2	584.00
11	No calculation at this stage							
12	No calculation at this stage							
13	No calculation at this stage							
14	No calculation at this stage							
15	26300.3	584.00	-470359.9	554.00	26199.7	540.00	-30056.5	584.00

Maximum and minimum displacement at each stage

Stage	Displacement				<u>Stage description</u>
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	
	ft		ft		
1	0.000	535.00	-0.000	593.00	Change EI of wall to 8.0771E+08lb.ft ² /ft run
2	No calculation at this stage				Install prop no.1 at elev. 584.00
3	0.008	550.00	0.000	593.00	Fill to elev. 591.00 on LEFT side
4	0.054	554.00	-0.002	593.00	Excav. to elev. 550.00 on RIGHT side
5	0.055	554.00	-0.002	593.00	Apply water pressure profile no.1
6	0.055	554.00	-0.002	593.00	Apply surcharge no.4 at elev. 591.00
7	0.055	554.00	0.000	593.00	Apply load no.1 at elev. 593.00
8	0.060	554.00	0.000	593.00	Apply surcharge no.1 at elev. 591.00
9	No calculation at this stage				Apply surcharge no.2 at elev. 591.00
10	0.076	554.00	0.000	593.00	Apply surcharge no.3 at elev. 591.00
11	No calculation at this stage				Change soil type 2 to soil type 11
12	No calculation at this stage				Change soil type 3 to soil type 4
13	No calculation at this stage				Change soil type 5 to soil type 6
14	No calculation at this stage				Change soil type 7 to soil type 9
15	0.303	554.00	-0.010	593.00	Change soil type 8 to soil type 10

Prop forces at each stage (horizontal components)

Stage -- Anchor no. 1 --
no. at elev. 584.00


	lb/ft run	lb/prop
3	2799.28	26033.27
4	5827.62	54196.91
5	6134.10	57047.14
6	6153.91	57231.35
7	7672.28	71352.24
8	10705.08	99557.26
10	11288.16	104979.93
15	34456.36	320444.16

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: 25-10.22_SecB-B.1
Pulliam Dock Wall - Section B - P54x11/16 & NZ26
Load Case B.1 - SSP EL. 540

| Sheet No.
| Job No. 2201593
| Made by : EQB
|
| Date:22-10-2025
Checked :

Units: lb,ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
WALLAP ANALYSIS: C.1 – EMBEDMENT CHECK						

GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : EQB
 Data filename/Run ID: SecC-C-1_EmbedmentCheck |
 Pulliam Dock Wall - Section C - Pipe54x5/8 & NZ26 | Date:15-07-2025
 Load Case C.1 SSP El. 540_King Pile Embedment Depth Check | Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Left side	Soil types	Right side
1	553.00	3 Clay IIA		3 Clay IIA
2	540.00	5 KP - Clay IIA		5 KP - Clay IIA
3	532.00	8 KP - Clay III		8 KP - Clay III

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft3	Eh, lb/ft2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu) (Kac)	Ka (Kpc)	Kp (dc/dy)	lb/ft2
1 Granular	130.0	0	0.470	NC	0.307	3.255	
Fill - AW		(42000)		(0.330)	(0.000)	(0.000)	
2 Granular	120.0	0	0.500	NC	0.333	3.000	
Fill - BW		(15000)		(0.330)	(0.000)	(0.000)	
3 Clay IIA	130.0	1200000	0.561	NC	1.000	1.000	1000d
				(0.490)	(2.000)	(1.330)	
4 Clay IIA - L.Term	130.0	47151	0.561	OC	0.390	2.561	
				(0.490)	(0.000)	(0.000)	
5 KP - Clay IIA	130.0	600000	0.561	NC	0.484	0.000	1000d
				(0.490)	(0.968)	(1.330)	
6 KP - ClayI- IA.L.Term	130.0	47151	0.561	OC	0.189	1.707	
				(0.330)	(0.000)	(0.000)	
7 Clay III	130.0	1500000	0.561	NC	1.000	1.000	2500d
				(0.490)	(2.000)	(2.000)	
8 KP - Clay III	130.0	1500000	0.561	NC	0.484	0.000	2500d
				(0.490)	(0.968)	(1.330)	
9 KP - Clay III.LTerm	130.0	68650	0.561	OC	0.189	1.707	
				(0.330)	(0.000)	(0.000)	
10 Granular	120.0	0	0.727	NC	0.595	3.000	
Fill - Temp		(15000)		(0.330)	(0.000)	(0.000)	
11 Clay III - L.Term	130.0	68650	0.561	OC	0.390	2.561	
				(0.490)	(0.000)	(0.000)	

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---				--- parameters for Kp ---			
Soil		Wall	Back-	Soil		Wall	Back-
friction		adhesion	fill	friction		adhesion	fill
angle		coeff.	angle	angle		coeff.	angle
1 Granular Fill - AW	32.00	0.000	0.00	32.00	0.000	0.00	
2 Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00	
3 Clay IIA	0.00	0.000	0.00	0.00	-0.507	0.00	
4 Clay IIA - L.Term	26.00	0.000	0.00	26.00	0.000	0.00	
5 KP - Clay IIA	28.06	-0.627	0.00	Incompatible values			
6 KP - ClayIIA.L.Term	43.01	0.000	0.00	15.14	0.000	0.00	
7 Clay III	0.00	0.000	0.00	Incompatible values			
8 KP - Clay III	28.06	-0.627	0.00	Incompatible values			
9 KP - Clay III.LTerm	43.01	0.000	0.00	23.35	-0.384	0.00	
10 Granular Fill - Temp	30.00	0.000	27.00	30.00	0.000	0.00	
11 Clay III - L.Term	26.00	0.000	0.00	26.00	0.000	0.00	

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	576.00	576.00

Automatic water pressure balancing at toe of wall : No

Water		Left side			Right side			
press.	-----				-----			
profile	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	
no.	no.		elev.	press.	no.		elev.	
		ft	ft	lb/ft2		ft	ft	
							lb/ft2	
1	1	577.00	577.00	0.0	1	576.00	576.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
 Elevation of toe of wall = 480.00
 Maximum finite element length = 6.00 ft
 Youngs modulus of wall E = 4.1760E+09 lb/ft2
 Moment of inertia of wall I = 0.22000 ft4/ft run
 E.I = 9.1872E+08 lb.ft2/ft run
 Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop	Prop	Cross-	Youngs	Free	Inclin	Pre-	Strut	Allow	
no.	Elev.	spacing	modulus	length	-ation	stress	or	tension	
		ft	lb/ft2	ft	(degs)	/prop	Anchor	?	L/R
		sq.ft				lb			
1	584.00	9.30	0.066810	4.176E+09	75.00	0.00	0	Anchor	n/a R

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load	Horizontal	Moment	Moment	Partial
no.	Elevation	load	load	factor
		lb/ft run	lb.ft/ft run	lb.ft/ft/rad
				(Category)
1	593.00	2000	0	0
				N/A

SURCHARGE LOADS

Surch	Distance	Length	Width	Surcharge		Equiv.	Partial
-arge	from	parallel	perpend.	-----	lb/ft2	-----	soil
no.	Elev.	wall	to wall	Near edge	Far edge	type	factor/
							Category
1	591.00	0.00(L)	1000.00	15.00	500.00	=	N/A
2	591.00	15.00(L)	1000.00	84.00	0.00	3600.00	N/A
3	591.00	99.00(L)	1000.00	150.00	3600.00	=	N/A
4	591.00	6.00(L)	1000.00	15.00	10.00	=	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Change EI of wall to 8.0771E+08 lb.ft2/ft run From elevation 540.00 to 480.00 Yield moment not defined Reset wall displacements to zero at this stage
2	Fill to elevation 565.00 on LEFT side with soil type 10
3	Install strut or anchor no.1 at elevation 584.00
4	Change properties of soil type 10 to soil type 2 No analysis at this stage Ko pressures will not be reset
5	Fill to elevation 576.00 on LEFT side with soil type 2
6	Fill to elevation 591.00 on LEFT side with soil type 1
7	Excavate to elevation 550.00 on RIGHT side
8	Apply water pressure profile no.1
9	Apply surcharge no.1 at elevation 591.00
10	Apply load no.1 at elevation 593.00
11	Apply surcharge no.4 at elevation 591.00
12	Apply surcharge no.2 at elevation 591.00 No analysis at this stage
13	Apply surcharge no.3 at elevation 591.00
14	Change properties of soil type 3 to soil type 4 No analysis at this stage Ko pressures will not be reset
15	Change properties of soil type 5 to soil type 6 No analysis at this stage Ko pressures will not be reset
16	Change properties of soil type 8 to soil type 9 Ko pressures will not be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 71.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft

Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Output options		
		Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Change EI of wall to 8.0771E+08lb.ft2/	No	No	No
2	Fill to elev. 565.00 on LEFT side	Yes	Yes	Yes
3	Install prop no.1 at elev. 584.00	No	No	No
4	Change soil type 10 to soil type 2	No	No	No
5	Fill to elev. 576.00 on LEFT side	No	No	No
6	Fill to elev. 591.00 on LEFT side	No	No	No
7	Excav. to elev. 550.00 on RIGHT side	Yes	Yes	Yes
8	Apply water pressure profile no.1	Yes	Yes	Yes
9	Apply surcharge no.1 at elev. 591.00	Yes	Yes	Yes
10	Apply load no.1 at elev. 593.00	Yes	Yes	Yes
11	Apply surcharge no.4 at elev. 591.00	Yes	Yes	Yes
12	Apply surcharge no.2 at elev. 591.00	No	No	No
13	Apply surcharge no.3 at elev. 591.00	Yes	Yes	Yes
14	Change soil type 3 to soil type 4	No	No	No
15	Change soil type 5 to soil type 6	No	No	No
16	Change soil type 8 to soil type 9	Yes	Yes	Yes
*	Summary output	Yes	-	Yes

Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : EQB
 Data filename/Run ID: SecC-C-1_EmbedmentCheck |
 Pulliam Dock Wall - Section C - Pipe54x5/8 & NZ26 | Date:15-07-2025
 Load Case C.1 SSP El. 540_King Pile Embedment Depth Check | Checked :

Units: lb,ft

Stage No. 16 Change properties of soil type 8 to soil type 9
 Ko pressures will not be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method
 Factor of safety on gross pressure (excluding water pressure)

				FoS for toe		Toe elev. for		
				elev. = 480.00		FoS = 1.500		
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>	
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>	
			<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>	
16	591.00	550.00	584.00	2.793	n/a	511.47	38.53	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall
Analysis options

Length of wall perpendicular to section = 1000.00ft
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached
 Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
 Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u>	<u>Y</u>	<u>Nett</u>	<u>Wall</u>	<u>Wall</u>	<u>Shear</u>	<u>Bending</u>	<u>Prop</u>	<u>EI of</u>
<u>no.</u>	<u>coord</u>	<u>pressure</u>	<u>disp.</u>	<u>rotation</u>	<u>force</u>	<u>moment</u>	<u>forces</u>	<u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.005	-1.06E-02	2000.0	-0.0	2000.0	9.18E+08
2	591.00	0.00	0.026	-1.06E-02	2000.0	4000.0		9.18E+08
		361.42	0.026	-1.06E-02	2000.0	4000.0		
3	587.50	470.97	0.063	-1.07E-02	3456.7	13652.4		9.18E+08
4	584.00	432.36	0.101	-1.07E-02	5037.5	29015.3	-33321.5	9.18E+08
		432.36	0.101	-1.07E-02	-28284.0	29015.3		
5	580.50	571.20	0.139	-1.07E-02	-26527.8	-66863.1		9.18E+08
6	577.00	711.58	0.176	-1.02E-02	-24282.9	-156519.8		9.18E+08
7	576.00	795.39	0.186	-1.01E-02	-23529.4	-180432.9		9.18E+08
		856.80	0.186	-1.01E-02	-23529.4	-180432.9		
8	570.50	970.89	0.238	-8.67E-03	-18503.2	-298420.1		9.18E+08
9	565.00	1092.49	0.280	-6.62E-03	-12829.0	-385768.2		9.18E+08
10	559.00	1231.43	0.312	-3.92E-03	-5857.2	-441896.2		9.18E+08
11	553.00	1374.47	0.327	-9.98E-04	1960.5	-453815.8		9.18E+08
		1768.75	0.327	-9.98E-04	1960.5	-453815.8		
12	550.00	2003.76	0.328	4.59E-04	7619.2	-439196.7		9.18E+08
13	545.00	1537.07	0.320	2.68E-03	16471.3	-379163.5		9.18E+08
14	540.00	1078.24	0.301	4.48E-03	23009.6	-280382.6		8.07E+08
		176.91	0.301	4.48E-03	23009.6	-280382.6		
15	536.00	-61.25	0.281	5.63E-03	23240.9	-187145.9		8.07E+08
16	532.00	104.49	0.257	6.33E-03	23327.4	-94430.1		8.07E+08
		-940.99	0.257	6.33E-03	23327.4	-94430.1		
17	527.00	-1440.07	0.224	6.59E-03	17374.8	10371.8		8.07E+08
18	522.00	-1638.99	0.192	6.30E-03	9677.1	82509.9		8.07E+08
19	516.00	-1142.04	0.156	5.61E-03	1334.0	104562.0		8.07E+08
20	510.00	-421.33	0.125	4.88E-03	-3356.1	92690.8		8.07E+08
21	504.00	92.65	0.097	4.30E-03	-4342.2	62838.0		8.07E+08
22	498.00	238.27	0.072	3.93E-03	-3349.4	36644.0		8.07E+08
23	492.00	196.44	0.050	3.72E-03	-2045.3	19091.4		8.07E+08
24	486.00	77.84	0.028	3.62E-03	-1222.4	8596.9		8.07E+08
25	480.00	342.32	0.006	3.59E-03	38.1	0.0		---
At elev. 584.00					Prop force = 33321.5 lb/ft run			

(continued)

Stage No.16 Change properties of soil type 8 to soil type 9
 Ko pressures will not be reset

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	361.42	361.42	4711
3	587.50	0.00	954.67	293.33	3107.07	470.97	470.97	28265
4	584.00	0.00	1407.14	432.36	4579.66	432.36	432.36a	7292
5	580.50	0.00	1859.04	571.20	6050.40	571.20	571.20a	10938
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	14583
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	15625
		62.40	2385.59	794.40	7156.77	794.40	856.80a	5580
8	570.50	405.60	2728.20	908.49	8184.60	908.49	1314.09a	7627
9	565.00	748.80	3093.36	1030.09	9280.08	1030.09	1778.89a	9673
10	559.00	1123.20	3510.60	1169.03	10531.80	1169.03	2292.23a	11905
11	553.00	1497.60	3940.14	1312.07	11820.41	1312.07	2809.67a	14137
		1497.60	3940.14	1538.47	10090.97	1706.35	3203.95	1647
12	550.00	1684.80	4187.63	1635.11	10724.80	1941.36	3626.16	1647
13	545.00	1996.80	4602.19	1796.98	11786.53	2340.31	4337.11	1647
14	540.00	2308.80	5017.68	1959.21	12850.63	2747.13	5055.93	1647
		2308.80	5017.68	948.34	8565.18	1268.44	3577.24	1169
15	536.00	2558.40	5349.74	1011.10	9132.01	1428.06	3986.46	1169
16	532.00	2808.00	5680.91	1073.69	9697.32	1590.88	4398.88	1169
		2808.00	5680.91	1073.69	9697.32	1073.69	3881.69a	1703
17	527.00	3120.00	6092.98	1151.57	10400.73	1151.57	4271.57a	1703
18	522.00	3432.00	6502.40	1228.95	11099.60	1529.62	4961.62	1703
19	516.00	3806.40	6989.63	1321.04	11931.29	2366.86	6173.26	1703
20	510.00	4180.80	7471.99	1412.21	12754.68	2783.08	6963.88	1703
21	504.00	4555.20	7949.24	1502.41	13569.35	3040.89	7596.09	1703
22	498.00	4929.60	8421.29	1591.62	14375.14	3178.10	8107.70	1703
23	492.00	5304.00	8888.15	1679.86	15172.08	3243.35	8547.35	1703
24	486.00	5678.40	9349.92	1767.13	15960.31	3275.25	8953.65	1703
25	480.00	6052.80	9806.74	1853.47	16740.10	3447.36	9500.16	38588

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	570.50	343.20	0.00	0.00	0.00	0.00	343.20	0.0
9	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
10	559.00	1060.80	0.00	0.00	0.00	0.00	1060.80	0.0
11	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
12	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	0.00	0.00	1622.40	1838
13	545.00	1934.40	338.00	131.98	865.64	865.64	2800.04p	1838
14	540.00	2246.40	676.00	263.95	1731.28	1731.28	3977.68p	1838
		2246.40	676.00	127.76	1153.93	1153.93	3400.33p	1342
15	536.00	2496.00	946.40	178.87	1615.51	1551.71	4047.71	1342

(continued)

Stage No.16 Change properties of soil type 8 to soil type 9
 Ko pressures will not be reset

		RIGHT side						
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
16	532.00	2745.60	1216.80	229.98	2077.08	1548.79	4294.39	1342
		2745.60	1216.80	229.98	2077.08	2077.08	4822.68p	1954
17	527.00	3057.60	1554.80	293.86	2654.05	2654.05	5711.65p	1954
18	522.00	3369.60	1892.80	357.74	3231.01	3231.01	6600.61p	1954
19	516.00	3744.00	2298.40	434.40	3923.37	3571.31	7315.31	1954
20	510.00	4118.40	2704.01	511.06	4615.74	3266.81	7385.21	1954
21	504.00	4492.80	3109.61	587.72	5308.10	3010.64	7503.44	1954
22	498.00	4867.20	3515.21	664.38	6000.47	3002.23	7869.43	1954
23	492.00	5241.60	3920.82	741.03	6692.83	3109.31	8350.91	1954
24	486.00	5616.00	4326.42	817.69	7385.20	3259.81	8875.81	1954
25	480.00	5990.40	4732.03	894.35	8077.57	3167.44	9157.84	38588

Note: 4271.57a Soil pressure at active limit
 6600.61p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecC-C-1_EmbedmentCheck

Pulliam Dock Wall - Section C - Pipe54x5/8 & NZ26

Load Case C.1 SSP El. 540_King Pile Embedment Depth Check

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:15-07-2025


| Checked :

Units: lb, ft

Stage No.16 Change soil type 8 to soil type 9



Stage No.16 Change soil type 8 to soil type 9



GEI CONSULTANTS, INC.	Sheet No.
Program: WALLAP Version 6.06 Revision A52.B71.R55	Job No. 2201593
Licensed from GEOSOLVE	Made by : EQB
Data filename/Run ID: SecC-C-1_EmbedmentCheck	
Pulliam Dock Wall - Section C - Pipe54x5/8 & NZ26	Date:15-07-2025
Load Case C.1 SSP El. 540_King Pile Embedment Depth Check	Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe		Toe elev. for			
			elev. = 480.00		FoS = 1.500			
<u>Stage</u>	<u>Ground</u>	<u>level</u>	<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>
1	553.00	553.00	---	<u>Conditions not suitable for FoS calc.</u>				
2	565.00	553.00	Cant.	19.899	503.28	542.49	10.51	L to R
3	565.00	553.00		No analysis at this stage				
4	565.00	553.00		No analysis at this stage				
5	576.00	553.00	584.00	18.837	n/a	***	***	L to R
6	591.00	553.00	584.00	2.988	n/a	525.42	27.58	L to R
7	591.00	550.00	584.00	2.944	n/a	524.26	25.74	L to R
8	591.00	550.00	584.00	2.847	n/a	523.83	26.17	L to R
9	591.00	550.00	584.00	2.655	n/a	522.26	27.74	L to R
10	591.00	550.00	584.00	2.664	n/a	522.41	27.59	L to R
11	591.00	550.00	584.00	2.660	n/a	522.37	27.63	L to R
12	591.00	550.00		No analysis at this stage				
13	591.00	550.00	584.00	1.710	n/a	513.06	36.94	L to R
14	591.00	550.00		No analysis at this stage				
15	591.00	550.00		No analysis at this stage				
16	591.00	550.00	584.00	2.793	n/a	511.47	38.53	L to R

Legend: *** Result not found

GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : EQB
 Data filename/Run ID: SecC-C-1_EmbedmentCheck |
 Pulliam Dock Wall - Section C - Pipe54x5/8 & NZ26 | Date:15-07-2025
 Load Case C.1 SSP El. 540_King Pile Embedment Depth Check | Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached
 Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
 Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	593.00	0.047	-0.000	0.0	-0.0	2000.0	0.0
2	591.00	0.054	-0.000	4000.0	-0.0	2000.0	0.0
3	587.50	0.068	-0.000	13652.4	-0.0	3456.7	0.0
4	584.00	0.101	-0.000	29015.3	-0.0	5037.5	-28284.0
5	580.50	0.139	-0.000	0.0	-66863.1	0.0	-26527.8
6	577.00	0.176	-0.000	0.0	-156519.8	0.0	-24282.9
7	576.00	0.186	-0.000	0.0	-180432.9	0.0	-23529.4
8	570.50	0.238	-0.000	0.0	-298420.1	0.0	-18503.2
9	565.00	0.280	-0.000	0.0	-385768.2	0.0	-12829.0
10	559.00	0.312	-0.000	1507.5	-441896.2	3728.7	-5857.2
11	553.00	0.327	-0.000	10670.3	-453815.8	9926.5	0.0
12	550.00	0.328	-0.000	16746.1	-439196.7	13669.2	0.0
13	545.00	0.320	-0.000	17799.3	-379163.5	17417.5	-583.6
14	540.00	0.301	0.000	13120.7	-280382.6	23009.6	-1430.3
15	536.00	0.281	0.000	40937.1	-187145.9	23687.4	-779.9
16	532.00	0.257	0.000	101595.2	-94430.1	25422.7	-7.1
17	527.00	0.224	0.000	160251.4	-0.0	17374.8	-339.1
18	522.00	0.192	0.000	190625.4	-0.0	9677.1	-4936.2
19	516.00	0.156	0.000	162133.5	-0.0	1334.0	-7965.9
20	510.00	0.125	0.000	115749.4	0.0	0.0	-7954.9
21	504.00	0.097	-0.000	65224.7	-120.8	0.0	-6875.9
22	498.00	0.072	0.000	36644.0	-1926.4	0.0	-4304.0
23	492.00	0.050	0.000	19091.4	-2250.0	415.4	-2045.3
24	486.00	0.028	0.000	8596.9	-1088.4	492.4	-1222.4
25	480.00	0.010	0.000	0.0	-0.0	38.1	-0.0

Summary of results (continued)

Maximum and minimum bending moment and shear force at each stage

Stage no.	Bending moment				Shear force			
	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	0.0	504.00	-0.0	516.00	0.0	545.00	-0.0	480.00
2	16824.4	545.00	-187.4	498.00	2614.7	553.00	-1430.3	540.00
3	No calculation at this stage							
4	No calculation at this stage							
5	17799.3	545.00	-25133.4	565.00	4959.5	553.00	-1627.7	584.00
6	94303.3	527.00	-163043.2	565.00	9926.5	553.00	-13612.7	584.00
7	124392.0	527.00	-202495.7	559.00	13711.4	540.00	-15416.6	584.00
8	128641.6	527.00	-211026.9	559.00	14093.5	540.00	-16013.4	584.00
9	152553.1	527.00	-250448.8	559.00	17094.8	540.00	-20264.1	584.00
10	152015.1	527.00	-244399.9	559.00	17048.6	540.00	-20206.8	584.00
11	152103.9	527.00	-244643.4	559.00	17039.6	540.00	-20248.5	584.00
12	No calculation at this stage							
13	190625.4	522.00	-338035.8	559.00	25422.7	532.00	-24036.3	584.00
14	No calculation at this stage							
15	No calculation at this stage							
16	104562.0	516.00	-453815.8	553.00	23327.4	532.00	-28284.0	584.00

Maximum and minimum displacement at each stage

Stage no.	Displacement				Stage description
	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	
	ft		ft		
1	0.000	480.00	-0.000	593.00	Change EI of wall to 8.0771E+08lb.ft ² /ft run
2	0.021	593.00	0.000	593.00	Fill to elev. 565.00 on LEFT side
3	No calculation at this stage				Install prop no.1 at elev. 584.00
4	No calculation at this stage				Change soil type 10 to soil type 2
5	0.022	580.50	0.000	593.00	Fill to elev. 576.00 on LEFT side
6	0.086	565.00	0.000	593.00	Fill to elev. 591.00 on LEFT side
7	0.105	559.00	0.000	593.00	Excav. to elev. 550.00 on RIGHT side
8	0.109	559.00	0.000	593.00	Apply water pressure profile no.1
9	0.133	559.00	0.000	593.00	Apply surcharge no.1 at elev. 591.00
10	0.133	559.00	0.000	593.00	Apply load no.1 at elev. 593.00
11	0.133	559.00	0.000	593.00	Apply surcharge no.4 at elev. 591.00
12	No calculation at this stage				Apply surcharge no.2 at elev. 591.00
13	0.189	559.00	0.000	593.00	Apply surcharge no.3 at elev. 591.00
14	No calculation at this stage				Change soil type 3 to soil type 4
15	No calculation at this stage				Change soil type 5 to soil type 6
16	0.328	550.00	0.000	593.00	Change soil type 8 to soil type 9

Summary of results (continued)

Prop forces at each stage (horizontal components)

Stage	-- Anchor no. 1 ---
no.	at elev. 584.00
	lb/ft run lb/prop
5	1627.68 15137.43
6	14591.31 135699.16
7	16395.24 152475.74
8	16992.04 158025.99
9	22992.98 213834.68
10	24565.38 228458.03
11	24609.63 228869.57
13	28418.93 264296.06
16	33321.53 309890.19

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecC-C-1_EmbedmentCheck

Pulliam Dock Wall - Section C - Pipe54x5/8 & NZ26

Load Case C.1 SSP El. 540_King Pile Embedment Depth Check

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:15-07-2025

| Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
WALLAP ANALYSIS: C.1						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	553.00	3 Clay IIA	3 Clay IIA
2	540.00	5 KP - Clay IIA	5 KP - Clay IIA
3	532.00	8 KP - Clay III	8 KP - Clay III

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft3	Eh, lb/ft2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	lb/ft2 (dc/dy)
1 Granular	130.0	0	0.470	NC	0.307	3.255	
Fill - AW		(42000)		(0.330)	(0.000)	(0.000)	
2 Granular	120.0	0	0.500	NC	0.333	3.000	
Fill - BW		(15000)		(0.330)	(0.000)	(0.000)	
3 Clay IIA	130.0	1200000	0.561	NC	1.000	1.000	1000d
				(0.490)	(2.000)	(2.000)	
4 Clay IIA - L.Term	130.0	47151	0.561	OC	0.390	2.561	
				(0.490)	(0.000)	(0.000)	
5 KP - Clay IIA	130.0	600000	0.561	NC	0.484	0.000	1000d
				(0.490)	(0.968)	(2.000)	
6 KP - ClayI- IA.L.Term	130.0	47151	0.561	OC	0.189	2.561	
				(0.330)	(0.000)	(0.000)	
7 Clay III	130.0	1500000	0.561	NC	1.000	1.000	2500d
				(0.490)	(2.000)	(2.000)	
8 KP - Clay III	130.0	1500000	0.561	NC	0.484	0.000	2500d
				(0.490)	(0.968)	(2.000)	
9 KP - Clay III.LTerm	130.0	68650	0.561	OC	0.189	2.561	
				(0.330)	(0.000)	(0.000)	
10 Granular	120.0	0	0.727	NC	0.595	3.000	
Fill - Temp		(15000)		(0.330)	(0.000)	(0.000)	
11 Clay III - L.Term	130.0	68650	0.561	OC	0.390	2.561	
				(0.490)	(0.000)	(0.000)	

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---				--- parameters for Kp ---			
		Soil friction	Wall adhesion	Back-fill			Soil friction
		angle	coeff.	angle			angle
1	Granular Fill - AW	32.00	0.000	0.00	32.00	0.000	0.00
2	Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00
3	Clay IIA	0.00	0.000	0.00	0.00	0.000	0.00
4	Clay IIA - L.Term	26.00	0.000	0.00	26.00	0.000	0.00
5	KP - Clay IIA	28.06	-0.627	0.00	Incompatible values		
6	KP - ClayIIA.L.Term	43.01	0.000	0.00	25.99	0.000	0.00
7	Clay III	0.00	0.000	0.00	0.00	0.000	0.00
8	KP - Clay III	28.06	-0.627	0.00	Incompatible values		
9	KP - Clay III.LTerm	43.01	0.000	0.00	Incompatible values		
10	Granular Fill - Temp	30.00	0.000	27.00	30.00	0.000	0.00
11	Clay III - L.Term	26.00	0.000	0.00	26.00	0.000	0.00

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	576.00	576.00

Automatic water pressure balancing at toe of wall : No

Water		Left side			Right side			
press.	-----							
profile	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	
no.	no.		elev.	press.	no.		elev.	
		ft	ft	lb/ft2		ft	ft	
							lb/ft2	
1	1	577.00	577.00	0.0	1	576.00	576.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
 Elevation of toe of wall = 509.00
 Maximum finite element length = 5.00 ft
 Youngs modulus of wall E = 4.1760E+09 lb/ft2
 Moment of inertia of wall I = 0.22000 ft4/ft run
 E.I = 9.1872E+08 lb.ft2/ft run
 Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop	Prop	Cross-	Youngs	Free	Inclin	Pre-	Strut	Allow	
no.	Elev.	section	modulus	length	-ation	stress	or	tension	
		area			(degs)	/prop	Anchor	?	L/R
		sq.ft	lb/ft2	ft		lb			
1	584.00	9.30	0.066810	4.176E+09	75.00	0.00	0	Anchor	n/a R

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load	Horizontal	Moment	Moment	Partial
no.	Elevation	load	load	factor
		lb/ft run	lb.ft/ft run	lb.ft/ft/rad (Category)
1	593.00	2000	0	0
				N/A

SURCHARGE LOADS

Surch	Distance	Length	Width	Surcharge		Equiv.	Partial
-arge	from	parallel	perpend.	-----	lb/ft2 -----	soil	factor/
no.	Elev.	wall	to wall	Near edge	Far edge	type	Category
1	591.00	0.00 (L)	1000.00	15.00	500.00	=	N/A
2	591.00	15.00 (L)	1000.00	84.00	0.00	3600.00	N/A
3	591.00	99.00 (L)	1000.00	150.00	3600.00	=	N/A
4	591.00	6.00 (L)	1000.00	15.00	10.00	=	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Change EI of wall to 8.0771E+08 lb.ft2/ft run From elevation 540.00 to 509.00 Yield moment not defined Reset wall displacements to zero at this stage
2	Fill to elevation 565.00 on LEFT side with soil type 10
3	Install strut or anchor no.1 at elevation 584.00
4	Change properties of soil type 10 to soil type 2 No analysis at this stage Ko pressures will not be reset
5	Fill to elevation 576.00 on LEFT side with soil type 2
6	Fill to elevation 591.00 on LEFT side with soil type 1
7	Excavate to elevation 550.00 on RIGHT side
8	Apply water pressure profile no.1
9	Apply surcharge no.1 at elevation 591.00
10	Apply load no.1 at elevation 593.00
11	Apply surcharge no.4 at elevation 591.00
12	Apply surcharge no.2 at elevation 591.00 No analysis at this stage
13	Apply surcharge no.3 at elevation 591.00
14	Change properties of soil type 3 to soil type 4 No analysis at this stage Ko pressures will not be reset
15	Change properties of soil type 5 to soil type 6 No analysis at this stage Ko pressures will not be reset
16	Change properties of soil type 8 to soil type 9 Ko pressures will not be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 71.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft

Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Output options		
		Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Change EI of wall to 8.0771E+08lb.ft2/	No	No	No
2	Fill to elev. 565.00 on LEFT side	Yes	Yes	Yes
3	Install prop no.1 at elev. 584.00	No	No	No
4	Change soil type 10 to soil type 2	No	No	No
5	Fill to elev. 576.00 on LEFT side	No	No	No
6	Fill to elev. 591.00 on LEFT side	No	No	No
7	Excav. to elev. 550.00 on RIGHT side	Yes	Yes	Yes
8	Apply water pressure profile no.1	Yes	Yes	Yes
9	Apply surcharge no.1 at elev. 591.00	Yes	Yes	Yes
10	Apply load no.1 at elev. 593.00	Yes	Yes	Yes
11	Apply surcharge no.4 at elev. 591.00	Yes	Yes	Yes
12	Apply surcharge no.2 at elev. 591.00	No	No	No
13	Apply surcharge no.3 at elev. 591.00	Yes	Yes	Yes
14	Change soil type 3 to soil type 4	No	No	No
15	Change soil type 5 to soil type 6	No	No	No
16	Change soil type 8 to soil type 9	Yes	Yes	Yes
*	Summary output	Yes	-	Yes


Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: 25-10.22_SecC-C-1
Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26
Load Case C.1 SSP El. 540

| Sheet No.
| Job No. 2201593
| Made by : EQB
| Date:22-10-2025
Checked :

Units: lb, ft

Stage No.2 Fill to elev. 565.00 on LEFT side



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 2 Fill to elevation 565.00 on LEFT side with soil type 10

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
2	565.00	553.00	Cant.	14.687	521.28	544.67	8.33	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.021	3.76E-04	0.0	0.0		9.18E+08
2	591.00	0.00	0.020	3.76E-04	0.0	-0.0		9.18E+08
3	587.50	0.00	0.019	3.76E-04	0.0	-0.0		9.18E+08
4	584.00	0.00	0.017	3.76E-04	0.0	-0.0		9.18E+08
5	580.50	0.00	0.016	3.76E-04	0.0	-0.0		9.18E+08
6	577.00	0.00	0.015	3.76E-04	0.0	-0.0		9.18E+08
7	576.00	0.00	0.014	3.76E-04	0.0	-0.0		9.18E+08
8	573.00	0.00	0.013	3.76E-04	0.0	-0.0		9.18E+08
9	570.00	0.00	0.012	3.76E-04	0.0	-0.0		9.18E+08
10	565.00	0.00	0.010	3.76E-04	0.0	-0.0		9.18E+08
11	560.00	176.04	0.008	3.74E-04	440.1	872.4		9.18E+08
12	556.50	307.98	0.007	3.65E-04	1287.1	3790.2		9.18E+08
13	553.00	446.54	0.006	3.38E-04	2607.5	10480.7		9.18E+08
		-519.42	0.006	3.38E-04	2607.5	10480.7		
14	550.00	-451.49	0.005	2.94E-04	1151.2	16547.5		9.18E+08
15	545.00	-240.27	0.004	2.03E-04	-578.2	16659.7		9.18E+08
16	540.00	-101.29	0.003	1.29E-04	-1432.1	10765.2		8.07E+08
		143.24	0.003	1.29E-04	-1432.1	10765.2		
17	536.00	179.33	0.002	8.73E-05	-787.0	6182.6		8.07E+08
18	532.00	204.23	0.002	6.09E-05	-19.9	4469.2		8.07E+08
		-71.07	0.002	6.09E-05	-19.9	4469.2		
19	528.50	-32.76	0.002	4.26E-05	-201.6	3964.3		8.07E+08
20	525.00	-6.97	0.002	2.74E-05	-271.1	3058.1		8.07E+08
21	520.00	13.70	0.002	1.30E-05	-254.3	1615.4		8.07E+08
22	515.00	23.40	0.002	6.42E-06	-161.5	515.3		8.07E+08
23	512.00	27.03	0.002	5.21E-06	-85.9	136.0		8.07E+08
24	509.00	30.23	0.002	4.96E-06	-0.0	0.0		---

(continued)

Stage No.2 Fill to elevation 565.00 on LEFT side with soil type 10

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
		686.40	0.00	0.00	0.00	0.00	686.40	658
11	560.00	998.40	288.00	171.36	864.00	176.04	1174.44	3949
12	556.50	1216.80	489.60	291.32	1468.80	307.98	1524.78	6714
13	553.00	1435.20	691.20	411.28	2073.60	446.54	1881.74	9478
		1435.20	691.20	0.00	2691.20	0.00	1435.20a	81563
14	550.00	1622.40	894.00	0.00	2894.00	97.77	1720.17	81563
15	545.00	1934.40	1232.00	0.00	3232.00	389.01	2323.41	81563
16	540.00	2246.40	1570.00	0.00	3570.00	645.49	2891.89	81563
		2246.40	1570.00	0.00	2000.00	763.13	3009.53	40782
17	536.00	2496.00	1840.40	0.00	2000.00	932.19	3428.19	40782
18	532.00	2745.60	2110.80	53.63	2000.00	1095.86	3841.46	40782
		2745.60	2110.80	0.00	5000.00	963.42	3709.02	101954
19	528.50	2964.00	2347.40	0.00	5000.00	1114.58	4078.58	101954
20	525.00	3182.40	2584.00	0.00	5000.00	1259.72	4442.12	101954
21	520.00	3494.40	2922.00	0.00	5000.00	1459.28	4953.68	101954
22	515.00	3806.40	3260.00	0.00	5000.00	1653.57	5459.97	101954
23	512.00	3993.60	3462.80	0.00	5000.00	1769.08	5762.68	101954
24	509.00	4180.80	3665.60	0.00	5000.00	1884.39	6065.19	101954

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	556.50	1216.80	0.00	0.00	0.00	0.00	1216.80	0.0
13	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
		1435.20	0.00	0.00	2000.00	519.42	1954.62	87972
14	550.00	1622.40	202.80	0.00	2202.80	549.26	2171.66	87972
15	545.00	1934.40	540.80	0.00	2540.80	629.28	2563.68	87972
16	540.00	2246.40	878.80	0.00	2878.80	746.78	2993.18	87972
		2246.40	878.80	0.00	2000.00	619.89	2866.29	43986
17	536.00	2496.00	1149.20	0.00	2000.00	752.86	3248.86	43986
18	532.00	2745.60	1419.60	0.00	2000.00	891.63	3637.23	43986
		2745.60	1419.60	0.00	5000.00	1034.48	3780.08	109965

(continued)


Stage No.2 Fill to elevation 565.00 on LEFT side with soil type 10

		RIGHT side						
Node no.	Y coord	Water press.	Vertic -al	Effective stresses		Earth pressure	Total earth pressure	Coeff. of subgrade reaction
				Active limit	Passive limit			
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
19	528.50	2964.00	1656.20	0.00	5000.00	1147.34	4111.34	109965
20	525.00	3182.40	1892.80	0.00	5000.00	1266.69	4449.09	109965
21	520.00	3494.40	2230.80	0.00	5000.00	1445.58	4939.98	109965
22	515.00	3806.40	2568.80	0.00	5000.00	1630.17	5436.57	109965
23	512.00	3993.60	2771.60	0.00	5000.00	1742.06	5735.66	109965
24	509.00	4180.80	2974.40	0.00	5000.00	1854.16	6034.96	109965


Note: 1435.20a Soil pressure at active limit
123.45p Soil pressure at passive limit

Units: lb, ft

Stage No.2 Fill to elev. 565.00 on LEFT side



Stage No.2 Fill to elev. 565.00 on LEFT side




GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: 25-10.22_SecC-C-1
Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26
Load Case C.1 SSP El. 540

| Sheet No.
| Job No. 2201593
| Made by : EQB
| Date:22-10-2025
Checked :

Units: lb, ft

Stage No.7 Excav. to elev. 550.00 on RIGHT side



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 7 Excavate to elevation 550.00 on RIGHT side

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
7	591.00	550.00	584.00	4.260	n/a	528.65	21.35	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.034	-2.28E-03	0.0	0.0		9.18E+08
2	591.00	0.00	0.038	-2.28E-03	0.0	-0.0		9.18E+08
3	587.50	139.80	0.046	-2.28E-03	244.7	285.4		9.18E+08
4	584.00	279.61	0.054	-2.29E-03	978.6	2283.4	-14646.3	9.18E+08
		279.61	0.054	-2.29E-03	-13667.7	2283.4		
5	580.50	419.41	0.062	-2.21E-03	-12444.4	-43555.5		9.18E+08
6	577.00	559.21	0.069	-1.96E-03	-10731.8	-84256.7		9.18E+08
7	576.00	599.15	0.071	-1.87E-03	-10152.7	-94702.3		9.18E+08
		656.57	0.071	-1.87E-03	-10152.7	-94702.3		
8	573.00	706.89	0.076	-1.51E-03	-8107.5	-122120.8		9.18E+08
9	570.00	764.43	0.080	-1.08E-03	-5900.5	-143630.2		9.18E+08
10	565.00	860.34	0.084	-2.49E-04	-1838.5	-163085.8		9.18E+08
11	560.00	956.24	0.083	6.31E-04	2702.9	-160896.8		9.18E+08
12	556.50	1023.38	0.080	1.21E-03	6167.2	-145386.9		9.18E+08
13	553.00	1090.51	0.074	1.71E-03	9866.5	-117359.5		9.18E+08
		1274.80	0.074	1.71E-03	9866.5	-117359.5		
14	550.00	1477.60	0.069	2.03E-03	13995.1	-81308.7		9.18E+08
		-522.40	0.069	2.03E-03	13995.1	-81308.7		
15	545.00	-522.40	0.058	2.31E-03	11383.1	-19094.0		9.18E+08
16	540.00	-522.40	0.046	2.28E-03	8771.1	30364.5		8.07E+08
		-848.48	0.046	2.28E-03	8771.1	30364.5		
17	536.00	-512.69	0.037	2.05E-03	6048.8	59480.9		8.07E+08
18	532.00	-213.78	0.030	1.71E-03	4595.9	79100.6		8.07E+08
		-1998.57	0.030	1.71E-03	4595.9	79100.6		
19	528.50	-1199.90	0.024	1.36E-03	-1001.5	82849.3		8.07E+08
20	525.00	-585.03	0.020	1.03E-03	-4125.1	71918.7		8.07E+08
21	520.00	24.82	0.016	6.72E-04	-5525.6	43817.2		8.07E+08
22	515.00	430.47	0.013	4.86E-04	-4387.4	16380.4		8.07E+08
23	512.00	679.27	0.012	4.46E-04	-2722.8	5133.1		8.07E+08
24	509.00	1135.91	0.010	4.36E-04	0.0	-0.0		---

At elev. 584.00

Prop force = 14646.3 lb/ft run

(continued)

Stage No.7 Excavate to elevation 550.00 on RIGHT side

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	0.00	0.00	0.00	11785
3	587.50	0.00	455.00	139.80	1480.84	139.80	139.80a	4427
4	584.00	0.00	910.00	279.61	2961.68	279.61	279.61a	8855
5	580.50	0.00	1365.00	419.41	4442.51	419.41	419.41a	13282
6	577.00	0.00	1820.00	559.21	5923.35	559.21	559.21a	17709
7	576.00	0.00	1950.00	599.15	6346.45	599.15	599.15a	18974
		0.00	1950.00	649.35	5850.00	656.57	656.57	6777
8	573.00	187.20	2122.80	706.89	6368.40	706.89	894.09a	8132
9	570.00	374.40	2295.60	764.43	6886.80	764.43	1138.83a	9487
10	565.00	686.40	2583.60	860.34	7750.80	860.34	1546.74a	11746
11	560.00	998.40	2871.60	956.24	8614.80	956.24	1954.64a	14005
12	556.50	1216.80	3073.20	1023.38	9219.60	1023.38	2240.18a	15586
13	553.00	1435.20	3274.80	1090.51	9824.40	1090.51	2525.71a	17167
		1435.20	3274.80	1274.80	5274.80	1274.80	2710.00a	49066
14	550.00	1622.40	3477.60	1477.60	5477.60	1477.60	3100.00a	49066
15	545.00	1934.40	3815.60	1815.60	5815.60	1815.60	3750.00a	49066
16	540.00	2246.40	4153.60	2153.60	6153.60	2153.60	4400.00a	49066
		2246.40	4153.60	1042.34	2000.00	1151.52	3397.92	24533
17	536.00	2496.00	4424.00	1173.22	2000.00	1332.68	3828.68	24533
18	532.00	2745.60	4694.40	1304.09	2000.00	1490.61	4236.21	24533
		2745.60	4694.40	0.00	5000.00	1360.09	4105.69	61333
19	528.50	2964.00	4931.00	0.00	5000.00	1772.27	4736.27	61333
20	525.00	3182.40	5167.60	81.12	5000.00	2119.48	5301.88	61333
21	520.00	3494.40	5505.60	244.71	5000.00	2520.68	6015.08	61333
22	515.00	3806.40	5843.60	408.30	5000.00	2849.82	6656.22	61333
23	512.00	3993.60	6046.40	506.46	5000.00	3058.52	7052.12	391886
24	509.00	4180.80	6249.20	604.61	5000.00	3380.01	7560.81	391886

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	556.50	1216.80	0.00	0.00	0.00	0.00	1216.80	0.0
13	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
14	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	2000.00	2000.00	3622.40p	82501
15	545.00	1934.40	338.00	0.00	2338.00	2338.00	4272.40p	82501
16	540.00	2246.40	676.00	0.00	2676.00	2676.00	4922.40p	82501
		2246.40	676.00	0.00	2000.00	2000.00	4246.40p	41250
17	536.00	2496.00	946.40	0.00	2000.00	1845.37	4341.37	41250

Stage No.7
Excavate to elevation 550.00 on RIGHT side

(continued)

		RIGHT side						
Node no.	Y coord	Water press.	Vertic -al	Effective stresses		Earth pressure	Total earth pressure	Coeff. of subgrade reaction
				Active limit	Passive limit			
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
18	532.00	2745.60	1216.80	0.00	2000.00	1704.39	4449.99	41250
		2745.60	1216.80	0.00	5000.00	3358.66	6104.26	103126
19	528.50	2964.00	1453.40	0.00	5000.00	2972.17	5936.17	103126
20	525.00	3182.40	1690.00	0.00	5000.00	2704.51	5886.91	103126
21	520.00	3494.40	2028.00	0.00	5000.00	2495.86	5990.26	103126
22	515.00	3806.40	2366.00	0.00	5000.00	2419.35	6225.75	103126
23	512.00	3993.60	2568.80	0.00	5000.00	2379.25	6372.85	391886
24	509.00	4180.80	2771.61	0.00	5000.00	2244.11	6424.91	391886

Note:


4400.00a Soil pressure at active limit
4246.40p Soil pressure at passive limit

GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: 25-10.22_SecC-C-1
 Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26
 Load Case C.1 SSP El. 540


| Sheet No.
 | Job No. 2201593
 | Made by : EQB
 |
 | Date:22-10-2025
 | Checked :

Units: lb, ft

Stage No.7 Excav. to elev. 550.00 on RIGHT side



Stage No.7 Excav. to elev. 550.00 on RIGHT side




GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: 25-10.22_SecC-C-1
 Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26
 Load Case C.1 SSP El. 540

| Sheet No.
 | Job No. 2201593
 | Made by : EQB
 |
 | Date:22-10-2025
 | Checked :

Units: lb, ft

Stage No.8 Apply water pressure profile no.1



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 8 Apply water pressure profile no.1

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
8	591.00	550.00	584.00	4.091	n/a	528.42	21.58	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.034	-2.38E-03	0.0	0.0		9.18E+08
2	591.00	0.00	0.039	-2.38E-03	0.0	-0.0		9.18E+08
3	587.50	139.80	0.047	-2.38E-03	244.7	285.4		9.18E+08
4	584.00	279.61	0.055	-2.39E-03	978.6	2283.4	-15158.1	9.18E+08
		279.61	0.055	-2.39E-03	-14179.5	2283.4		
5	580.50	419.41	0.064	-2.31E-03	-12956.2	-45346.7		9.18E+08
6	577.00	559.21	0.071	-2.05E-03	-11243.6	-87839.1		9.18E+08
7	576.00	642.38	0.073	-1.95E-03	-10642.8	-98789.2		9.18E+08
		690.97	0.073	-1.95E-03	-10642.8	-98789.2		
8	573.00	748.51	0.079	-1.58E-03	-8483.6	-127512.6		9.18E+08
9	570.00	806.06	0.083	-1.13E-03	-6151.7	-149963.1		9.18E+08
10	565.00	901.96	0.086	-2.62E-04	-1881.7	-170154.7		9.18E+08
11	560.00	997.86	0.085	6.56E-04	2867.9	-167661.3		9.18E+08
12	556.50	1065.00	0.082	1.26E-03	6477.9	-151319.2		9.18E+08
13	553.00	1132.13	0.077	1.78E-03	10322.8	-121949.7		9.18E+08
		1274.80	0.077	1.78E-03	10322.8	-121949.7		
14	550.00	1477.60	0.071	2.12E-03	14451.4	-84530.0		9.18E+08
		-522.40	0.071	2.12E-03	14451.4	-84530.0		
15	545.00	-522.40	0.059	2.40E-03	11839.4	-20033.8		9.18E+08
16	540.00	-522.40	0.047	2.37E-03	9227.4	31706.1		8.07E+08
		-872.99	0.047	2.37E-03	9227.4	31706.1		
17	536.00	-564.80	0.038	2.14E-03	6351.8	62451.5		8.07E+08
18	532.00	-244.90	0.030	1.78E-03	4732.4	82866.4		8.07E+08
		-2080.04	0.030	1.78E-03	4732.4	82866.4		
19	528.50	-1245.99	0.025	1.41E-03	-1088.1	86594.2		8.07E+08
20	525.00	-605.67	0.020	1.06E-03	-4328.5	75078.0		8.07E+08
21	520.00	26.35	0.016	6.90E-04	-5776.8	45701.4		8.07E+08
22	515.00	453.38	0.013	4.95E-04	-4577.5	17027.7		8.07E+08
23	512.00	711.17	0.012	4.54E-04	-2830.7	5313.3		8.07E+08
24	509.00	1175.94	0.010	4.44E-04	0.0	-0.0		---
At elev. 584.00					Prop force = 15158.1 lb/ft run			

(continued)

Stage No.8 Apply water pressure profile no.1

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	0.00	0.00	0.00	730
3	587.50	0.00	455.00	139.80	1480.84	139.80	139.80a	4378
4	584.00	0.00	910.00	279.61	2961.68	279.61	279.61a	8755
5	580.50	0.00	1365.00	419.41	4442.51	419.41	419.41a	13133
6	577.00	0.00	1820.00	559.21	5923.35	559.21	559.21a	17511
7	576.00	62.40	1887.60	579.98	6143.36	579.98	642.38a	18761
		62.40	1887.60	628.57	5662.80	628.57	690.97a	6700
8	573.00	249.60	2060.40	686.11	6181.20	686.11	935.71a	8041
9	570.00	436.80	2233.20	743.66	6699.60	743.66	1180.46a	9381
10	565.00	748.80	2521.20	839.56	7563.60	839.56	1588.36a	11614
11	560.00	1060.80	2809.20	935.46	8427.60	935.46	1996.26a	13848
12	556.50	1279.20	3010.80	1002.60	9032.40	1002.60	2281.80a	15411
13	553.00	1497.60	3212.40	1069.73	9637.20	1069.73	2567.33a	16975
		1497.60	3212.40	1212.40	5212.40	1212.40	2710.00a	48595
14	550.00	1684.80	3415.20	1415.20	5415.20	1415.20	3100.00a	48595
15	545.00	1996.80	3753.20	1753.20	5753.20	1753.20	3750.00a	48595
16	540.00	2308.80	4091.20	2091.20	6091.20	2091.20	4400.00a	48595
		2308.80	4091.20	1012.14	2000.00	1064.61	3373.41	24298
17	536.00	2558.40	4361.60	1143.01	2000.00	1254.24	3812.64	24298
18	532.00	2808.00	4632.00	1273.89	2000.00	1419.29	4227.29	24298
		2808.00	4632.00	0.00	5000.00	1271.70	4079.70	60744
19	528.50	3026.40	4868.60	0.00	5000.00	1695.88	4722.28	60744
20	525.00	3244.80	5105.20	50.92	5000.00	2051.70	5296.50	60744
21	520.00	3556.80	5443.20	214.51	5000.00	2460.36	6017.16	79377
22	515.00	3868.80	5781.20	378.10	5000.00	2800.10	6668.90	167746
23	512.00	4056.00	5984.00	476.26	5000.00	3013.29	7069.29	167746
24	509.00	4243.20	6186.80	574.41	5000.00	3338.85	7582.05	167746

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	556.50	1216.80	0.00	0.00	0.00	0.00	1216.80	0.0
13	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
14	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	2000.00	2000.00	3622.40p	94837
15	545.00	1934.40	338.00	0.00	2338.00	2338.00	4272.40p	94837
16	540.00	2246.40	676.00	0.00	2676.00	2676.00	4922.40p	94837
		2246.40	676.00	0.00	2000.00	2000.00	4246.40p	47418
17	536.00	2496.00	946.40	0.00	2000.00	1881.44	4377.44	47418

Stage No.8

Apply water pressure profile no.1

(continued)

		RIGHT side						
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses		Earth pressure lb/ft2	Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
				Active limit lb/ft2	Passive limit lb/ft2			
18	532.00	2745.60	1216.80	0.00	2000.00	1726.59	4472.19	47418
		2745.60	1216.80	0.00	5000.00	3414.14	6159.74	118546
19	528.50	2964.00	1453.40	0.00	5000.00	3004.27	5968.27	118546
20	525.00	3182.40	1690.00	0.00	5000.00	2719.77	5902.17	118546
21	520.00	3494.40	2028.00	0.00	5000.00	2496.41	5990.81	118546
22	515.00	3806.40	2366.00	0.00	5000.00	2409.12	6215.52	167746
23	512.00	3993.60	2568.80	0.00	5000.00	2364.53	6358.13	167746
24	509.00	4180.80	2771.61	0.00	5000.00	2225.31	6406.11	167746

Note:

4400.00a
Soil pressure at active limit

4246.40p
Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593


| Made by : EQB

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.8 Apply water pressure profile no.1



Stage No.8 Apply water pressure profile no.1




GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: 25-10.22_SecC-C-1
 Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26
 Load Case C.1 SSP El. 540

| Sheet No.
 | Job No. 2201593
 | Made by : EQB
 | Date:22-10-2025
 | Checked :

Units: lb, ft

Stage No.9 Apply surcharge no.1 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 9 Apply surcharge no.1 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
9	591.00	550.00	584.00	3.680	n/a	527.47	22.53	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.045	-2.79E-03	0.0	0.0		9.18E+08
2	591.00	0.00	0.050	-2.79E-03	0.0	-0.0		9.18E+08
		227.16	0.050	-2.79E-03	0.0	-0.0		
3	587.50	394.94	0.060	-2.79E-03	1088.7	1825.5		9.18E+08
4	584.00	537.71	0.070	-2.81E-03	2720.8	8477.6	-21036.5	9.18E+08
		537.71	0.070	-2.81E-03	-18315.7	8477.6		
5	580.50	662.10	0.080	-2.73E-03	-16216.1	-51924.1		9.18E+08
6	577.00	698.61	0.089	-2.43E-03	-13834.8	-104372.9		9.18E+08
7	576.00	768.10	0.091	-2.31E-03	-13101.5	-117893.6		9.18E+08
		990.60	0.091	-2.31E-03	-13101.5	-117893.6		
8	573.00	987.64	0.098	-1.87E-03	-10134.1	-152691.8		9.18E+08
9	570.00	986.14	0.102	-1.33E-03	-7173.4	-179062.3		9.18E+08
10	565.00	1003.31	0.107	-2.92E-04	-2199.8	-203139.1		9.18E+08
11	560.00	1087.19	0.105	8.07E-04	3026.4	-201019.6		9.18E+08
12	556.50	1147.23	0.101	1.53E-03	6936.6	-183589.9		9.18E+08
13	553.00	1208.18	0.095	2.17E-03	11058.6	-152123.7		9.18E+08
		1503.18	0.095	2.17E-03	11058.6	-152123.7		
14	550.00	1691.94	0.087	2.60E-03	15851.3	-111490.0		9.18E+08
		-308.06	0.087	2.60E-03	15851.3	-111490.0		
15	545.00	-328.25	0.073	3.01E-03	14260.5	-37399.5		9.18E+08
16	540.00	-345.19	0.058	3.03E-03	12576.9	28802.1		8.07E+08
		-839.69	0.058	3.03E-03	12576.9	28802.1		
17	536.00	-699.50	0.046	2.78E-03	9498.5	73248.3		8.07E+08
18	532.00	-454.96	0.036	2.34E-03	7189.6	105461.2		8.07E+08
		-2838.06	0.036	2.34E-03	7189.6	105461.2		
19	528.50	-1724.21	0.029	1.86E-03	-794.4	113129.8		8.07E+08
20	525.00	-865.85	0.023	1.40E-03	-5327.0	99697.8		8.07E+08
21	520.00	-19.94	0.017	9.07E-04	-7541.5	62037.9		8.07E+08
22	515.00	541.50	0.013	6.41E-04	-6237.6	23928.2		8.07E+08
23	512.00	964.48	0.011	5.83E-04	-3978.6	7623.3		8.07E+08
24	509.00	1687.91	0.010	5.68E-04	0.0	-0.0		---
At elev. 584.00					Prop force = 21036.5 lb/ft run			

(continued)

Stage No.9 Apply surcharge no.1 at elevation 591.00

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	227.16	227.16	663
3	587.50	0.00	952.47	292.65	3099.88	394.94	394.94	3981
4	584.00	0.00	1392.99	428.01	4533.62	537.71	537.71	7961
5	580.50	0.00	1820.14	559.25	5923.80	662.10	662.10	11942
6	577.00	0.00	2239.75	688.18	7289.45	698.61	698.61	15923
7	576.00	62.40	2296.75	705.70	7474.98	705.70	768.10a	17060
		62.40	2296.75	764.82	6890.26	928.20	990.60	6093
8	573.00	249.60	2438.09	811.88	7314.26	925.24	1174.84	7311
9	570.00	436.80	2581.18	859.53	7743.54	923.74	1360.54	8530
10	565.00	748.80	2825.54	940.91	8476.63	940.91	1689.71a	10561
11	560.00	1060.80	3077.45	1024.79	9232.34	1024.79	2085.59a	12592
12	556.50	1279.20	3257.74	1084.83	9773.21	1084.83	2364.03a	14014
13	553.00	1497.60	3440.78	1145.78	10322.33	1145.78	2643.38a	15435
		1497.60	3440.78	1440.78	5440.78	1440.78	2938.38a	44898
14	550.00	1684.80	3629.54	1629.54	5629.54	1629.54	3314.34a	44898
15	545.00	1996.80	3947.35	1947.35	5947.35	1947.35	3944.15a	44898
16	540.00	2308.80	4268.41	2268.41	6268.41	2268.41	4577.21a	44898
		2308.80	4268.41	1097.91	2000.00	1097.91	3406.71a	22449
17	536.00	2558.40	4527.14	1223.14	2000.00	1238.10	3796.50	22449
18	532.00	2808.00	4787.25	1349.03	2000.00	1447.44	4255.44	22449
		2808.00	4787.25	0.00	5000.00	1109.21	3917.21	56123
19	528.50	3026.40	5015.80	7.65	5000.00	1625.48	4651.88	56123
20	525.00	3244.80	5245.11	118.63	5000.00	2052.41	5297.21	56123
21	520.00	3556.80	5573.83	277.73	5000.00	2529.44	6086.24	56123
22	515.00	3868.80	5903.67	437.38	5000.00	2910.62	6779.42	56123
23	512.00	4056.00	6102.04	533.39	5000.00	3198.97	7254.97	348441
24	509.00	4243.20	6300.70	629.54	5000.00	3651.79	7894.99	348441

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	556.50	1216.80	0.00	0.00	0.00	0.00	1216.80	0.0
13	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
14	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	2000.00	2000.00	3622.40p	84154
15	545.00	1934.40	338.00	0.00	2338.00	2338.00	4272.40p	84154
16	540.00	2246.40	676.00	0.00	2676.00	2676.00	4922.40p	84154
		2246.40	676.00	0.00	2000.00	2000.00	4246.40p	42077
17	536.00	2496.00	946.40	0.00	2000.00	2000.00	4496.00p	42077

(continued)

Stage No.9 Apply surcharge no.1 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective stresses</u>		<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	lb/ft2	lb/ft2	lb/ft3
18	532.00	2745.60	1216.80	0.00	2000.00	1964.80	4710.40	42077
		2745.60	1216.80	0.00	5000.00	4009.68	6755.28	105192
19	528.50	2964.00	1453.40	0.00	5000.00	3412.09	6376.09	105192
20	525.00	3182.40	1690.00	0.00	5000.00	2980.67	6163.07	105192
21	520.00	3494.40	2028.00	0.00	5000.00	2611.78	6106.18	105192
22	515.00	3806.40	2366.00	0.00	5000.00	2431.52	6237.92	105192
23	512.00	3993.60	2568.80	0.00	5000.00	2296.89	6290.49	348441
24	509.00	4180.80	2771.61	0.00	5000.00	2026.28	6207.08	348441

Note: 3406.71a Soil pressure at active limit
 4496.00p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.9 Apply surcharge no.1 at elev. 591.00



Stage No.9 Apply surcharge no.1 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.10 Apply load no.1 at elev. 593.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 10 Apply load no.1 at elevation 593.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
10	591.00	550.00	584.00	3.708	n/a	527.57	22.43	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
1	593.00	0.00	0.053	-2.34E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.057	-2.34E-03	2000.0	4000.0		9.18E+08
		214.89	0.057	-2.34E-03	2000.0	4000.0		
3	587.50	337.78	0.066	-2.37E-03	2967.2	12750.4		9.18E+08
4	584.00	453.21	0.074	-2.45E-03	4351.4	25627.0	-22598.6	9.18E+08
		453.21	0.074	-2.45E-03	-18247.2	25627.0		
5	580.50	573.16	0.083	-2.43E-03	-16451.0	-35052.3		9.18E+08
6	577.00	688.18	0.091	-2.19E-03	-14243.7	-88889.5		9.18E+08
7	576.00	768.10	0.093	-2.09E-03	-13515.6	-102822.5		9.18E+08
		964.64	0.093	-2.09E-03	-13515.6	-102822.5		
8	573.00	968.31	0.099	-1.69E-03	-10616.1	-138979.9		9.18E+08
9	570.00	974.27	0.103	-1.19E-03	-7702.3	-166883.5		9.18E+08
10	565.00	1003.31	0.107	-2.18E-04	-2758.4	-193752.9		9.18E+08
11	560.00	1092.27	0.105	8.37E-04	2480.6	-194426.0		9.18E+08
12	556.50	1154.39	0.101	1.54E-03	6412.3	-178875.5		9.18E+08
13	553.00	1216.18	0.094	2.17E-03	10560.8	-149200.7		9.18E+08
		1525.23	0.094	2.17E-03	10560.8	-149200.7		
14	550.00	1712.11	0.087	2.59E-03	15416.7	-109961.4		9.18E+08
		-256.53	0.087	2.59E-03	15416.7	-109961.4		
15	545.00	-289.93	0.073	2.99E-03	14050.6	-37399.4		9.18E+08
16	540.00	-320.83	0.058	3.02E-03	12523.7	28231.6		8.07E+08
		-827.51	0.058	3.02E-03	12523.7	28231.6		
17	536.00	-692.03	0.046	2.77E-03	9484.6	72562.3		8.07E+08
18	532.00	-451.07	0.036	2.33E-03	7198.4	104779.1		8.07E+08
		-2828.33	0.036	2.33E-03	7198.4	104779.1		
19	528.50	-1719.98	0.028	1.86E-03	-761.1	112538.0		8.07E+08
20	525.00	-865.21	0.023	1.40E-03	-5285.2	99248.3		8.07E+08
21	520.00	-22.22	0.017	9.06E-04	-7503.8	61805.2		8.07E+08
22	515.00	538.00	0.013	6.40E-04	-6214.3	23855.4		8.07E+08
23	512.00	960.60	0.012	5.82E-04	-3966.5	7604.4		8.07E+08
24	509.00	1683.71	0.010	5.68E-04	0.0	-0.0		---
At elev. 584.00					Prop force =	22598.6 lb/ft run		

(continued)

Stage No.10 Apply load no.1 at elevation 593.00

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective Active limit lb/ft2	Effective Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	214.89	214.89	1803
3	587.50	0.00	952.47	292.65	3099.88	337.78	337.78	10818
4	584.00	0.00	1392.99	428.01	4533.62	453.21	453.21	21636
5	580.50	0.00	1820.14	559.25	5923.80	573.16	573.16	32454
6	577.00	0.00	2239.75	688.18	7289.45	688.18	688.18a	43272
7	576.00	62.40	2296.75	705.70	7474.98	705.70	768.10a	46363
		62.40	2296.75	764.82	6890.26	902.24	964.64	16558
8	573.00	249.60	2438.09	811.88	7314.26	905.91	1155.51	19870
9	570.00	436.80	2581.18	859.53	7743.54	911.87	1348.67	23182
10	565.00	748.80	2825.54	940.91	8476.63	940.91	1689.71a	16690
11	560.00	1060.80	3077.45	1024.79	9232.34	1029.87	2090.67	19900
12	556.50	1279.20	3257.74	1084.83	9773.21	1091.99	2371.19	22147
13	553.00	1497.60	3440.78	1145.78	10322.33	1153.78	2651.38	24394
		1497.60	3440.78	1440.78	5440.78	1462.83	2960.43	67208
14	550.00	1684.80	3629.54	1629.54	5629.54	1649.71	3334.51	67208
15	545.00	1996.80	3947.35	1947.35	5947.35	1962.34	3959.14	67208
16	540.00	2308.80	4268.41	2268.41	6268.41	2277.94	4586.74	67208
		2308.80	4268.41	1097.91	2000.00	1102.68	3411.48	33604
17	536.00	2558.40	4527.14	1223.14	2000.00	1241.03	3799.43	33604
18	532.00	2808.00	4787.25	1349.03	2000.00	1448.96	4256.96	33604
		2808.00	4787.25	0.00	5000.00	1113.02	3921.02	84010
19	528.50	3026.40	5015.80	7.65	5000.00	1627.14	4653.54	84010
20	525.00	3244.80	5245.11	118.63	5000.00	2052.67	5297.47	84010
21	520.00	3556.80	5573.83	277.73	5000.00	2528.30	6085.10	117693
22	515.00	3868.80	5903.67	437.38	5000.00	2908.87	6777.67	117693
23	512.00	4056.00	6102.04	533.39	5000.00	3197.03	7253.03	117693
24	509.00	4243.20	6300.70	629.54	5000.00	3649.69	7892.89	117693

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective Active limit lb/ft2	Effective Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	556.50	1216.80	0.00	0.00	0.00	0.00	1216.80	0.0
13	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
14	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	2000.00	1968.63	3591.03	104553
15	545.00	1934.40	338.00	0.00	2338.00	2314.68	4249.08	104553
16	540.00	2246.40	676.00	0.00	2676.00	2661.17	4907.57	104553
		2246.40	676.00	0.00	2000.00	1992.59	4238.99	52276
17	536.00	2496.00	946.40	0.00	2000.00	1995.45	4491.45	52276

(continued)

Stage No.10 Apply load no.1 at elevation 593.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective stresses</u>		<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	lb/ft2	lb/ft2	lb/ft3
18	532.00	2745.60	1216.80	0.00	2000.00	1962.43	4708.03	52276
		2745.60	1216.80	0.00	5000.00	4003.76	6749.36	130691
19	528.50	2964.00	1453.40	0.00	5000.00	3409.52	6373.52	130691
20	525.00	3182.40	1690.00	0.00	5000.00	2980.28	6162.68	130691
21	520.00	3494.40	2028.00	0.00	5000.00	2612.92	6107.32	117693
22	515.00	3806.40	2366.00	0.00	5000.00	2433.27	6239.67	117693
23	512.00	3993.60	2568.80	0.00	5000.00	2298.83	6292.43	117693
24	509.00	4180.80	2771.61	0.00	5000.00	2028.38	6209.18	117693

Note: 1689.71a Soil pressure at active limit
 123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.10 Apply load no.1 at elev. 593.00



Stage No.10 Apply load no.1 at elev. 593.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.11 Apply surcharge no.4 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 11 Apply surcharge no.4 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
11	591.00	550.00	584.00	3.700	n/a	527.55	22.45	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.053	-2.34E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.057	-2.35E-03	2000.0	4000.0		9.18E+08
		214.82	0.057	-2.35E-03	2000.0	4000.0		
3	587.50	337.92	0.066	-2.38E-03	2967.3	12751.1		9.18E+08
4	584.00	454.47	0.074	-2.45E-03	4354.0	25632.6	-22642.9	9.18E+08
		454.47	0.074	-2.45E-03	-18288.9	25632.6		
5	580.50	575.13	0.083	-2.43E-03	-16487.1	-35182.5		9.18E+08
6	577.00	690.21	0.091	-2.20E-03	-14272.8	-89132.5		9.18E+08
7	576.00	770.05	0.093	-2.09E-03	-13542.7	-103093.5		9.18E+08
		968.19	0.093	-2.09E-03	-13542.7	-103093.5		
8	573.00	971.87	0.099	-1.70E-03	-10632.6	-139315.9		9.18E+08
9	570.00	977.68	0.103	-1.19E-03	-7708.2	-167252.7		9.18E+08
10	565.00	1006.33	0.107	-2.16E-04	-2748.2	-194109.7		9.18E+08
11	560.00	1094.92	0.105	8.41E-04	2504.9	-194695.5		9.18E+08
12	556.50	1156.85	0.101	1.55E-03	6445.5	-179044.1		9.18E+08
13	553.00	1218.54	0.094	2.17E-03	10602.5	-149238.3		9.18E+08
		1524.64	0.094	2.17E-03	10602.5	-149238.3		
14	550.00	1712.03	0.087	2.60E-03	15457.5	-109876.7		9.18E+08
		-264.33	0.087	2.60E-03	15457.5	-109876.7		
15	545.00	-294.84	0.073	3.00E-03	14059.5	-37209.7		9.18E+08
16	540.00	-323.49	0.058	3.02E-03	12513.7	28403.6		8.07E+08
		-827.22	0.058	3.02E-03	12513.7	28403.6		
17	536.00	-691.17	0.046	2.77E-03	9476.9	72696.2		8.07E+08
18	532.00	-449.82	0.036	2.33E-03	7195.0	104888.9		8.07E+08
		-2829.57	0.036	2.33E-03	7195.0	104888.9		
19	528.50	-1720.46	0.029	1.86E-03	-767.6	112627.9		8.07E+08
20	525.00	-865.18	0.023	1.40E-03	-5292.5	99312.3		8.07E+08
21	520.00	-21.72	0.017	9.06E-04	-7509.7	61832.6		8.07E+08
22	515.00	538.81	0.013	6.41E-04	-6217.0	23858.6		8.07E+08
23	512.00	961.59	0.012	5.82E-04	-3966.4	7603.2		8.07E+08
24	509.00	1682.68	0.010	5.68E-04	0.0	-0.0		---
At elev. 584.00					Prop force =	22642.9 lb/ft run		

(continued)

Stage No.11 Apply surcharge no.4 at elevation 591.00

		<u>LEFT side</u>					<u>Total earth pressure</u> lb/ft2	<u>Coeff. of subgrade reaction</u> lb/ft3
<u>Node no.</u>	<u>Y coord</u>	<u>Water press.</u> lb/ft2	<u>Vertic -al</u> lb/ft2	<u>Effective stresses</u> <u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	214.82	214.82	715
3	587.50	0.00	953.04	292.83	3101.75	337.92	337.92	4287
4	584.00	0.00	1395.20	428.69	4540.80	454.47	454.47	8574
5	580.50	0.00	1823.69	560.34	5935.35	575.13	575.13	12861
6	577.00	0.00	2244.06	689.51	7303.48	690.21	690.21	17148
7	576.00	62.40	2301.20	707.06	7489.45	707.65	770.05	18373
		62.40	2301.20	766.30	6903.59	905.79	968.19	6562
8	573.00	249.60	2442.76	813.44	7328.28	909.47	1159.07	7874
9	570.00	436.80	2585.91	861.11	7757.73	915.28	1352.08	9187
10	565.00	748.80	2830.14	942.44	8490.42	943.93	1692.73	11374
11	560.00	1060.80	3081.79	1026.24	9245.37	1032.52	2093.32	13561
12	556.50	1279.20	3261.87	1086.20	9785.62	1094.45	2373.65	15092
13	553.00	1497.60	3444.71	1147.09	10334.13	1156.14	2653.74	16623
		1497.60	3444.71	1444.71	5444.71	1462.24	2959.84	47742
14	550.00	1684.80	3633.30	1633.30	5633.30	1649.63	3334.43	47742
15	545.00	1996.80	3950.84	1950.84	5950.84	1963.05	3959.85	47742
16	540.00	2308.80	4271.65	2271.65	6271.65	2279.23	4588.03	47742
		2308.80	4271.65	1099.48	2000.00	1104.94	3413.74	23871
17	536.00	2558.40	4530.21	1224.62	2000.00	1243.36	3801.76	23871
18	532.00	2808.00	4790.15	1350.43	2000.00	1451.32	4259.32	23871
		2808.00	4790.15	0.00	5000.00	1114.55	3922.55	59678
19	528.50	3026.40	5018.57	8.99	5000.00	1628.83	4655.23	59678
20	525.00	3244.80	5247.76	119.91	5000.00	2054.45	5299.25	59678
21	520.00	3556.80	5576.32	278.94	5000.00	2530.13	6086.93	59678
22	515.00	3868.80	5906.02	438.51	5000.00	2910.71	6779.51	59678
23	512.00	4056.00	6104.31	534.48	5000.00	3198.87	7254.87	59678
24	509.00	4243.20	6302.90	630.60	5000.00	3649.35	7892.55	59678

		<u>RIGHT side</u>					<u>Total earth pressure</u> lb/ft2	<u>Coeff. of subgrade reaction</u> lb/ft3
<u>Node no.</u>	<u>Y coord</u>	<u>Water press.</u> lb/ft2	<u>Vertic -al</u> lb/ft2	<u>Effective stresses</u> <u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	556.50	1216.80	0.00	0.00	0.00	0.00	1216.80	0.0
13	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
14	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	2000.00	1976.36	3598.76	96307
15	545.00	1934.40	338.00	0.00	2338.00	2320.29	4254.69	96307
16	540.00	2246.40	676.00	0.00	2676.00	2665.12	4911.52	96307
		2246.40	676.00	0.00	2000.00	1994.56	4240.96	48153
17	536.00	2496.00	946.40	0.00	2000.00	1996.93	4492.93	48153

(continued)

Stage No.11 Apply surcharge no.4 at elevation 591.00

		RIGHT side						
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Effective stresses</u>		<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
				<u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Passive</u> <u>limit</u> <u>lb/ft2</u>			
18	532.00	2745.60	1216.80	0.00	2000.00	1963.54	4709.14	48153
		2745.60	1216.80	0.00	5000.00	4006.52	6752.12	120384
19	528.50	2964.00	1453.40	0.00	5000.00	3411.69	6375.69	120384
20	525.00	3182.40	1690.00	0.00	5000.00	2982.03	6164.43	120384
21	520.00	3494.40	2028.00	0.00	5000.00	2614.25	6108.65	120384
22	515.00	3806.40	2366.00	0.00	5000.00	2434.29	6240.69	120384
23	512.00	3993.60	2568.80	0.00	5000.00	2299.68	6293.28	120384
24	509.00	4180.80	2771.61	0.00	5000.00	2029.06	6209.86	120384

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.11 Apply surcharge no.4 at elev. 591.00



Stage No.11 Apply surcharge no.4 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.13 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 13 Apply surcharge no.3 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act. Pass.</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
				<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
13	591.00	550.00	584.00	2.432	n/a	523.60	26.40	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
1	593.00	0.00	0.046	-3.86E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.054	-3.86E-03	2000.0	4000.0		9.18E+08
		231.54	0.054	-3.86E-03	2000.0	4000.0		
3	587.50	332.08	0.067	-3.89E-03	2986.3	12856.9		9.18E+08
4	584.00	432.36	0.081	-3.97E-03	4324.1	25720.6	-25477.9	9.18E+08
		432.36	0.081	-3.97E-03	-21153.8	25720.6		
5	580.50	571.20	0.095	-3.93E-03	-19397.6	-45219.8		9.18E+08
6	577.00	711.58	0.108	-3.64E-03	-17152.7	-109328.6		9.18E+08
7	576.00	795.39	0.112	-3.51E-03	-16399.2	-126158.2		9.18E+08
		930.86	0.112	-3.51E-03	-16399.2	-126158.2		
8	573.00	920.72	0.122	-3.02E-03	-13621.8	-171054.7		9.18E+08
9	570.00	981.66	0.130	-2.40E-03	-10768.3	-208373.5		9.18E+08
10	565.00	1092.49	0.139	-1.15E-03	-5582.9	-250138.5		9.18E+08
11	560.00	1207.93	0.141	2.38E-04	168.1	-263708.9		9.18E+08
12	556.50	1290.66	0.139	1.22E-03	4540.7	-255501.5		9.18E+08
13	553.00	1374.47	0.133	2.15E-03	9204.6	-231498.0		9.18E+08
		2002.54	0.133	2.15E-03	9204.6	-231498.0		
14	550.00	2250.03	0.125	2.85E-03	15583.5	-194089.3		9.18E+08
		250.03	0.125	2.85E-03	15583.5	-194089.3		
15	545.00	326.59	0.109	3.68E-03	17025.0	-113916.8		9.18E+08
16	540.00	404.08	0.089	4.06E-03	18851.7	-25266.0		8.07E+08
		-477.04	0.089	4.06E-03	18851.7	-25266.0		
17	536.00	-316.32	0.073	4.01E-03	17264.9	47245.7		8.07E+08
18	532.00	-156.04	0.058	3.61E-03	16320.2	113372.9		8.07E+08
		-4203.59	0.058	3.61E-03	16320.2	113372.9		
19	528.50	-3253.99	0.046	3.05E-03	3269.4	146785.8		8.07E+08
20	525.00	-1784.34	0.036	2.43E-03	-5547.6	138325.9		8.07E+08
21	520.00	-202.15	0.026	1.73E-03	-10513.9	88412.9		8.07E+08
22	515.00	870.02	0.018	1.35E-03	-8844.2	33024.6		8.07E+08
23	512.00	1441.50	0.014	1.27E-03	-5376.9	10148.9		8.07E+08
24	509.00	2143.13	0.011	1.25E-03	0.0	-0.0		---
At elev. 584.00			Prop force = 25477.9 lb/ft run					

(continued)

Stage No.13 Apply surcharge no.3 at elevation 591.00

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	231.54	231.54	4745
3	587.50	0.00	954.67	293.33	3107.07	332.08	332.08	4196
4	584.00	0.00	1407.14	432.36	4579.66	432.36	432.36a	8393
5	580.50	0.00	1859.04	571.20	6050.40	571.20	571.20a	12589
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	16786
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	17985
		62.40	2385.59	794.40	7156.77	868.46	930.86	6423
8	573.00	249.60	2569.43	855.62	7708.30	858.32	1107.92	7708
9	570.00	436.80	2760.54	919.26	8281.61	919.26	1356.06a	8992
10	565.00	748.80	3093.36	1030.09	9280.08	1030.09	1778.89a	11133
11	560.00	1060.80	3440.02	1145.53	10320.06	1145.53	2206.33a	13274
12	556.50	1279.20	3688.46	1228.26	11065.37	1228.26	2507.46a	14773
13	553.00	1497.60	3940.14	1312.07	11820.41	1312.07	2809.67a	16272
		1497.60	3940.14	1940.14	5940.14	1940.14	3437.74a	46893
14	550.00	1684.80	4187.63	2187.63	6187.63	2187.63	3872.43a	46893
15	545.00	1996.80	4602.19	2602.19	6602.19	2602.19	4598.99a	46893
16	540.00	2308.80	5017.68	3017.68	7017.68	3017.68	5326.48a	46893
		2308.80	5017.68	1460.56	2000.00	1460.56	3769.36a	23446
17	536.00	2558.40	5349.74	1621.28	2000.00	1621.28	4179.68a	23446
18	532.00	2808.00	5680.91	1781.56	2000.00	1781.56	4589.56a	23446
		2808.00	5680.91	329.56	5000.00	734.01	3542.01	58616
19	528.50	3026.40	5969.62	469.30	5000.00	1563.37	4589.77	58616
20	525.00	3244.80	6257.10	608.43	5000.00	2274.78	5519.58	58616
21	520.00	3556.80	6665.33	806.02	5000.00	3099.77	6656.57	58616
22	515.00	3868.80	7070.37	1002.06	5000.00	3670.03	7538.83	58616
23	512.00	4056.00	7311.76	1118.89	5000.00	3928.79	7984.79	58616
24	509.00	4243.20	7551.89	1235.11	5000.00	4184.73	8427.93	58616

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	556.50	1216.80	0.00	0.00	0.00	0.00	1216.80	0.0
13	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
14	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	2000.00	2000.00	3622.40p	67723
15	545.00	1934.40	338.00	0.00	2338.00	2338.00	4272.40p	67723
16	540.00	2246.40	676.00	0.00	2676.00	2676.00	4922.40p	67723
		2246.40	676.00	0.00	2000.00	2000.00	4246.40p	33862
17	536.00	2496.00	946.40	0.00	2000.00	2000.00	4496.00p	33862

(continued)

Stage No.13 Apply surcharge no.3 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective stresses</u>		<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	lb/ft2	lb/ft2	lb/ft3
18	532.00	2745.60	1216.80	0.00	2000.00	2000.00	4745.60p	33862
		2745.60	1216.80	0.00	5000.00	5000.00	7745.60p	84654
19	528.50	2964.00	1453.40	0.00	5000.00	4879.76	7843.76	84654
20	525.00	3182.40	1690.00	0.00	5000.00	4121.52	7303.92	84654
21	520.00	3494.40	2028.00	0.00	5000.00	3364.33	6858.73	84654
22	515.00	3806.40	2366.00	0.00	5000.00	2862.42	6668.82	84654
23	512.00	3993.60	2568.80	0.00	5000.00	2549.69	6543.29	84654
24	509.00	4180.80	2771.61	0.00	5000.00	2103.99	6284.79	84654


Note: 4589.56a Soil pressure at active limit
7745.60p Soil pressure at passive limit

GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: 25-10.22_SecC-C-1
 Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26
 Load Case C.1 SSP El. 540


| Sheet No.
 | Job No. 2201593
 | Made by : EQB
 |
 | Date:22-10-2025
 | Checked :

Units: lb, ft

Stage No.13 Apply surcharge no.3 at elev. 591.00



Stage No.13 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.16 Change soil type 8 to soil type 9



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 16 Change properties of soil type 8 to soil type 9
Ko pressures will not be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
16	591.00	550.00	584.00	2.378	n/a	520.97	29.03	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
1	593.00	0.00	0.011	-9.37E-03	2000.0	-0.0	2000.0	9.18E+08
2	591.00	0.00	0.030	-9.37E-03	2000.0	4000.0		9.18E+08
		347.45	0.030	-9.37E-03	2000.0	4000.0		
3	587.50	473.65	0.062	-9.41E-03	3436.9	13566.8		9.18E+08
4	584.00	432.36	0.096	-9.49E-03	5022.4	28874.7	-31227.4	9.18E+08
		432.36	0.096	-9.49E-03	-26205.0	28874.7		
5	580.50	571.20	0.129	-9.43E-03	-24448.8	-59745.0		9.18E+08
6	577.00	711.58	0.161	-9.04E-03	-22203.9	-141533.2		9.18E+08
7	576.00	795.39	0.170	-8.88E-03	-21450.4	-163414.0		9.18E+08
		856.80	0.170	-8.88E-03	-21450.4	-163414.0		
8	573.00	918.02	0.196	-8.25E-03	-18788.2	-223690.4		9.18E+08
9	570.00	981.66	0.219	-7.43E-03	-15938.7	-276516.4		9.18E+08
10	565.00	1092.49	0.253	-5.74E-03	-10753.3	-344133.4		9.18E+08
11	560.00	1207.93	0.276	-3.76E-03	-5002.3	-383555.8		9.18E+08
12	556.50	1290.66	0.287	-2.28E-03	-629.8	-393444.9		9.18E+08
13	553.00	1374.47	0.292	-7.98E-04	4034.2	-387537.8		9.18E+08
		1734.21	0.292	-7.98E-04	4034.2	-387537.8		
14	550.00	1968.14	0.293	4.33E-04	9587.7	-366847.8		9.18E+08
15	545.00	1500.78	0.286	2.24E-03	18260.0	-297375.9		9.18E+08
16	540.00	1042.52	0.271	3.56E-03	24618.3	-190071.1		8.07E+08
		-427.16	0.271	3.56E-03	24618.3	-190071.1		
17	536.00	-793.91	0.256	4.27E-03	22176.1	-94810.6		8.07E+08
18	532.00	-627.36	0.238	4.53E-03	19333.6	-12859.2		8.07E+08
		-1980.13	0.238	4.53E-03	19333.6	-12859.2		
19	528.50	-2404.42	0.222	4.47E-03	11660.6	42543.1		8.07E+08
20	525.00	-2288.98	0.207	4.24E-03	3447.2	65870.8		8.07E+08
21	520.00	-813.06	0.186	3.86E-03	-4307.9	55484.5		8.07E+08
22	515.00	301.20	0.168	3.62E-03	-5587.6	23489.4		8.07E+08
23	512.00	898.69	0.157	3.56E-03	-3787.8	7823.9		8.07E+08
24	509.00	1626.48	0.146	3.54E-03	0.0	0.0		---
At elev. 584.00					Prop force =	31227.4 lb/ft run		

(continued)

Stage No.16 Change properties of soil type 8 to soil type 9
Ko pressures will not be reset

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	347.45	347.45	4785
3	587.50	0.00	954.67	293.33	3107.07	473.65	473.65	28713
4	584.00	0.00	1407.14	432.36	4579.66	432.36	432.36a	7491
5	580.50	0.00	1859.04	571.20	6050.40	571.20	571.20a	11237
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	14982
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	16052
		62.40	2385.59	794.40	7156.77	794.40	856.80a	5733
8	573.00	249.60	2569.43	855.62	7708.30	855.62	1105.22a	6880
9	570.00	436.80	2760.54	919.26	8281.61	919.26	1356.06a	8026
10	565.00	748.80	3093.36	1030.09	9280.08	1030.09	1778.89a	9937
11	560.00	1060.80	3440.02	1145.53	10320.06	1145.53	2206.33a	11848
12	556.50	1279.20	3688.46	1228.26	11065.37	1228.26	2507.46a	13186
13	553.00	1497.60	3940.14	1312.07	11820.41	1312.07	2809.67a	14523
		1497.60	3940.14	1538.47	10090.97	1671.81	3169.41	1681
14	550.00	1684.80	4187.63	1635.11	10724.80	1905.74	3590.54	1681
15	545.00	1996.80	4602.19	1796.98	11786.53	2304.02	4300.82	1681
16	540.00	2308.80	5017.68	1959.21	12850.63	2711.40	5020.20	1681
		2308.80	5017.68	948.34	12850.27	1241.67	3550.47	1201
17	536.00	2558.40	5349.74	1011.10	13700.70	1401.86	3960.26	1201
18	532.00	2808.00	5680.91	1073.69	14548.82	1565.03	4373.03	1201
		2808.00	5680.91	1073.69	14548.82	1073.69	3881.69a	1749
19	528.50	3026.40	5969.62	1128.26	15288.19	1255.34	4281.74	1749
20	525.00	3244.80	6257.10	1182.59	16024.43	1976.71	5221.51	1749
21	520.00	3556.80	6665.33	1259.75	17069.91	2819.11	6375.91	1749
22	515.00	3868.80	7070.37	1336.30	18107.21	3408.71	7277.51	1749
23	512.00	4056.00	7311.76	1381.92	18725.42	3679.41	7735.41	1749
24	509.00	4243.20	7551.89	1427.31	19340.38	3947.36	8190.56	1749

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	580.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	565.00	686.40	0.00	0.00	0.00	0.00	686.40	0.0
11	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
12	556.50	1216.80	0.00	0.00	0.00	0.00	1216.80	0.0
13	553.00	1435.20	0.00	0.00	0.00	0.00	1435.20	0.0
14	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	0.00	0.00	1622.40	1920
15	545.00	1934.40	338.00	131.98	865.64	865.64	2800.04p	1920
16	540.00	2246.40	676.00	263.95	1731.28	1731.28	3977.68p	1920
		2246.40	676.00	127.76	1731.24	1731.24	3977.64p	1414

(continued)

Stage No.16 Change properties of soil type 8 to soil type 9

Ko pressures will not be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Effective stresses</u> <u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
17	536.00	2496.00	946.40	178.87	2423.73	2258.17	4754.17	1414
18	532.00	2745.60	1216.80	229.98	3116.23	2254.79	5000.39	1414
		2745.60	1216.80	229.98	3116.23	3116.23	5861.83p	2058
19	528.50	2964.00	1453.40	274.69	3722.16	3722.16	6686.16p	2058
20	525.00	3182.40	1690.00	319.41	4328.09	4328.09	7510.49p	2058
21	520.00	3494.40	2028.00	383.29	5193.71	3694.57	7188.97	2058
22	515.00	3806.40	2366.00	447.17	6059.34	3169.91	6976.31	2058
23	512.00	3993.60	2568.80	485.50	6578.71	2843.12	6836.72	2058
24	509.00	4180.80	2771.61	523.83	7098.08	2383.29	6564.09	2058

Note: 3881.69a Soil pressure at active limit

7510.49p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.16 Change soil type 8 to soil type 9



Stage No.16 Change soil type 8 to soil type 9



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe		Toe elev. for			
			elev. = 509.00		FoS = 1.500			
<u>Stage</u>	<u>Ground level</u>		<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>at equilb.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>
1	553.00	553.00	---	<u>Conditions not suitable for FoS calc.</u>				
2	565.00	553.00	Cant.	14.687	521.28	544.67	8.33	L to R
3	565.00	553.00		No analysis at this stage				
4	565.00	553.00		No analysis at this stage				
5	576.00	553.00	584.00	40.416	n/a	550.40	2.60	L to R
6	591.00	553.00	584.00	4.394	n/a	529.71	23.29	L to R
7	591.00	550.00	584.00	4.260	n/a	528.65	21.35	L to R
8	591.00	550.00	584.00	4.091	n/a	528.42	21.58	L to R
9	591.00	550.00	584.00	3.680	n/a	527.47	22.53	L to R
10	591.00	550.00	584.00	3.708	n/a	527.57	22.43	L to R
11	591.00	550.00	584.00	3.700	n/a	527.55	22.45	L to R
12	591.00	550.00		No analysis at this stage				
13	591.00	550.00	584.00	2.432	n/a	523.60	26.40	L to R
14	591.00	550.00		No analysis at this stage				
15	591.00	550.00		No analysis at this stage				
16	591.00	550.00	584.00	2.378	n/a	520.97	29.03	L to R

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecC-C-1

Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26

Load Case C.1 SSP El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	593.00	0.053	-0.000	0.0	-0.0	2000.0	0.0
2	591.00	0.057	-0.000	4000.0	-0.0	2000.0	0.0
3	587.50	0.067	-0.000	13566.8	-0.0	3436.9	0.0
4	584.00	0.096	-0.000	28874.7	-0.0	5022.4	-26205.0
5	580.50	0.129	-0.000	0.0	-59745.0	0.0	-24448.8
6	577.00	0.161	-0.000	0.0	-141533.2	0.0	-22203.9
7	576.00	0.170	-0.000	0.0	-163414.0	0.0	-21450.4
8	573.00	0.196	-0.000	0.0	-223690.4	0.0	-18788.2
9	570.00	0.219	-0.000	0.0	-276516.4	0.0	-15938.7
10	565.00	0.253	-0.000	0.0	-344133.4	251.5	-10753.3
11	560.00	0.276	-0.000	872.4	-383555.8	4792.9	-5002.3
12	556.50	0.287	-0.000	3790.2	-393444.9	8257.2	-629.8
13	553.00	0.292	-0.000	10480.7	-387537.8	11956.5	0.0
14	550.00	0.293	-0.000	16547.5	-366847.8	15851.3	0.0
15	545.00	0.286	0.000	17640.5	-297375.9	18260.0	-578.2
16	540.00	0.271	0.000	37623.1	-190071.1	24618.3	-1700.8
17	536.00	0.256	0.000	73248.3	-94810.6	22176.1	-787.0
18	532.00	0.238	0.000	113372.9	-12859.2	19333.6	-19.9
19	528.50	0.222	0.000	146785.8	-0.0	11660.6	-1229.3
20	525.00	0.207	0.000	138325.9	-0.0	3447.2	-5547.6
21	520.00	0.186	0.000	88412.9	-0.0	0.0	-10513.9
22	515.00	0.168	0.000	33024.6	-0.0	0.0	-8844.2
23	512.00	0.157	0.000	10148.9	-0.0	0.0	-5376.9
24	509.00	0.146	0.000	0.0	-0.0	0.0	-0.0

Summary of results (continued)**Maximum and minimum bending moment and shear force at each stage**

Stage	Bending moment				Shear force			
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	0.0	545.00	-0.0	520.00	0.0	545.00	-0.0	509.00
2	16659.7	545.00	-0.0	576.00	2607.5	553.00	-1432.1	540.00
3	No calculation at this stage							
4	No calculation at this stage							
5	17640.5	545.00	-24798.0	565.00	4973.3	553.00	-1700.8	540.00
6	51758.0	532.00	-125590.9	565.00	11956.5	553.00	-11809.9	584.00
7	82849.3	528.50	-163085.8	565.00	13995.1	550.00	-13667.7	584.00
8	86594.2	528.50	-170154.7	565.00	14451.4	550.00	-14179.5	584.00
9	113129.8	528.50	-203139.1	565.00	15851.3	550.00	-18315.7	584.00
10	112538.0	528.50	-194426.0	560.00	15416.7	550.00	-18247.2	584.00
11	112627.9	528.50	-194695.5	560.00	15457.5	550.00	-18288.9	584.00
12	No calculation at this stage							
13	146785.8	528.50	-263708.9	560.00	18851.7	540.00	-21153.8	584.00
14	No calculation at this stage							
15	No calculation at this stage							
16	65870.8	525.00	-393444.9	556.50	24618.3	540.00	-26205.0	584.00

Maximum and minimum displacement at each stage

Stage	Displacement				Stage description
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	
	ft		ft		
1	0.000	512.00	-0.000	593.00	Change EI of wall to 8.0771E+08lb.ft ² /ft run
2	0.021	593.00	0.000	593.00	Fill to elev. 565.00 on LEFT side
3	No calculation at this stage				Install prop no.1 at elev. 584.00
4	No calculation at this stage				Change soil type 10 to soil type 2
5	0.022	577.00	0.000	593.00	Fill to elev. 576.00 on LEFT side
6	0.066	565.00	0.000	593.00	Fill to elev. 591.00 on LEFT side
7	0.084	565.00	0.000	593.00	Excav. to elev. 550.00 on RIGHT side
8	0.086	565.00	0.000	593.00	Apply water pressure profile no.1
9	0.107	565.00	0.000	593.00	Apply surcharge no.1 at elev. 591.00
10	0.107	565.00	0.000	593.00	Apply load no.1 at elev. 593.00
11	0.107	565.00	0.000	593.00	Apply surcharge no.4 at elev. 591.00
12	No calculation at this stage				Apply surcharge no.2 at elev. 591.00
13	0.141	560.00	0.000	593.00	Apply surcharge no.3 at elev. 591.00
14	No calculation at this stage				Change soil type 3 to soil type 4
15	No calculation at this stage				Change soil type 5 to soil type 6
16	0.293	550.00	0.000	593.00	Change soil type 8 to soil type 9

Summary of results (continued)

Prop forces at each stage (horizontal components)



Stage	-- Anchor no. 1 ---
no.	at elev. 584.00
	lb/ft run lb/prop
5	1605.99 14935.75
6	12788.50 118933.09
7	14646.32 136210.74
8	15158.09 140970.20
9	21036.52 195639.66
10	22598.57 210166.72
11	22642.93 210579.23
13	25477.90 236944.48
16	31227.45 290415.24

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: 25-10.22_SecC-C-1
Pulliam Dock Wall - Section C - Pipe54x11/16 & NZ26
Load Case C.1 SSP El. 540

| Sheet No.
| Job No. 2201593
| Made by : EQB
|
| Date:22-10-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
WALLAP ANALYSIS: D.1 – EMBEDMENT CHECK						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecD-D.1 EmbedCheck

Pulliam Dock Wall - Section D - Pipe54x5/8 & NZ26

Load Case D.1 - SSP Tip El. 540 Embed Depth Check

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:15-07-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	570.00	12 Sediment	12 Sediment
2	566.00	3 Clay I	3 Clay I
3	551.00	5 Clay IIA	5 Clay IIA
4	540.00	7 KP - Clay IIA	7 KP - Clay IIA
5	518.00	8 KP - Clay III	8 KP - Clay III

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft3	Eh, lb/ft2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	lb/ft2 (dc/dy)
1 Not defined							
2 Existing Fill	130.0	1200000	0.500	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000u
3 Clay I	130.0	1200000	0.531	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000d
4 Clay I - L. Term	130.0	1200000	0.531	OC (0.490)	0.361 (0.000)	2.770 (0.000)	
5 Clay IIA	130.0	600000	0.561	NC (0.490)	1.000 (2.000)	1.000 (2.000)	1500d
6 Clay IIA - L.Term	130.0	600000	0.561	OC (0.490)	0.390 (0.000)	2.561 (0.000)	
7 KP - Clay IIA	130.0	600000	0.560	NC (0.490)	0.484 (0.968)	0.000 (1.330)	1500d
8 KP - Clay III	130.0	1300000	0.560	NC (0.490)	0.484 (0.968)	0.000 (1.330)	2500d
9 KP - ClayI-IA.L.Term	130.0	47151	0.560	NC (0.330)	0.189 (0.000)	1.707 (0.000)	0.0d
10 KP - Clay III.LTerm	130.0	68650	0.560	NC (0.330)	0.189 (0.000)	1.707 (0.000)	0.0d
11 Exist. Fill - L.Term	130.0	1200000	0.500	NC (0.490)	0.333 (1.155)	3.000 (3.464)	0.0d
12 Sediment	80.00	36000	0.500	NC (0.490)	1.000 (2.000)	1.000 (2.000)	60.00d
13 Sediment - L.Term	80.00	0 (36000)	0.500	NC (0.490)	0.422 (0.000)	2.371 (0.000)	
14 Granular Fill - AW	130.0	0 (42000)	0.470	NC (0.330)	0.307 (0.000)	3.255 (0.000)	
15 Granular Fill - BW	125.0	0 (15000)	0.500	NC (0.330)	0.333 (0.000)	3.000 (0.000)	

Additional soil parameters associated with Ka and Kp

		--- parameters for Ka ---			--- parameters for Kp ---		
		Soil	Wall	Back-	Soil	Wall	Back-
----- Soil type -----		friction	adhesion	fill	friction	adhesion	fill
No.	Description	angle	coeff.	angle	angle	coeff.	angle
1	Not defined						
2	Existing Fill	0.00	0.000	0.00	0.00	0.000	0.00
3	Clay I	0.00	0.000	0.00	0.00	0.000	0.00
4	Clay I - L.Term	28.00	0.000	0.00	28.00	0.000	0.00
5	Clay IIA	0.00	0.000	0.00	0.00	0.000	0.00
6	Clay IIA - L.Term	26.00	0.000	0.00	26.00	0.000	0.00
7	KP - Clay IIA	28.06	-0.627	0.00	Incompatible values		
8	KP - Clay III	28.06	-0.627	0.00	Incompatible values		
9	KP - ClayIIA.L.Term	43.01	0.000	0.00	15.14	0.000	0.00
10	KP - Clay III.LTerm	43.01	0.000	0.00	15.14	0.000	0.00
11	Exist. Fill - L.Term	30.00	0.000	0.00	30.00	0.000	0.00
12	Sediment	0.00	0.000	0.00	0.00	0.000	0.00
13	Sediment - L.Term	24.00	0.000	0.00	24.00	0.000	0.00
14	Granular Fill - AW	32.00	0.000	0.00	32.00	0.000	0.00
15	Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	576.00	576.00

Automatic water pressure balancing at toe of wall : No

		Left side			Right side			
Water		-----			-----			
press.								
profile	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	Water
no.	no.		elev.	press.	no.		elev.	press.
		ft	ft	lb/ft2		ft	ft	lb/ft2
1	1	577.00	577.00	0.0	1	576.00	576.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
Elevation of toe of wall = 490.00
Maximum finite element length = 6.00 ft
Youngs modulus of wall E = 4.1760E+09 lb/ft2
Moment of inertia of wall I = 0.22000 ft4/ft run
E.I = 9.1872E+08 lb.ft2/ft run
Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop	Prop	Cross-	Youngs	Free	Inclin	Pre-	Strut	Allow	
no.	Elev.	section	modulus	length	-ation	stress	or	tension	
		area			(degs)	/prop	Anchor	?	L/R
		sq.ft	lb/ft2	ft		lb			
1	584.00	9.30	0.066810	4.176E+09	75.00	0.00	0	Anchor	n/a R

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load	Horizontal	Moment	Moment	Partial
no.	load	load	restraint	factor
	lb/ft run	lb.ft/ft run	lb.ft/ft/rad	(Category)
1	593.00	2000	0	0
				N/A

SURCHARGE LOADS

Surch	Distance	Length	Width	Surcharge		Equiv.	Partial
-arge	from	parallel	perpend.	-----	lb/ft2	-----	soil
no.	Elev.	to wall	to wall	Near edge	Far edge	type	factor/
1	591.00	0.00 (L)	1000.00	15.00	500.00	=	N/A
2	591.00	15.00 (L)	1000.00	84.00	0.00	3600.00	N/A
3	591.00	99.00 (L)	1000.00	150.00	3600.00	=	N/A
4	591.00	6.00 (L)	1000.00	15.00	10.00	=	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Change EI of wall to 8.0771E+08 lb.ft2/ft run From elevation 540.00 to 490.00 Yield moment not defined Reset wall displacements to zero at this stage
2	Fill to elevation 576.00 on LEFT side with soil type 15
3	Fill to elevation 581.00 on LEFT side with soil type 14
4	Install strut or anchor no.1 at elevation 584.00
5	Fill to elevation 591.00 on LEFT side with soil type 14
6	Excavate to elevation 550.00 on RIGHT side
7	Apply water pressure profile no.1
8	Apply surcharge no.1 at elevation 591.00
9	Apply load no.1 at elevation 593.00
10	Apply surcharge no.4 at elevation 591.00
11	Apply surcharge no.2 at elevation 591.00 No analysis at this stage
12	Apply surcharge no.3 at elevation 591.00
13	Change properties of soil type 12 to soil type 13 No analysis at this stage Ko pressures will not be reset
14	Change properties of soil type 3 to soil type 4 No analysis at this stage Ko pressures will not be reset
15	Change properties of soil type 5 to soil type 6 No analysis at this stage Ko pressures will not be reset
16	Change properties of soil type 7 to soil type 9 No analysis at this stage Ko pressures will not be reset
17	Change properties of soil type 8 to soil type 10 Ko pressures will be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 71.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft

Distance to rigid boundary on Right side = 1000.00 ft


OUTPUT OPTIONS

Stage no.	Stage description	Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Change EI of wall to 8.0771E+08lb.ft2/	No	No	No
2	Fill to elev. 576.00 on LEFT side	No	No	No
3	Fill to elev. 581.00 on LEFT side	No	No	No
4	Install prop no.1 at elev. 584.00	No	No	No
5	Fill to elev. 591.00 on LEFT side	Yes	Yes	Yes
6	Excav. to elev. 550.00 on RIGHT side	No	No	No
7	Apply water pressure profile no.1	No	No	No
8	Apply surcharge no.1 at elev. 591.00	No	No	No
9	Apply load no.1 at elev. 593.00	Yes	Yes	Yes
10	Apply surcharge no.4 at elev. 591.00	Yes	Yes	Yes
11	Apply surcharge no.2 at elev. 591.00	No	No	No
12	Apply surcharge no.3 at elev. 591.00	No	No	No
13	Change soil type 12 to soil type 13	No	No	No
14	Change soil type 3 to soil type 4	No	No	No
15	Change soil type 5 to soil type 6	No	No	No
16	Change soil type 7 to soil type 9	No	No	No
17	Change soil type 8 to soil type 10	No	No	No
*	Summary output	Yes	-	Yes

Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

Units: lb, ft

Stage No.17 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : EQB
 Data filename/Run ID: SecD-D.1 EmbedCheck |
 Pulliam Dock Wall - Section D - Pipe54x5/8 & NZ26 | Date:15-07-2025
 Load Case D.1 - SSP Tip El. 540 Embed Depth Check | Checked :

Units: lb,ft

Stage No. 17 Change properties of soil type 8 to soil type 10
 Ko pressures will be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method
 Factor of safety on gross pressure (excluding water pressure)

				FoS for toe		Toe elev. for		
				elev. = 490.00		FoS = 1.500		
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>	
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>	
			<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>	
17	591.00	550.00	584.00	2.415	n/a	511.18	38.82	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall
Analysis options

Length of wall perpendicular to section = 1000.00ft
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached
 Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
 Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u>	<u>Y</u>	<u>Nett</u>	<u>Wall</u>	<u>Wall</u>	<u>Shear</u>	<u>Bending</u>	<u>Prop</u>	<u>EI of</u>
<u>no.</u>	<u>coord</u>	<u>pressure</u>	<u>disp.</u>	<u>rotation</u>	<u>force</u>	<u>moment</u>	<u>forces</u>	<u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	-0.015	-1.41E-02	2000.0	-0.0	2000.0	9.18E+08
2	591.00	0.00	0.013	-1.41E-02	2000.0	4000.0		9.18E+08
		492.92	0.013	-1.41E-02	2000.0	4000.0		
3	587.50	701.03	0.063	-1.42E-02	4089.4	14587.4		9.18E+08
4	584.00	432.36	0.113	-1.43E-02	6072.9	33760.1	-33283.4	9.18E+08
		432.36	0.113	-1.43E-02	-27210.5	33760.1		
5	581.00	551.32	0.156	-1.42E-02	-25735.0	-45519.0		9.18E+08
6	577.00	711.58	0.212	-1.38E-02	-23209.2	-144367.6		9.18E+08
7	576.00	795.39	0.226	-1.37E-02	-22455.8	-167204.5		9.18E+08
		857.60	0.226	-1.37E-02	-22455.8	-167204.5		
8	570.00	992.58	0.304	-1.22E-02	-16905.2	-285829.3		9.18E+08
		1239.25	0.304	-1.22E-02	-16905.2	-285829.3		
9	566.00	1283.53	0.350	-1.08E-02	-11859.7	-343443.0		9.18E+08
		1107.78	0.350	-1.08E-02	-11859.7	-343443.0		
10	562.00	1221.32	0.391	-9.29E-03	-7201.5	-381241.1		9.18E+08
11	558.00	1337.40	0.425	-7.58E-03	-2084.0	-401190.4		9.18E+08
12	554.50	1440.45	0.449	-6.05E-03	2777.2	-400689.3		9.18E+08
13	551.00	1544.44	0.467	-4.56E-03	8000.7	-382361.4		9.18E+08
		1665.21	0.467	-4.56E-03	8000.7	-382361.4		
14	550.00	1697.47	0.471	-4.15E-03	9682.1	-373531.4		9.18E+08
15	545.00	993.70	0.487	-2.29E-03	16410.0	-308838.4		9.18E+08
16	540.00	290.29	0.495	-8.62E-04	19620.0	-219239.2		8.07E+08
		-90.77	0.495	-8.62E-04	19620.0	-219239.2		
17	534.00	-605.04	0.496	3.48E-04	17532.5	-106825.0		8.07E+08
18	528.00	-1152.04	0.492	8.02E-04	12261.3	-15443.4		8.07E+08
19	523.00	-1022.11	0.488	7.58E-04	6825.9	29747.2		8.07E+08
20	518.00	-764.74	0.485	5.13E-04	2358.8	49463.0		8.07E+08
		-524.34	0.485	5.13E-04	2358.8	49463.0		
21	514.00	-583.86	0.484	2.53E-04	142.4	55465.0		8.07E+08
22	510.00	-349.67	0.483	-1.01E-05	-1724.7	50992.1		8.07E+08
23	504.00	-61.52	0.484	-3.23E-04	-2958.3	33322.5		8.07E+08

(continued)

Stage No.17 Change properties of soil type 8 to soil type 10

Ko pressures will be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
24	498.00	177.91	0.487	-4.97E-04	-2609.1	13600.7		8.07E+08
25	494.00	324.04	0.489	-5.42E-04	-1605.2	4348.0		8.07E+08
26	490.00	478.57	0.491	-5.52E-04	0.0	0.0		---
At elev. 584.00			Prop force = 33283.4 lb/ft run					

		LEFT side						
		Effective stresses					Total	Coeff. of
Node	Y	Water	Vertic	Active	Passive	Earth	earth	subgrade
no.	coord	press.	-al	limit	limit	pressure	pressure	reaction
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	492.92	492.92	4663
3	587.50	0.00	954.67	293.33	3107.07	701.03	701.03	27978
4	584.00	0.00	1407.14	432.36	4579.66	432.36	432.36a	6881
5	581.00	0.00	1794.30	551.32	5839.72	551.32	551.32a	9831
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	13763
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	14746
		62.40	2385.59	795.20	7156.77	795.20	857.60a	5266
8	570.00	436.80	2790.54	930.18	8371.61	930.18	1366.98a	7373
		436.80	2790.54	1176.85	6616.88	1176.85	1613.65a	25324
9	566.00	686.40	2895.53	1221.13	6865.84	1221.13	1907.53a	30148
		686.40	2895.53	1045.38	8020.12	1045.38	1731.78a	40197
10	562.00	936.00	3210.00	1158.92	8891.15	1158.92	2094.92a	40197
11	558.00	1185.60	3531.52	1275.00	9781.69	1275.00	2460.60a	40197
12	554.50	1404.00	3816.95	1378.05	10572.29	1378.05	2782.05a	40197
13	551.00	1622.40	4104.99	1482.04	11370.10	1482.04	3104.44a	40197
		1622.40	4104.99	1602.81	10513.16	1602.81	3225.21a	20098
14	550.00	1684.80	4187.63	1635.07	10724.80	1635.07	3319.87a	20098
15	545.00	1996.80	4602.19	1796.94	11786.53	1796.94	3793.74a	20098
16	540.00	2308.80	5017.68	1959.17	12850.63	1959.17	4267.97a	20098
		2308.80	5017.68	948.34	8565.18	1000.76	3309.56	1104
17	534.00	2683.20	5515.47	1042.42	9414.91	1178.85	3862.05	1104
18	528.00	3057.60	6010.77	1136.03	10260.38	1210.61	4268.21	1104
19	523.00	3369.60	6420.75	1213.52	10960.23	1241.15	4610.75	1104
20	518.00	3681.60	6827.74	1290.44	11654.96	1359.71	5041.31	1104
		3681.60	6827.74	1290.44	11654.96	3105.87	6787.47	1607
21	514.00	3931.20	7150.97	1351.53	12206.71	3283.10	7214.30	1607
22	510.00	4180.80	7471.99	1412.21	12754.68	3458.19	7638.99	1607
23	504.00	4555.20	7949.24	1502.41	13569.35	3716.83	8272.03	1607
24	498.00	4929.60	8421.29	1591.62	14375.14	3971.16	8900.76	1607
25	494.00	5179.20	8733.10	1650.56	14907.41	4138.71	9317.91	1607
26	490.00	5428.80	9042.63	1709.06	15435.78	4304.88	9733.68	1607

[illegible]

(continued)

Stage No.17 Change properties of soil type 8 to soil type 10
 Ko pressures will be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u> <u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
9	566.00	624.00	0.00	0.00	0.00	0.00	624.00	0.0
10	562.00	873.60	0.00	0.00	0.00	0.00	873.60	0.0
11	558.00	1123.20	0.00	0.00	0.00	0.00	1123.20	0.0
12	554.50	1341.60	0.00	0.00	0.00	0.00	1341.60	0.0
13	551.00	1560.00	0.00	0.00	0.00	0.00	1560.00	0.0
14	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	0.00	0.00	1622.40	21456
15	545.00	1934.40	338.00	131.97	865.64	865.64	2800.04p	21456
16	540.00	2246.40	676.00	263.95	1731.28	1731.28	3977.68p	21456
		2246.40	676.00	127.76	1153.93	1153.93	3400.33p	1206
17	534.00	2620.80	1081.60	204.42	1846.29	1846.29	4467.09p	1206
18	528.00	2995.20	1487.21	281.08	2538.66	2425.06	5420.26	1206
19	523.00	3307.20	1825.21	344.96	3115.63	2325.67	5632.87	1206
20	518.00	3619.20	2163.22	408.85	3692.61	2186.86	5806.06	1206
		3619.20	2163.22	408.85	3692.61	3692.61	7311.81p	1756
21	514.00	3868.80	2433.62	459.95	4154.19	3929.36	7798.16	1756
22	510.00	4118.40	2704.03	511.06	4615.78	3870.26	7988.66	1756
23	504.00	4492.80	3109.65	587.72	5308.17	3840.75	8333.55	1756
24	498.00	4867.20	3515.27	664.39	6000.56	3855.65	8722.85	1756
25	494.00	5116.80	3785.69	715.49	6462.17	3877.07	8993.87	1756
26	490.00	5366.40	4056.11	766.60	6923.77	3888.71	9255.11	1756

Note: 4267.97a Soil pressure at active limit
 7311.81p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecD-D.1 EmbedCheck

Pulliam Dock Wall - Section D - Pipe54x5/8 & NZ26

Load Case D.1 - SSP Tip El. 540 Embed Depth Check

| Sheet No.

| Job No. 2201593


| Made by : EQB

| Date:15-07-2025


| Checked :

Units: lb, ft

Stage No.17 Change soil type 8 to soil type 10



Stage No.17 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecD-D.1 EmbedCheck

Pulliam Dock Wall - Section D - Pipe54x5/8 & NZ26

Load Case D.1 - SSP Tip El. 540 Embed Depth Check

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:15-07-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe elev. = 490.00		Toe elev. for FoS = 1.500			
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>	
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>at elev.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>
1	570.00	570.00	---	<u>Conditions not suitable for FoS calc.</u>				
2	576.00	570.00	Cant.	55.770	502.52	563.45	6.55	L to R
3	581.00	570.00	Cant.	13.822	499.88	556.15	13.85	L to R
4	581.00	570.00		No analysis at this stage				
5	591.00	570.00	584.00	3.908	n/a	562.48	7.52	L to R
6	591.00	550.00	584.00	3.225	n/a	545.62	4.38	L to R
7	591.00	550.00	584.00	3.101	n/a	545.28	4.72	L to R
8	591.00	550.00	584.00	2.851	n/a	543.48	6.52	L to R
9	591.00	550.00	584.00	2.864	n/a	543.94	6.06	L to R
10	591.00	550.00	584.00	2.860	n/a	543.91	6.09	L to R
11	591.00	550.00		No analysis at this stage				
12	591.00	550.00	584.00	1.805	n/a	514.19	35.81	L to R
13	591.00	550.00		No analysis at this stage				
14	591.00	550.00		No analysis at this stage				
15	591.00	550.00		No analysis at this stage				
16	591.00	550.00		No analysis at this stage				
17	591.00	550.00	584.00	2.415	n/a	511.18	38.82	L to R

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: SecD-D.1 EmbedCheck

Pulliam Dock Wall - Section D - Pipe54x5/8 & NZ26

Load Case D.1 - SSP Tip El. 540 Embed Depth Check

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:15-07-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	593.00	0.070	-0.015	0.0	-0.0	2000.0	0.0
2	591.00	0.072	-0.000	4000.0	-0.0	2000.0	0.0
3	587.50	0.076	-0.000	14587.4	-0.0	4089.4	0.0
4	584.00	0.113	-0.000	33760.1	-0.0	6072.9	-27210.5
5	581.00	0.156	-0.000	0.0	-45519.0	0.0	-25735.0
6	577.00	0.212	-0.000	426.1	-144367.6	319.5	-23209.2
7	576.00	0.226	-0.000	832.2	-167204.5	499.3	-22455.8
8	570.00	0.304	-0.000	9775.0	-285829.3	3190.9	-16905.2
9	566.00	0.350	0.000	26887.0	-343443.0	11814.9	-11859.7
10	562.00	0.391	0.000	43610.6	-381241.1	6908.6	-7201.5
11	558.00	0.425	0.000	46952.3	-401190.4	7158.2	-2084.0
12	554.50	0.449	0.000	43911.8	-400689.3	7376.6	-2440.5
13	551.00	0.467	0.000	30732.6	-382361.4	8000.7	-4916.4
14	550.00	0.471	0.000	25990.5	-373531.4	9682.1	-4556.7
15	545.00	0.487	0.000	14144.0	-308838.4	16410.0	-2533.8
16	540.00	0.495	0.000	27975.3	-219239.2	19620.0	-1569.8
17	534.00	0.496	0.000	33391.9	-106825.0	17532.5	-417.1
18	528.00	0.492	0.000	30518.9	-15443.4	12261.3	-461.4
19	523.00	0.488	0.000	29747.2	-2510.2	6825.9	-455.6
20	518.00	0.485	0.000	49463.0	-136.3	2358.8	-1160.7
21	514.00	0.484	0.000	55465.0	-3913.8	254.7	-727.3
22	510.00	0.483	0.000	50992.1	-5090.5	61.8	-1724.7
23	504.00	0.484	0.000	33322.5	-3984.9	545.2	-2958.3
24	498.00	0.487	0.000	13600.7	-1573.7	554.2	-2609.1
25	494.00	0.489	0.000	4348.0	-174.8	343.5	-1605.2
26	490.00	0.491	0.000	0.0	-0.0	0.0	-0.0

Summary of results (continued)**Maximum and minimum bending moment and shear force at each stage**

Stage	Bending moment				Shear force			
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	0.0	518.00	-0.0	545.00	0.0	566.00	-0.0	551.00
2	10729.2	558.00	-3641.7	528.00	1584.9	566.00	-1009.7	551.00
3	44909.6	558.00	-7029.6	534.00	6070.6	566.00	-3608.8	551.00
4	No calculation at this stage							
5	46952.3	558.00	-32715.5	576.00	11814.9	566.00	-5954.4	584.00
6	23064.5	528.00	-110962.9	570.00	6209.5	550.00	-11355.1	584.00
7	25168.9	534.00	-115888.9	570.00	6935.2	550.00	-11748.4	584.00
8	33391.9	534.00	-134132.6	570.00	8324.3	550.00	-15266.1	584.00
9	32799.4	534.00	-122214.9	570.00	7998.4	550.00	-15146.8	584.00
10	32841.4	534.00	-122500.8	570.00	8009.4	550.00	-15184.4	584.00
11	No calculation at this stage							
12	27526.9	528.00	-140292.8	570.00	8258.1	550.00	-16499.8	584.00
13	No calculation at this stage							
14	No calculation at this stage							
15	No calculation at this stage							
16	No calculation at this stage							
17	55465.0	514.00	-401190.4	558.00	19620.0	540.00	-27210.5	584.00

Maximum and minimum displacement at each stage

Stage	Displacement				
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>Stage description</u>
	ft		ft		
1	0.000	490.00	-0.000	593.00	Change EI of wall to 8.0771E+08lb.ft ² /ft run
2	0.010	593.00	0.000	593.00	Fill to elev. 576.00 on LEFT side
3	0.037	593.00	0.000	593.00	Fill to elev. 581.00 on LEFT side
4	No calculation at this stage				Install prop no.1 at elev. 584.00
5	0.052	593.00	0.000	593.00	Fill to elev. 591.00 on LEFT side
6	0.074	566.00	0.000	593.00	Excav. to elev. 550.00 on RIGHT side
7	0.076	566.00	0.000	593.00	Apply water pressure profile no.1
8	0.088	570.00	0.000	593.00	Apply surcharge no.1 at elev. 591.00
9	0.088	570.00	0.000	593.00	Apply load no.1 at elev. 593.00
10	0.088	570.00	0.000	593.00	Apply surcharge no.4 at elev. 591.00
11	No calculation at this stage				Apply surcharge no.2 at elev. 591.00
12	0.101	566.00	0.000	593.00	Apply surcharge no.3 at elev. 591.00
13	No calculation at this stage				Change soil type 12 to soil type 13
14	No calculation at this stage				Change soil type 3 to soil type 4
15	No calculation at this stage				Change soil type 5 to soil type 6
16	No calculation at this stage				Change soil type 7 to soil type 9
17	0.496	534.00	-0.015	593.00	Change soil type 8 to soil type 10

Summary of results (continued)

Prop forces at each stage (horizontal components)


Stage	-- Anchor no. 1 ---
no.	at elev. 584.00
	lb/ft run lb/prop
5	6993.31 65037.80
6	12333.72 114703.60
7	12727.06 118361.67
8	17967.03 167093.40
9	19483.72 181198.58
10	19524.42 181577.10
12	20831.17 193729.87
17	33283.40 309535.63

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: SecD-D.1 EmbedCheck
Pulliam Dock Wall - Section D - Pipe54x5/8 & NZ26
Load Case D.1 - SSP Tip El. 540 Embed Depth Check

| Sheet No.
| Job No. 2201593
| Made by : EQB
|
| Date:15-07-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
WALLAP ANALYSIS: D.1						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	570.00	12 Sediment	12 Sediment
2	566.00	3 Clay I	3 Clay I
3	551.00	5 Clay IIA	5 Clay IIA
4	540.00	7 KP - Clay IIA	7 KP - Clay IIA
5	518.00	8 KP - Clay III	8 KP - Clay III

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft3	Eh, lb/ft2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	lb/ft2 (dc/dy)
1 Not defined							
2 Existing Fill	130.0	1200000	0.500	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000u
3 Clay I	130.0	1200000	0.531	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000d
4 Clay I - L. Term	130.0	1200000	0.531	OC (0.490)	0.361 (0.000)	2.770 (0.000)	
5 Clay IIA	130.0	600000	0.561	NC (0.490)	1.000 (2.000)	1.000 (2.000)	1500d
6 Clay IIA - L.Term	130.0	600000	0.561	OC (0.490)	0.390 (0.000)	2.561 (0.000)	
7 KP - Clay IIA	130.0	600000	0.560	NC (0.490)	0.484 (0.968)	0.000 (2.000)	1500d
8 KP - Clay III	130.0	1500000	0.560	NC (0.490)	0.484 (0.968)	0.000 (2.000)	2500d
9 KP - ClayI-IA.L.Term	130.0	600000	0.560	NC (0.490)	0.189 (0.000)	2.561 (0.000)	0.0d
10 KP - Clay III.LTerm	130.0	1500000	0.560	NC (0.490)	0.189 (0.000)	2.561 (0.000)	0.0d
11 Exist. Fill - L.Term	130.0	1200000	0.500	NC (0.490)	0.333 (1.155)	3.000 (3.464)	0.0d
12 Sediment	80.00	36000	0.500	NC (0.490)	1.000 (2.000)	1.000 (2.000)	60.00d
13 Sediment - L.Term	80.00	0 (36000)	0.500	NC (0.490)	0.422 (0.000)	2.371 (0.000)	
14 Granular Fill - AW	130.0	0 (42000)	0.470	NC (0.330)	0.307 (0.000)	3.255 (0.000)	
15 Granular Fill - BW	125.0	0 (15000)	0.500	NC (0.330)	0.333 (0.000)	3.000 (0.000)	

Additional soil parameters associated with Ka and Kp

		--- parameters for Ka ---			--- parameters for Kp ---		
		Soil	Wall	Back-	Soil	Wall	Back-
----- Soil type -----		friction	adhesion	fill	friction	adhesion	fill
No.	Description	angle	coeff.	angle	angle	coeff.	angle
1	Not defined						
2	Existing Fill	0.00	0.000	0.00	0.00	0.000	0.00
3	Clay I	0.00	0.000	0.00	0.00	0.000	0.00
4	Clay I - L.Term	28.00	0.000	0.00	28.00	0.000	0.00
5	Clay IIA	0.00	0.000	0.00	0.00	0.000	0.00
6	Clay IIA - L.Term	26.00	0.000	0.00	26.00	0.000	0.00
7	KP - Clay IIA	28.06	-0.627	0.00	Incompatible values		
8	KP - Clay III	28.06	-0.627	0.00	Incompatible values		
9	KP - ClayIIA.L.Term	43.01	0.000	0.00	26.00	0.000	0.00
10	KP - Clay III.LTerm	43.01	0.000	0.00	26.00	0.000	0.00
11	Exist. Fill - L.Term	30.00	0.000	0.00	30.00	0.000	0.00
12	Sediment	0.00	0.000	0.00	0.00	0.000	0.00
13	Sediment - L.Term	24.00	0.000	0.00	24.00	0.000	0.00
14	Granular Fill - AW	32.00	0.000	0.00	32.00	0.000	0.00
15	Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	576.00	576.00

Automatic water pressure balancing at toe of wall : No

		Left side			Right side			
Water		-----			-----			
press.								
profile	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	Water
no.	no.		elev.	press.	no.		elev.	press.
		ft	ft	lb/ft2		ft	ft	lb/ft2
1	1	577.00	577.00	0.0	1	576.00	576.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
Elevation of toe of wall = 509.00
Maximum finite element length = 5.00 ft
Youngs modulus of wall E = 4.1760E+09 lb/ft2
Moment of inertia of wall I = 0.22000 ft4/ft run
E.I = 9.1872E+08 lb.ft2/ft run
Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop	Prop	Cross-	Youngs	Free	Inclin	Pre-	Strut	Allow	
no.	Elev.	section	modulus	length	-ation	stress	or	tension	
		area			(degs)	/prop	Anchor	?	L/R
		sq.ft	lb/ft2	ft		lb			
1	584.00	9.30	0.066810	4.176E+09	75.00	0.00	0	Anchor	n/a R

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load	Horizontal	Moment	Moment	Partial
no.	Elevation	load	load	factor
		lb/ft run	lb.ft/ft run	(Category)
1	593.00	2000	0	0
				N/A

SURCHARGE LOADS

Surch	Distance	Length	Width	Surcharge		Equiv.	Partial
-arge	from	parallel	perpend.	-----	lb/ft2	-----	soil
no.	Elev.	to wall	to wall	Near edge	Far edge	type	factor/
1	591.00	0.00 (L)	1000.00	15.00	500.00	=	N/A
2	591.00	15.00 (L)	1000.00	84.00	0.00	3600.00	N/A
3	591.00	99.00 (L)	1000.00	150.00	3600.00	=	N/A
4	591.00	6.00 (L)	1000.00	15.00	10.00	=	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Change EI of wall to 8.0771E+08 lb.ft2/ft run From elevation 540.00 to 509.00 Yield moment not defined Reset wall displacements to zero at this stage
2	Fill to elevation 576.00 on LEFT side with soil type 15
3	Fill to elevation 581.00 on LEFT side with soil type 14
4	Install strut or anchor no.1 at elevation 584.00
5	Fill to elevation 591.00 on LEFT side with soil type 14
6	Excavate to elevation 550.00 on RIGHT side
7	Apply water pressure profile no.1
8	Apply surcharge no.1 at elevation 591.00
9	Apply load no.1 at elevation 593.00
10	Apply surcharge no.4 at elevation 591.00
11	Apply surcharge no.2 at elevation 591.00 No analysis at this stage
12	Apply surcharge no.3 at elevation 591.00
13	Change properties of soil type 12 to soil type 13 No analysis at this stage Ko pressures will not be reset
14	Change properties of soil type 3 to soil type 4 No analysis at this stage Ko pressures will not be reset
15	Change properties of soil type 5 to soil type 6 No analysis at this stage Ko pressures will not be reset
16	Change properties of soil type 7 to soil type 9 No analysis at this stage Ko pressures will not be reset
17	Change properties of soil type 8 to soil type 10 Ko pressures will be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 71.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft

Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Output options		
		Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Change EI of wall to 8.0771E+08lb.ft2/	No	No	No
2	Fill to elev. 576.00 on LEFT side	No	No	No
3	Fill to elev. 581.00 on LEFT side	No	No	No
4	Install prop no.1 at elev. 584.00	No	No	No
5	Fill to elev. 591.00 on LEFT side	Yes	Yes	Yes
6	Excav. to elev. 550.00 on RIGHT side	No	No	No
7	Apply water pressure profile no.1	No	No	No
8	Apply surcharge no.1 at elev. 591.00	No	No	No
9	Apply load no.1 at elev. 593.00	Yes	Yes	Yes
10	Apply surcharge no.4 at elev. 591.00	Yes	Yes	Yes
11	Apply surcharge no.2 at elev. 591.00	No	No	No
12	Apply surcharge no.3 at elev. 591.00	Yes	Yes	Yes
13	Change soil type 12 to soil type 13	No	No	No
14	Change soil type 3 to soil type 4	No	No	No
15	Change soil type 5 to soil type 6	No	No	No
16	Change soil type 7 to soil type 9	No	No	No
17	Change soil type 8 to soil type 10	Yes	Yes	Yes
*	Summary output	Yes	-	Yes


Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: 25-10.22_SecD-D.1
 Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26
 Load Case D.1 - SSP Tip El. 540

| Sheet No.
 | Job No. 2201593
 | Made by : EQB
 |
 | Date:22-10-2025
 | Checked :

Units: lb, ft

Stage No.5 Fill to elev. 591.00 on LEFT side



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 5 Fill to elevation 591.00 on LEFT side with soil type 14

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
5	591.00	570.00	584.00	5.304	n/a	562.47	7.53	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
1	593.00	0.00	0.050	4.41E-04	0.0	0.0		9.18E+08
2	591.00	0.00	0.049	4.41E-04	0.0	-0.0		9.18E+08
3	587.50	159.28	0.048	4.40E-04	278.7	436.6		9.18E+08
4	584.00	308.84	0.046	4.34E-04	1097.9	2824.4	-7002.8	9.18E+08
		308.84	0.046	4.34E-04	-5904.8	2824.4		
5	581.00	429.30	0.045	4.51E-04	-4797.6	-13225.4		9.18E+08
6	577.00	581.68	0.043	5.42E-04	-2775.7	-28329.8		9.18E+08
7	576.00	619.03	0.042	5.74E-04	-2175.3	-30804.5		9.18E+08
		868.76	0.042	5.74E-04	-2175.3	-30804.5		
8	573.00	937.35	0.041	6.78E-04	533.8	-33233.6		9.18E+08
9	570.00	1007.15	0.038	7.77E-04	3450.6	-27242.2		9.18E+08
		2138.15	0.038	7.77E-04	3450.6	-27242.2		
10	566.00	2181.45	0.035	8.28E-04	12089.8	3759.2		9.18E+08
		-1590.89	0.035	8.28E-04	12089.8	3759.2		
11	563.00	-1387.59	0.033	7.67E-04	7622.1	33718.3		9.18E+08
12	560.00	-1210.45	0.031	6.30E-04	3725.0	50155.3		9.18E+08
13	555.50	-1019.70	0.028	3.74E-04	-1292.8	54237.7		9.18E+08
14	551.00	-922.09	0.027	1.49E-04	-5661.9	37887.7		9.18E+08
		226.17	0.027	1.49E-04	-5661.9	37887.7		
15	550.00	231.79	0.027	1.11E-04	-5432.9	32338.4		9.18E+08
16	545.00	242.15	0.027	1.09E-06	-4248.0	8053.4		9.18E+08
17	540.00	241.68	0.027	6.74E-06	-3038.4	-10132.1		8.07E+08
		239.36	0.027	6.74E-06	-3038.4	-10132.1		
18	535.00	249.29	0.027	1.07E-04	-1816.8	-22303.7		8.07E+08
19	530.00	285.20	0.026	2.63E-04	-480.6	-28273.5		8.07E+08
20	525.00	354.48	0.024	4.35E-04	1118.6	-27160.0		8.07E+08
21	521.50	396.11	0.022	5.39E-04	2432.1	-21158.3		8.07E+08
22	518.00	343.92	0.020	6.08E-04	3727.2	-10530.3		8.07E+08
		-696.59	0.020	6.08E-04	3727.2	-10530.3		
23	513.50	-415.65	0.017	6.40E-04	1224.6	-1052.8		8.07E+08
24	509.00	-128.64	0.014	6.43E-04	0.0	0.0		---
At elev. 584.00					Prop force =	7002.8 lb/ft run		

(continued)

Stage No.5 Fill to elevation 591.00 on LEFT side with soil type 14

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	0.00	0.00	0.00	566
3	587.50	0.00	455.00	139.80	1480.84	159.28	159.28	3395
4	584.00	0.00	910.00	279.61	2961.68	308.84	308.84	6789
5	581.00	0.00	1300.00	399.44	4230.96	429.30	429.30	9699
6	577.00	0.00	1820.00	559.21	5923.35	581.68	581.68	13579
7	576.00	0.00	1950.00	599.15	6346.45	619.03	619.03	14549
		0.00	1950.00	650.00	5850.00	868.76	868.76	5196
8	573.00	187.20	2137.80	712.60	6413.40	937.35	1124.55	6235
9	570.00	374.40	2325.60	775.20	6976.80	1007.15	1381.55	7274
		374.40	2325.60	2205.60	2445.60	2205.60	2580.00a	1195
10	566.00	624.00	2396.00	2276.00	2516.00	2276.00	2900.00a	1195
		624.00	2396.00	0.00	6396.00	424.88	1048.88	39831
11	563.00	811.20	2598.80	0.00	6598.80	546.80	1358.00	39831
12	560.00	998.40	2801.60	0.00	6801.60	671.75	1670.15	39831
13	555.50	1279.20	3105.80	0.00	7105.80	855.78	2134.98	39831
14	551.00	1560.00	3410.00	0.00	7410.00	1030.24	2590.24	39831
		1560.00	3410.00	410.00	6410.00	1522.77	3082.77	19915
15	550.00	1622.40	3477.60	477.60	6477.60	1561.52	3183.92	19915
16	545.00	1934.40	3815.60	815.60	6815.60	1753.68	3688.08	19915
17	540.00	2246.40	4153.60	1153.60	7153.60	1946.68	4193.08	19915
		2246.40	4153.60	558.34	3000.00	1942.53	4188.93	19915
18	535.00	2558.40	4491.60	721.93	3000.00	2140.41	4698.81	19915
19	530.00	2870.40	4829.60	885.53	3000.00	2346.88	5217.28	19915
20	525.00	3182.40	5167.60	1049.12	3000.00	2563.35	5745.75	19915
21	521.50	3400.80	5404.20	1163.63	3000.00	2694.16	6094.96	19915
22	518.00	3619.20	5640.80	1278.15	3000.00	2722.29	6341.49	19915
		3619.20	5640.80	310.15	5000.00	2464.58	6083.78	49788
23	513.50	3900.00	5945.00	457.38	5000.00	2731.68	6631.68	49788
24	509.00	4180.80	6249.20	604.61	5000.00	3000.46	7181.26	49788

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
		374.40	0.00	0.00	120.00	67.45	441.85	1291
10	566.00	624.00	70.40	0.00	190.40	94.55	718.55	1291
		624.00	70.40	0.00	4070.40	2015.78	2639.78	43025
11	563.00	811.20	273.20	0.00	4273.20	1934.39	2745.59	43025
12	560.00	998.40	476.00	0.00	4476.00	1882.20	2880.60	43025
13	555.50	1279.20	780.20	0.00	4780.20	1875.48	3154.68	43025
14	551.00	1560.00	1084.40	0.00	5084.40	1952.33	3512.33	43025
		1560.00	1084.40	0.00	4084.40	1296.61	2856.61	21512

(continued)

Stage No.5 Fill to elevation 591.00 on LEFT side with soil type 14

		RIGHT side						
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u>	<u>Vertic</u>	<u>Effective stresses</u>		<u>Earth</u>	<u>Total</u>	<u>Coeff. of</u>
		<u>press.</u>	<u>-al</u>	<u>Active</u>	<u>Passive</u>	<u>pressure</u>	<u>earth</u>	<u>subgrade</u>
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
15	550.00	1622.40	1152.00	0.00	4152.00	1329.74	2952.14	21512
16	545.00	1934.40	1490.00	0.00	4490.00	1511.52	3445.92	21512
17	540.00	2246.40	1828.00	0.00	4828.00	1705.00	3951.40	21512
		2246.40	1828.00	0.00	3000.00	1703.17	3949.57	21512
18	535.00	2558.40	2166.00	0.00	3000.00	1891.12	4449.52	21512
19	530.00	2870.40	2504.00	0.00	3000.00	2061.68	4932.08	21512
20	525.00	3182.40	2842.00	0.00	3000.00	2208.87	5391.27	21512
21	521.50	3400.80	3078.60	38.04	3000.00	2298.05	5698.85	21512
22	518.00	3619.20	3315.20	152.56	3000.00	2378.37	5997.57	21512
		3619.20	3315.20	0.00	5000.00	3161.16	6780.36	53781
23	513.50	3900.00	3619.40	0.00	5000.00	3147.33	7047.33	53781
24	509.00	4180.80	3923.60	0.00	5000.00	3129.10	7309.90	53781

Note: 2900.00a Soil pressure at active limit
123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.5 Fill to elev. 591.00 on LEFT side



Stage No.5 Fill to elev. 591.00 on LEFT side




GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: 25-10.22_SecD-D.1
 Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26
 Load Case D.1 - SSP Tip El. 540

| Sheet No.
 | Job No. 2201593
 | Made by : EQB
 |
 | Date:22-10-2025
 | Checked :

Units: lb, ft

Stage No.9 Apply load no.1 at elev. 593.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 9 Apply load no.1 at elevation 593.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act. Pass.</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
				<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
9	591.00	550.00	584.00	3.557	n/a	543.94	6.06	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.067	-1.10E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.069	-1.11E-03	2000.0	4000.0		9.18E+08
		213.29	0.069	-1.11E-03	2000.0	4000.0		
3	587.50	334.06	0.073	-1.14E-03	2957.9	12852.0		9.18E+08
4	584.00	457.41	0.078	-1.21E-03	4342.9	25804.6	-19506.5	9.18E+08
		457.41	0.078	-1.21E-03	-15163.5	25804.6		
5	581.00	576.02	0.081	-1.23E-03	-13613.4	-17274.9		9.18E+08
6	577.00	688.18	0.086	-1.04E-03	-11085.0	-66633.8		9.18E+08
7	576.00	768.10	0.087	-9.71E-04	-10356.9	-77354.8		9.18E+08
		1008.68	0.087	-9.71E-04	-10356.9	-77354.8		
8	573.00	1010.01	0.089	-6.75E-04	-7328.8	-104068.3		9.18E+08
9	570.00	1036.29	0.091	-3.06E-04	-4259.4	-121393.4		9.18E+08
		2553.58	0.091	-3.06E-04	-4259.4	-121393.4		
10	566.00	2588.45	0.091	2.14E-04	6024.7	-117930.9		9.18E+08
		62.40	0.091	2.14E-04	6024.7	-117930.9		
11	563.00	72.79	0.090	5.68E-04	6227.5	-99032.3		9.18E+08
12	560.00	80.59	0.088	8.61E-04	6457.5	-80473.1		9.18E+08
13	555.50	85.68	0.083	1.18E-03	6831.6	-51666.2		9.18E+08
14	551.00	85.42	0.077	1.36E-03	7216.6	-20593.7		9.18E+08
		640.35	0.077	1.36E-03	7216.6	-20593.7		
15	550.00	703.19	0.076	1.38E-03	7888.4	-13051.4		9.18E+08
		-1220.93	0.076	1.38E-03	7888.4	-13051.4		
16	545.00	-842.11	0.069	1.38E-03	2730.8	11126.7		9.18E+08
17	540.00	-474.27	0.062	1.31E-03	-560.2	14281.7		8.07E+08
		-506.85	0.062	1.31E-03	-560.2	14281.7		
18	535.00	-150.52	0.056	1.25E-03	-2203.6	5114.1		8.07E+08
19	530.00	184.70	0.049	1.26E-03	-2118.1	-7838.5		8.07E+08
20	525.00	516.89	0.043	1.33E-03	-364.2	-16213.2		8.07E+08
21	521.50	729.69	0.038	1.40E-03	1817.3	-14419.9		8.07E+08
22	518.00	842.40	0.033	1.44E-03	4568.5	-3912.8		8.07E+08
		-1305.13	0.033	1.44E-03	4568.5	-3912.8		
23	513.50	-505.59	0.027	1.44E-03	494.4	3165.4		8.07E+08

(continued)

Stage No.9 Apply load no.1 at elevation 593.00

Node no.	Y coord	Nett pressure lb/ft2	Wall disp. ft	Wall rotation rad.	Shear force lb/ft	Bending moment lb.ft/ft	Prop forces lb/ft	EI of wall lb.ft2/ft
24	509.00	285.87	0.020	1.43E-03	0.0	0.0		---
At elev. 584.00					Prop force = 19506.5 lb/ft run			

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	213.29	213.29	1823
3	587.50	0.00	952.47	292.65	3099.88	334.06	334.06	10939
4	584.00	0.00	1392.99	428.01	4533.62	457.41	457.41	21879
5	581.00	0.00	1759.74	540.70	5727.24	576.02	576.02	31255
6	577.00	0.00	2239.75	688.18	7289.45	688.18	688.18a	43757
7	576.00	62.40	2296.75	705.70	7474.98	705.70	768.10a	46883
		62.40	2296.75	765.58	6890.26	946.28	1008.68	16744
8	573.00	249.60	2453.09	817.70	7359.26	947.61	1197.21	20093
9	570.00	436.80	2611.18	870.39	7833.54	973.89	1410.69	23441
		436.80	2611.18	2491.18	2731.18	2491.18	2927.98a	3402
10	566.00	686.40	2646.05	2526.05	2766.05	2526.05	3212.45a	3402
		686.40	2646.05	0.00	6646.05	0.00	686.40a	113400
11	563.00	873.60	2825.44	0.00	6825.44	10.39	883.99	61460
12	560.00	1060.80	3007.45	0.00	7007.45	18.19	1078.99	61460
13	555.50	1341.60	3284.77	0.00	7284.77	23.28	1364.88	61460
14	551.00	1622.40	3566.45	0.00	7566.45	23.02	1645.42	61460
		1622.40	3566.45	566.45	6566.45	577.95	2200.35	30730
15	550.00	1684.80	3629.54	629.54	6629.54	640.79	2325.59	30730
16	545.00	1996.80	3947.35	947.35	6947.35	956.56	2953.36	30730
17	540.00	2308.80	4268.41	1268.41	7268.41	1275.10	3583.90	30730
		2308.80	4268.41	613.91	3000.00	1240.69	3549.49	30730
18	535.00	2620.80	4592.05	770.55	3000.00	1567.22	4188.02	30730
19	530.00	2932.80	4917.75	928.19	3000.00	1885.73	4818.53	30730
20	525.00	3244.80	5245.11	1086.63	3000.00	2201.43	5446.23	30730
21	521.50	3463.20	5475.08	1197.94	3000.00	2397.57	5860.77	30730
22	518.00	3681.60	5705.64	1309.53	3000.00	2489.18	6170.78	30730
		3681.60	5705.64	341.53	5000.00	1780.86	5462.46	76825
23	513.50	3962.40	6002.81	485.36	5000.00	2254.20	6216.60	224092
24	509.00	4243.20	6300.70	629.54	5000.00	2723.83	6967.03	224092

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	566.00	624.00	0.00	0.00	0.00	0.00	624.00	0.0
11	563.00	811.20	0.00	0.00	0.00	0.00	811.20	0.0

(continued)

Stage No.9 Apply load no.1 at elevation 593.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Effective</u> <u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Effective</u> <u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
12	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
13	555.50	1279.20	0.00	0.00	0.00	0.00	1279.20	0.0
14	551.00	1560.00	0.00	0.00	0.00	0.00	1560.00	0.0
15	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	3000.00	1924.11	3546.51	44711
16	545.00	1934.40	338.00	0.00	3338.00	1861.07	3795.47	44711
17	540.00	2246.40	676.00	0.00	3676.00	1811.76	4058.16	44711
		2246.40	676.00	0.00	3000.00	1809.93	4056.33	44711
18	535.00	2558.40	1014.00	0.00	3000.00	1780.14	4338.54	44711
19	530.00	2870.40	1352.00	0.00	3000.00	1763.42	4633.82	44711
20	525.00	3182.40	1690.01	0.00	3000.00	1746.94	4929.34	44711
21	521.50	3400.80	1926.61	0.00	3000.00	1730.28	5131.08	44711
22	518.00	3619.20	2163.22	0.00	3000.00	1709.18	5328.38	44711
		3619.20	2163.22	0.00	5000.00	3148.39	6767.59	111777
23	513.50	3900.00	2467.42	0.00	5000.00	2822.19	6722.19	224092
24	509.00	4180.80	2771.63	0.00	5000.00	2500.36	6681.16	224092

Note: 686.40a Soil pressure at active limit
 123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.9 Apply load no.1 at elev. 593.00



Stage No.9 Apply load no.1 at elev. 593.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.10 Apply surcharge no.4 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 10 Apply surcharge no.4 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
10	591.00	550.00	584.00	3.550	n/a	543.91	6.09	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.067	-1.11E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.070	-1.11E-03	2000.0	4000.0		9.18E+08
		213.24	0.070	-1.11E-03	2000.0	4000.0		
3	587.50	334.27	0.073	-1.14E-03	2958.1	12852.9		9.18E+08
4	584.00	458.82	0.078	-1.22E-03	4346.1	25811.1	-19547.0	9.18E+08
		458.82	0.078	-1.22E-03	-15200.9	25811.1		
5	581.00	578.18	0.081	-1.23E-03	-13645.4	-17372.4		9.18E+08
6	577.00	690.60	0.086	-1.05E-03	-11107.9	-66839.7		9.18E+08
7	576.00	770.48	0.087	-9.73E-04	-10377.3	-77582.3		9.18E+08
		1012.39	0.087	-9.73E-04	-10377.3	-77582.3		
8	573.00	1013.76	0.089	-6.76E-04	-7338.1	-104340.3		9.18E+08
9	570.00	1039.93	0.091	-3.07E-04	-4257.6	-121676.2		9.18E+08
		2558.31	0.091	-3.07E-04	-4257.6	-121676.2		
10	566.00	2593.09	0.091	2.14E-04	6045.2	-118168.9		9.18E+08
		62.40	0.091	2.14E-04	6045.2	-118168.9		
11	563.00	71.76	0.090	5.69E-04	6246.5	-99201.9		9.18E+08
12	560.00	79.64	0.088	8.63E-04	6473.5	-80590.6		9.18E+08
13	555.50	84.90	0.083	1.18E-03	6843.8	-51722.3		9.18E+08
14	551.00	84.89	0.077	1.36E-03	7225.8	-20603.9		9.18E+08
		642.00	0.077	1.36E-03	7225.8	-20603.9		
15	550.00	704.83	0.076	1.38E-03	7899.2	-13051.7		9.18E+08
		-1222.43	0.076	1.38E-03	7899.2	-13051.7		
16	545.00	-843.18	0.069	1.38E-03	2735.1	11160.5		9.18E+08
17	540.00	-474.92	0.062	1.31E-03	-560.1	14322.9		8.07E+08
		-507.50	0.062	1.31E-03	-560.1	14322.9		
18	535.00	-150.79	0.056	1.25E-03	-2205.8	5146.6		8.07E+08
19	530.00	184.78	0.049	1.26E-03	-2120.9	-7821.4		8.07E+08
20	525.00	517.31	0.043	1.34E-03	-365.6	-16209.4		8.07E+08
21	521.50	730.35	0.038	1.40E-03	1817.8	-14418.9		8.07E+08
22	518.00	843.32	0.033	1.44E-03	4571.7	-3906.4		8.07E+08
		-1306.48	0.033	1.44E-03	4571.7	-3906.4		
23	513.50	-505.95	0.027	1.44E-03	493.7	3172.2		8.07E+08

(continued)

Stage No.10 Apply surcharge no.4 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
24	509.00	286.50	0.020	1.44E-03	0.0	0.0		---
At elev. 584.00				Prop force =	19547.0	lb/ft run		

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Effective</u> <u>Active</u> <u>limit</u> lb/ft2	<u>Effective</u> <u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2	<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	213.24	213.24	654
3	587.50	0.00	953.04	292.83	3101.75	334.27	334.27	3925
4	584.00	0.00	1395.20	428.69	4540.80	458.82	458.82	7850
5	581.00	0.00	1763.13	541.74	5738.28	578.18	578.18	11214
6	577.00	0.00	2244.06	689.51	7303.48	690.60	690.60	15699
7	576.00	62.40	2301.20	707.06	7489.45	708.08	770.48	16820
		62.40	2301.20	767.07	6903.59	949.99	1012.39	6007
8	573.00	249.60	2457.76	819.25	7373.28	951.36	1200.96	7209
9	570.00	436.80	2615.91	871.97	7847.73	977.53	1414.33	8410
		436.80	2615.91	2495.91	2735.91	2495.91	2932.71a	1332
10	566.00	686.40	2650.69	2530.69	2770.69	2530.69	3217.09a	1332
		686.40	2650.69	0.00	6650.69	0.00	686.40a	44389
11	563.00	873.60	2829.95	0.00	6829.95	9.36	882.96	44389
12	560.00	1060.80	3011.79	0.00	7011.79	17.24	1078.04	44389
13	555.50	1341.60	3288.85	0.00	7288.85	22.50	1364.10	44389
14	551.00	1622.40	3570.26	0.00	7570.26	22.49	1644.89	44389
		1622.40	3570.26	570.26	6570.26	579.60	2202.00	22195
15	550.00	1684.80	3633.30	633.30	6633.30	642.43	2327.23	22195
16	545.00	1996.80	3950.84	950.84	6950.84	958.21	2955.01	22195
17	540.00	2308.80	4271.65	1271.65	7271.65	1276.77	3585.57	22195
		2308.80	4271.65	615.48	3000.00	1242.37	3551.17	22195
18	535.00	2620.80	4595.07	772.01	3000.00	1568.92	4189.72	22195
19	530.00	2932.80	4920.57	929.56	3000.00	1887.45	4820.25	22195
20	525.00	3244.80	5247.76	1087.91	3000.00	2203.18	5447.98	22195
21	521.50	3463.20	5477.62	1199.17	3000.00	2399.36	5862.56	22195
22	518.00	3681.60	5708.07	1310.71	3000.00	2491.00	6172.60	22195
		3681.60	5708.07	342.71	5000.00	1781.77	5463.37	55486
23	513.50	3962.40	6005.12	486.48	5000.00	2255.43	6217.83	55486
24	509.00	4243.20	6302.90	630.60	5000.00	2725.40	6968.60	55486

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Effective</u> <u>Active</u> <u>limit</u> lb/ft2	<u>Effective</u> <u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2	<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	566.00	624.00	0.00	0.00	0.00	0.00	624.00	0.0
11	563.00	811.20	0.00	0.00	0.00	0.00	811.20	0.0

(continued)

Stage No.10 Apply surcharge no.4 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Effective</u> <u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Effective</u> <u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
12	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
13	555.50	1279.20	0.00	0.00	0.00	0.00	1279.20	0.0
14	551.00	1560.00	0.00	0.00	0.00	0.00	1560.00	0.0
15	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	3000.00	1927.26	3549.66	33021
16	545.00	1934.40	338.00	0.00	3338.00	1863.80	3798.20	33021
17	540.00	2246.40	676.00	0.00	3676.00	1814.09	4060.49	33021
		2246.40	676.00	0.00	3000.00	1812.26	4058.66	33021
18	535.00	2558.40	1014.00	0.00	3000.00	1782.11	4340.51	33021
19	530.00	2870.40	1352.00	0.00	3000.00	1765.07	4635.47	33021
20	525.00	3182.40	1690.01	0.00	3000.00	1748.27	4930.67	33021
21	521.50	3400.80	1926.61	0.00	3000.00	1731.40	5132.20	33021
22	518.00	3619.20	2163.22	0.00	3000.00	1710.08	5329.28	33021
		3619.20	2163.22	0.00	5000.00	3150.65	6769.85	82553
23	513.50	3900.00	2467.42	0.00	5000.00	2823.78	6723.78	82553
24	509.00	4180.80	2771.63	0.00	5000.00	2501.29	6682.09	82553


Note: 686.40a Soil pressure at active limit
123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: 25-10.22_SecD-D.1
Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26
Load Case D.1 - SSP Tip El. 540


| Sheet No.
| Job No. 2201593
| Made by : EQB
|
| Date:22-10-2025
Checked :

Units: lb, ft

Stage No.10 Apply surcharge no.4 at elev. 591.00



Stage No.10 Apply surcharge no.4 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.12 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 12 Apply surcharge no.3 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 509.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
12	591.00	550.00	584.00	2.315	n/a	537.37	12.63	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u>	<u>Wall</u> <u>disp.</u>	<u>Wall</u> <u>rotation</u>	<u>Shear</u> <u>force</u>	<u>Bending</u> <u>moment</u>	<u>Prop</u> <u>forces</u>	<u>EI of</u> <u>wall</u>
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.064	-1.87E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.068	-1.87E-03	2000.0	4000.0		9.18E+08
		227.25	0.068	-1.87E-03	2000.0	4000.0		
3	587.50	333.17	0.074	-1.90E-03	2980.7	12942.0		9.18E+08
4	584.00	445.61	0.081	-1.98E-03	4343.6	25993.6	-20903.4	9.18E+08
		445.61	0.081	-1.98E-03	-16559.9	25993.6		
5	581.00	551.32	0.087	-1.98E-03	-15064.5	-21384.3		9.18E+08
6	577.00	711.58	0.095	-1.77E-03	-12538.7	-76615.1		9.18E+08
7	576.00	795.39	0.096	-1.68E-03	-11785.2	-88777.3		9.18E+08
		1043.71	0.096	-1.68E-03	-11785.2	-88777.3		
8	573.00	1062.60	0.101	-1.34E-03	-8625.7	-119554.5		9.18E+08
9	570.00	1108.42	0.104	-9.21E-04	-5369.2	-140461.5		9.18E+08
		2732.94	0.104	-9.21E-04	-5369.2	-140461.5		
10	566.00	2837.93	0.107	-3.11E-04	5772.5	-139816.4		9.18E+08
		62.40	0.107	-3.11E-04	5772.5	-139816.4		
11	563.00	62.40	0.107	1.15E-04	5959.7	-121681.5		9.18E+08
12	560.00	62.40	0.106	4.84E-04	6146.9	-103984.3		9.18E+08
13	555.50	62.40	0.103	9.26E-04	6427.7	-76778.0		9.18E+08
14	551.00	167.39	0.098	1.23E-03	6944.8	-47405.1		9.18E+08
		1167.39	0.098	1.23E-03	6944.8	-47405.1		
15	550.00	1250.03	0.097	1.27E-03	8153.5	-39867.9		9.18E+08
		-1201.89	0.097	1.27E-03	8153.5	-39867.9		
16	545.00	-728.04	0.090	1.42E-03	3328.7	-13715.8		9.18E+08
17	540.00	-250.29	0.083	1.47E-03	882.8	-5742.7		8.07E+08
		-712.55	0.083	1.47E-03	882.8	-5742.7		
18	535.00	-214.26	0.075	1.52E-03	-1434.2	-9886.1		8.07E+08
19	530.00	281.23	0.067	1.61E-03	-1266.8	-19423.0		8.07E+08
20	525.00	573.46	0.059	1.74E-03	869.9	-22871.0		8.07E+08
21	521.50	658.19	0.053	1.83E-03	3025.3	-16812.7		8.07E+08
22	518.00	749.14	0.046	1.87E-03	5488.2	-2702.8		8.07E+08
		-1694.77	0.046	1.87E-03	5488.2	-2702.8		
23	513.50	-605.96	0.038	1.86E-03	311.5	4792.5		8.07E+08

(continued)

Stage No.12 Apply surcharge no.3 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
24	509.00	467.50	0.029	1.85E-03	0.0	-0.0		---
At elev. 584.00				Prop force =	20903.4	lb/ft run		

LEFT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Effective stresses</u>			<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
				<u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	227.25	227.25	7263
3	587.50	0.00	954.67	293.33	3107.07	333.17	333.17	3749
4	584.00	0.00	1407.14	432.36	4579.66	445.61	445.61	7417
5	581.00	0.00	1794.30	551.32	5839.72	551.32	551.32a	10596
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	14834
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	15894
		62.40	2385.59	795.20	7156.77	981.31	1043.71	5676
8	573.00	249.60	2584.43	861.48	7753.30	1000.20	1249.80	6812
9	570.00	436.80	2790.54	930.18	8371.61	1046.02	1482.82	7947
		436.80	2790.54	2670.54	2910.54	2670.54	3107.34a	1274
10	566.00	686.40	2895.53	2775.53	3015.53	2775.53	3461.93a	1274
		686.40	2895.53	0.00	6895.53	0.00	686.40a	42458
11	563.00	873.60	3130.63	0.00	7130.63	0.00	873.60a	42458
12	560.00	1060.80	3370.02	0.00	7370.02	0.00	1060.80a	42458
13	555.50	1341.60	3735.09	0.00	7735.09	0.00	1341.60a	42458
14	551.00	1622.40	4104.99	104.99	8104.99	104.99	1727.39a	42458
		1622.40	4104.99	1104.99	7104.99	1104.99	2727.39a	21229
15	550.00	1684.80	4187.63	1187.63	7187.63	1187.63	2872.43a	21229
16	545.00	1996.80	4602.19	1602.19	7602.19	1602.19	3598.99a	21229
17	540.00	2308.80	5017.68	2017.68	8017.68	2017.68	4326.48a	21229
		2308.80	5017.68	976.56	3000.00	1553.59	3862.39	21229
18	535.00	2620.80	5432.64	1177.40	3000.00	1994.56	4615.36	21229
19	530.00	2932.80	5846.03	1377.48	3000.00	2433.91	5366.71	21229
20	525.00	3244.80	6257.10	1576.43	3000.00	2661.39	5906.19	21229
21	521.50	3463.20	6543.18	1714.90	3000.00	2692.41	6155.61	21229
22	518.00	3681.60	6827.74	1852.63	3000.00	2724.25	6405.85	21229
		3681.60	6827.74	884.63	5000.00	2212.05	5893.65	53073
23	513.50	3962.40	7191.22	1060.55	5000.00	2853.56	6815.96	53073
24	509.00	4243.20	7551.89	1235.11	5000.00	3486.13	7729.33	53073

RIGHT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Effective stresses</u>			<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
				<u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	566.00	624.00	0.00	0.00	0.00	0.00	624.00	0.0
11	563.00	811.20	0.00	0.00	0.00	0.00	811.20	0.0

(continued)


Stage No.12 Apply surcharge no.3 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Effective</u> <u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Effective</u> <u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
12	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
13	555.50	1279.20	0.00	0.00	0.00	0.00	1279.20	0.0
14	551.00	1560.00	0.00	0.00	0.00	0.00	1560.00	0.0
15	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	3000.00	2451.92	4074.32	25207
16	545.00	1934.40	338.00	0.00	3338.00	2392.63	4327.03	25207
17	540.00	2246.40	676.00	0.00	3676.00	2330.37	4576.77	25207
		2246.40	676.00	0.00	3000.00	2328.54	4574.94	25207
18	535.00	2558.40	1014.00	0.00	3000.00	2271.23	4829.63	25207
19	530.00	2870.40	1352.00	0.00	3000.00	2215.08	5085.48	25207
20	525.00	3182.40	1690.01	0.00	3000.00	2150.33	5332.73	25207
21	521.50	3400.80	1926.61	0.00	3000.00	2096.62	5497.42	25207
22	518.00	3619.20	2163.22	0.00	3000.00	2037.51	5656.71	25207
		3619.20	2163.22	0.00	5000.00	3969.22	7588.42	63017
23	513.50	3900.00	2467.42	0.00	5000.00	3521.92	7421.92	63017
24	509.00	4180.80	2771.63	0.00	5000.00	3081.03	7261.83	63017


Note: 4326.48a Soil pressure at active limit
123.45p Soil pressure at passive limit

Units: lb, ft

Stage No.12 Apply surcharge no.3 at elev. 591.00



Stage No.12 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025

| Checked :

Units: lb, ft

Stage No.17 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Stage No. 17 Change properties of soil type 8 to soil type 10
Ko pressures will be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe		Toe elev. for			
			elev. = 509.00		FoS = 1.500			
Stage	Ground level	Prop	Factor	Moment	Toe	Wall	Direction	
No.	Act.	Pass.	of	at equil.	elev.	Penetr	of	
			Safety	at elev.		-ation	failure	
17	591.00	550.00	584.00	2.358	n/a	520.72	29.28	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

*** Wall displacements reset to zero at stage 1

Node	Y	Nett	Wall	Wall	Shear	Bending	Prop	EI of
no.	coord	pressure	disp.	rotation	force	moment	forces	wall
		lb/ft2	ft	rad.	lb/ft	lb.ft/ft	lb/ft	lb.ft2/ft
1	593.00	0.00	0.046	-5.97E-03	2000.0	0.0	2000.0	9.18E+08
2	591.00	0.00	0.058	-5.97E-03	2000.0	4000.0		9.18E+08
		301.65	0.058	-5.97E-03	2000.0	4000.0		
3	587.50	310.82	0.079	-6.01E-03	3071.8	13397.7		9.18E+08
4	584.00	432.36	0.101	-6.08E-03	4372.4	26604.1	-28732.8	9.18E+08
		432.36	0.101	-6.08E-03	-24360.4	26604.1		
5	581.00	551.32	0.119	-6.05E-03	-22884.9	-44215.3		9.18E+08
6	577.00	711.58	0.142	-5.67E-03	-20359.1	-130728.0		9.18E+08
7	576.00	795.39	0.148	-5.52E-03	-19605.7	-150710.7		9.18E+08
		857.60	0.148	-5.52E-03	-19605.7	-150710.7		
8	573.00	923.88	0.164	-4.94E-03	-16933.4	-205715.7		9.18E+08
9	570.00	992.58	0.178	-4.19E-03	-14058.8	-252135.8		9.18E+08
		1239.25	0.178	-4.19E-03	-14058.8	-252135.8		
10	566.00	1283.53	0.192	-2.99E-03	-9013.2	-298360.4		9.18E+08
		1107.78	0.192	-2.99E-03	-9013.2	-298360.4		
11	563.00	1192.66	0.199	-1.98E-03	-5562.5	-319751.1		9.18E+08
12	560.00	1279.09	0.204	-9.24E-04	-1854.9	-331404.8		9.18E+08
13	555.50	1410.89	0.204	6.89E-04	4197.6	-327442.9		9.18E+08
14	551.00	1544.44	0.198	2.21E-03	10847.1	-294355.9		9.18E+08
		1665.21	0.198	2.21E-03	10847.1	-294355.9		
15	550.00	1697.47	0.195	2.52E-03	12528.4	-282675.9		9.18E+08
16	545.00	993.70	0.179	3.84E-03	19256.3	-203313.9		9.18E+08
17	540.00	290.29	0.158	4.67E-03	22466.3	-99102.2		8.07E+08
		-720.50	0.158	4.67E-03	22466.3	-99102.2		
18	535.00	-1507.69	0.133	4.98E-03	16895.8	-783.7		8.07E+08
19	530.00	-1957.17	0.109	4.78E-03	8233.7	65353.6		8.07E+08
20	525.00	-1058.06	0.086	4.31E-03	695.6	86625.5		8.07E+08
21	521.50	-481.54	0.072	3.94E-03	-1998.7	82080.7		8.07E+08
22	518.00	13.00	0.058	3.61E-03	-2818.6	71625.8		8.07E+08
		-1923.62	0.058	3.61E-03	-2818.6	71625.8		
23	513.50	-211.00	0.043	3.30E-03	-7621.5	37945.5		8.07E+08

(continued)

Stage No.17 Change properties of soil type 8 to soil type 10

Ko pressures will be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft	<u>EI of</u> <u>wall</u> lb.ft2/ft
24	509.00	3598.33	0.028	3.20E-03	0.0	-0.0		---
At elev. 584.00		Prop force = 28732.8 lb/ft run						

LEFT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
		<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	500.00	153.63	1627.29	301.65	301.65	8128
3	587.50	0.00	954.67	293.33	3107.07	310.82	310.82	4292
4	584.00	0.00	1407.14	432.36	4579.66	432.36	432.36a	8584
5	581.00	0.00	1794.30	551.32	5839.72	551.32	551.32a	12263
6	577.00	0.00	2315.91	711.58	7537.34	711.58	711.58a	17168
7	576.00	62.40	2385.59	732.99	7764.11	732.99	795.39a	18394
		62.40	2385.59	795.20	7156.77	795.20	857.60a	6569
8	573.00	249.60	2584.43	861.48	7753.30	861.48	1111.08a	7883
9	570.00	436.80	2790.54	930.18	8371.61	930.18	1366.98a	9197
		436.80	2790.54	1176.85	6616.88	1176.85	1613.65a	30107
10	566.00	686.40	2895.53	1221.13	6865.84	1221.13	1907.53a	35841
		686.40	2895.53	1045.38	8020.12	1045.38	1731.78a	47788
11	563.00	873.60	3130.63	1130.26	8671.31	1130.26	2003.86a	47788
12	560.00	1060.80	3370.02	1216.69	9334.37	1216.69	2277.49a	47788
13	555.50	1341.60	3735.09	1348.49	10345.54	1348.49	2690.09a	47788
14	551.00	1622.40	4104.99	1482.04	11370.10	1482.04	3104.44a	47788
		1622.40	4104.99	1602.81	10513.16	1602.81	3225.21a	23894
15	550.00	1684.80	4187.63	1635.07	10724.80	1635.07	3319.87a	23894
16	545.00	1996.80	4602.19	1796.94	11786.53	1796.94	3793.74a	23894
17	540.00	2308.80	5017.68	1959.17	12850.63	1959.17	4267.97a	23894
		2308.80	5017.68	948.34	12850.27	948.34	3257.14a	23894
18	535.00	2620.80	5432.64	1026.77	13912.99	1026.77	3647.57a	23894
19	530.00	2932.80	5846.03	1104.90	14971.68	1442.91	4375.71	23894
20	525.00	3244.80	6257.10	1182.59	16024.43	2014.03	5258.83	23894
21	521.50	3463.20	6543.18	1236.66	16757.09	2240.19	5703.39	23894
22	518.00	3681.60	6827.74	1290.44	17485.85	2432.16	6113.76	23894
		3681.60	6827.74	1290.44	17485.85	3093.32	6774.92	59736
23	513.50	3962.40	7191.22	1359.14	18416.71	3718.16	7680.56	59736
24	509.00	4243.20	7551.89	1427.31	19340.38	5423.01	9666.21	1174620

RIGHT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u> lb/ft2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> lb/ft3
		<u>Water</u> <u>press.</u> lb/ft2	<u>Vertic</u> <u>-al</u> lb/ft2	<u>Active</u> <u>limit</u> lb/ft2	<u>Passive</u> <u>limit</u> lb/ft2	<u>Earth</u> <u>pressure</u> lb/ft2		
1	593.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	591.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	587.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	584.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	581.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	577.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	576.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	573.00	187.20	0.00	0.00	0.00	0.00	187.20	0.0
9	570.00	374.40	0.00	0.00	0.00	0.00	374.40	0.0
10	566.00	624.00	0.00	0.00	0.00	0.00	624.00	0.0

(continued)

Stage No.17 Change properties of soil type 8 to soil type 10

Ko pressures will be reset

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u> <u>lb/ft2</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> <u>lb/ft3</u>
		<u>Water</u> <u>press.</u> <u>lb/ft2</u>	<u>Vertic</u> <u>-al</u> <u>lb/ft2</u>	<u>Effective stresses</u> <u>Active</u> <u>limit</u> <u>lb/ft2</u>	<u>Passive</u> <u>limit</u> <u>lb/ft2</u>	<u>Earth</u> <u>pressure</u> <u>lb/ft2</u>		
11	563.00	811.20	0.00	0.00	0.00	0.00	811.20	0.0
12	560.00	998.40	0.00	0.00	0.00	0.00	998.40	0.0
13	555.50	1279.20	0.00	0.00	0.00	0.00	1279.20	0.0
14	551.00	1560.00	0.00	0.00	0.00	0.00	1560.00	0.0
15	550.00	1622.40	0.00	0.00	0.00	0.00	1622.40	0.0
		1622.40	0.00	0.00	0.00	0.00	1622.40	36325
16	545.00	1934.40	338.00	131.97	865.64	865.64	2800.04p	36325
17	540.00	2246.40	676.00	263.95	1731.28	1731.28	3977.68p	36325
		2246.40	676.00	127.76	1731.24	1731.24	3977.64p	36325
18	535.00	2558.40	1014.00	191.65	2596.86	2596.86	5155.26p	36325
19	530.00	2870.40	1352.00	255.53	3462.48	3462.48	6332.88p	36325
20	525.00	3182.40	1690.01	319.41	4328.11	3134.49	6316.89	36325
21	521.50	3400.80	1926.61	364.13	4934.05	2784.13	6184.93	36325
22	518.00	3619.20	2163.22	408.85	5540.00	2481.56	6100.76	36325
		3619.20	2163.22	408.85	5540.00	5079.34	8698.54	90814
23	513.50	3900.00	2467.42	466.34	6319.07	3991.56	7891.56	90814
24	509.00	4180.80	2771.63	523.84	7098.15	1887.08	6067.88	1174620

Note: 3647.57a Soil pressure at active limit

6332.88p Soil pressure at passive limit

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB


|

| Date:22-10-2025


| Checked :

Units: lb, ft

Stage No.17 Change soil type 8 to soil type 10



Stage No.17 Change soil type 8 to soil type 10



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe elev. = 509.00		Toe elev. for FoS = 1.500			
<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u>	<u>Pass.</u>	<u>Prop</u> <u>Elev.</u>	<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>at elev.</u> <u>equilib.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	<u>Direction</u> <u>of</u> <u>failure</u>
1	570.00	570.00	---	<u>Conditions not suitable for FoS calc.</u>				
2	576.00	570.00	Cant.	57.509	512.71	563.05	6.95	L to R
3	581.00	570.00	Cant.	13.926	514.54	556.05	13.95	L to R
4	581.00	570.00		No analysis at this stage				
5	591.00	570.00	584.00	5.304	n/a	562.47	7.53	L to R
6	591.00	550.00	584.00	4.106	n/a	545.62	4.38	L to R
7	591.00	550.00	584.00	3.934	n/a	545.28	4.72	L to R
8	591.00	550.00	584.00	3.529	n/a	543.48	6.52	L to R
9	591.00	550.00	584.00	3.557	n/a	543.94	6.06	L to R
10	591.00	550.00	584.00	3.550	n/a	543.91	6.09	L to R
11	591.00	550.00		No analysis at this stage				
12	591.00	550.00	584.00	2.315	n/a	537.37	12.63	L to R
13	591.00	550.00		No analysis at this stage				
14	591.00	550.00		No analysis at this stage				
15	591.00	550.00		No analysis at this stage				
16	591.00	550.00		No analysis at this stage				
17	591.00	550.00	584.00	2.358	n/a	520.72	29.28	L to R

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Job No. 2201593

| Made by : EQB

|

| Date:22-10-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	593.00	0.067	-0.000	0.0	0.0	2000.0	0.0
2	591.00	0.070	-0.000	4000.0	-0.0	2000.0	0.0
3	587.50	0.079	-0.000	13397.7	-0.0	3071.8	0.0
4	584.00	0.101	-0.000	26604.1	-0.0	4372.4	-24360.4
5	581.00	0.119	-0.000	0.0	-44215.3	0.0	-22884.9
6	577.00	0.142	-0.000	426.1	-130728.0	319.5	-20359.1
7	576.00	0.148	-0.000	832.2	-150710.7	499.3	-19605.7
8	573.00	0.164	-0.000	3674.4	-205715.7	1399.7	-16933.4
9	570.00	0.178	-0.000	9533.1	-252135.8	3450.6	-14058.8
10	566.00	0.192	-0.000	26654.2	-298360.4	12089.8	-9013.2
11	563.00	0.199	0.000	40768.3	-319751.1	7622.1	-5562.5
12	560.00	0.204	0.000	50155.3	-331404.8	6993.6	-1854.9
13	555.50	0.204	0.000	54237.7	-327442.9	7274.4	-1899.9
14	551.00	0.198	0.000	37887.7	-294355.9	10847.1	-5661.9
15	550.00	0.195	0.000	32338.4	-282675.9	12528.4	-5432.9
16	545.00	0.179	0.000	11160.5	-203313.9	19256.3	-4248.0
17	540.00	0.158	0.000	14526.7	-99102.2	22466.3	-3038.4
18	535.00	0.133	0.000	5674.8	-22303.7	16895.8	-2205.8
19	530.00	0.109	0.000	65353.6	-28273.5	8233.7	-2123.3
20	525.00	0.086	0.000	86625.5	-27160.0	1118.6	-391.7
21	521.50	0.072	0.000	82080.7	-21158.3	3025.3	-1998.7
22	518.00	0.058	0.000	71625.8	-10530.3	5488.2	-2818.6
23	513.50	0.043	0.000	37945.5	-1052.8	1224.6	-7621.5
24	509.00	0.029	0.000	0.0	-0.0	0.0	-0.0

Summary of results (continued)**Maximum and minimum bending moment and shear force at each stage**

Stage	Bending moment				Shear force			
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	0.0	513.50	-0.0	530.00	0.0	566.00	-0.0	509.00
2	10562.4	560.00	-4658.5	530.00	1583.6	566.00	-1023.7	551.00
3	45635.0	560.00	-11540.1	525.00	6074.6	566.00	-3554.8	551.00
4	No calculation at this stage							
5	54237.7	555.50	-33233.6	573.00	12089.8	566.00	-5904.8	584.00
6	2526.1	584.00	-109330.4	570.00	6096.5	550.00	-11306.5	584.00
7	4805.9	540.00	-114404.5	570.00	6831.1	550.00	-11719.9	584.00
8	14526.7	540.00	-133334.4	570.00	8215.6	550.00	-15279.8	584.00
9	25804.6	584.00	-121393.4	570.00	7888.4	550.00	-15163.5	584.00
10	25811.1	584.00	-121676.2	570.00	7899.2	550.00	-15200.9	584.00
11	No calculation at this stage							
12	25993.6	584.00	-140461.5	570.00	8153.5	550.00	-16559.9	584.00
13	No calculation at this stage							
14	No calculation at this stage							
15	No calculation at this stage							
16	No calculation at this stage							
17	86625.5	525.00	-331404.8	560.00	22466.3	540.00	-24360.4	584.00

Maximum and minimum displacement at each stage

Stage	Displacement				
no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>Stage description</u>
	ft		ft		
1	0.000	530.00	-0.000	593.00	Change EI of wall to 8.0771E+08lb.ft ² /ft run
2	0.010	593.00	0.000	593.00	Fill to elev. 576.00 on LEFT side
3	0.036	593.00	0.000	593.00	Fill to elev. 581.00 on LEFT side
4	No calculation at this stage				Install prop no.1 at elev. 584.00
5	0.050	593.00	0.000	593.00	Fill to elev. 591.00 on LEFT side
6	0.077	566.00	0.000	593.00	Excav. to elev. 550.00 on RIGHT side
7	0.079	566.00	0.000	593.00	Apply water pressure profile no.1
8	0.091	566.00	0.000	593.00	Apply surcharge no.1 at elev. 591.00
9	0.091	566.00	0.000	593.00	Apply load no.1 at elev. 593.00
10	0.091	566.00	0.000	593.00	Apply surcharge no.4 at elev. 591.00
11	No calculation at this stage				Apply surcharge no.2 at elev. 591.00
12	0.107	563.00	0.000	593.00	Apply surcharge no.3 at elev. 591.00
13	No calculation at this stage				Change soil type 12 to soil type 13
14	No calculation at this stage				Change soil type 3 to soil type 4
15	No calculation at this stage				Change soil type 5 to soil type 6
16	No calculation at this stage				Change soil type 7 to soil type 9
17	0.204	555.50	0.000	593.00	Change soil type 8 to soil type 10

Run ID. 25-10.22_SecD-D.1

Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26

Load Case D.1 - SSP Tip El. 540

| Sheet No.

| Date:22-10-2025

| Checked :

Summary of results (continued)

Prop forces at each stage (horizontal components)


Stage -- Anchor no. 1 ---
no. at elev. 584.00
lb/ft run lb/prop
5 7002.77 65125.80
6 12285.07 114251.14
7 12698.56 118096.61
8 17987.28 167281.68
9 19506.48 181410.24
10 19546.99 181786.99
12 20903.45 194402.05
17 28732.82 267215.26

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: 25-10.22_SecD-D.1
Pulliam Dock Wall - Section D - Pipe54x11/16 & NZ26
Load Case D.1 - SSP Tip El. 540

| Sheet No.
| Job No. 2201593
| Made by : EQB
|
| Date:22-10-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
DEADMAN SHEETING WALLAP ANALYSIS						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
DEADMAN WALLAP ANALYSIS: BL-14-22 – X.1						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.1

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	591.00	9 Struc Fill_null	9 Struc Fill_null
2	585.00	2 Existing Fill_und	1 Struc Fill
3	581.00	2 Existing Fill_und	2 Existing Fill_und
4	577.00	3 Clay I_und	3 Clay I_und
5	554.00	5 Clay IIA_und	5 Clay IIA_und

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description	lb/ft3	Eh, lb/ft2	Ko	NC/OC	Ka	Kp	lb/ft2
(Datum elev.)		(dEh/dy)	(dKo/dy)	(Nu)	(Kac)	(Kpc)	(dc/dy)
1 Struc Fill	125.0	0	0.441	NC	0.283	3.537	
		(31000)		(0.300)	(0.000)	(0.000)	
2 Existing Fill_und	130.0	1200000	0.500	NC	1.000	1.000	2000d
				(0.490)	(2.000)	(2.000)	
3 Clay I_und	130.0	1200000	0.531	NC	1.000	1.000	2000d
				(0.490)	(2.000)	(2.000)	
4 Clay I_drnd	130.0	1200000	0.531	OC	0.361	2.770	
				(0.490)	(0.000)	(0.000)	
5 Clay IIA_und	130.0	600000	0.561	NC	1.000	1.000	1000d
				(0.490)	(2.000)	(2.000)	
6 Clay IIA_drnd	130.0	600000	0.561	OC	0.390	2.561	
				(0.490)	(0.000)	(0.000)	
7 Exist. Fill_drnd	130.0	1200000	0.500	NC	0.333	3.000	0.0d
				(0.490)	(1.155)	(3.464)	
8 Limestone	100.0	0	0.293	NC	0.172	5.828	
		(21000)		(0.290)	(0.000)	(0.000)	
9 Struc Fill_null	125.0	0	0.000	NC	0.000	0.000	
		(31000)		(0.300)	(0.000)	(0.000)	
10 Existing Fill_null	130.0	0	0.000	NC	0.000	0.000	
		(21000)		(0.290)	(0.000)	(0.000)	

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---				--- parameters for Kp ---					
		Soil	Wall	Back-			Soil	Wall	Back-
----- Soil type -----		friction	adhesion	fill			friction	adhesion	fill
No.	Description	angle	coeff.	angle			angle	coeff.	angle
1	Struc Fill	34.00	0.000	0.00			34.00	0.000	0.00
2	Existing Fill_und	0.00	0.000	0.00			0.00	0.000	0.00
3	Clay I_und	0.00	0.000	0.00			0.00	0.000	0.00
4	Clay I_drnd	28.00	0.000	0.00			28.00	0.000	0.00
5	Clay IIA_und	0.00	0.000	0.00			0.00	0.000	0.00
6	Clay IIA_drnd	26.00	0.000	0.00			26.00	0.000	0.00
7	Exist. Fill_drnd	30.00	0.000	0.00			30.00	0.000	0.00
8	Limestone	45.00	0.000	0.00			45.00	0.000	0.00
9	Struc Fill_null	Incompatible values					Incompatible values		
10	Existing Fill null	0.00	0.000	0.00			0.00	0.000	0.00

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft³

	Left side	Right side
Initial water table elevation	577.00	577.00

Automatic water pressure balancing at toe of wall : No

WALL PROPERTIES

Type of structure = Fully Embedded Wall
 Elevation of toe of wall = 555.00
 Maximum finite element length = 2.00 ft
 Youngs modulus of wall E = 4.1760E+09 lb/ft²
 Moment of inertia of wall I = 8.2800E-03 ft⁴/ft run
 E.I = 3.4577E+07 lb.ft²/ft run
 Yield Moment of wall = Not defined

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load no.	Elevation	Horizontal load lb/ft run	Moment load lb.ft/ft run	Moment restraint lb.ft/ft/rad	Partial factor (Category)
1	581.50	34500	0	0	N/A

SURCHARGE LOADS

Surch -arge no.	Distance from wall	Length parallel to wall	Width perpend. to wall	Surcharge ----- lb/ft ² -----		Equiv. soil type	Partial factor/ Category
	Elev.			Near edge	Far edge		
1	591.00	-0.00(R)	1000.00	50.00	2143.00	0.00	N/A
2	591.00	0.00(L)	1000.00	34.00	2143.00	3600.00	N/A
3	591.00	34.00(L)	1000.00	150.00	3600.00	=	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Apply load no.1 at elevation 581.50
2	Apply surcharge no.1 at elevation 591.00
	No analysis at this stage
3	Apply surcharge no.2 at elevation 591.00
4	Apply surcharge no.3 at elevation 591.00
5	Change properties of soil type 2 to soil type 7
	No analysis at this stage
	Ko pressures will not be reset
6	Change properties of soil type 3 to soil type 4
	Ko pressures will not be reset

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft³

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 33.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft

Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Apply load no.1 at elev. 581.50	Yes	Yes	Yes
2	Apply surcharge no.1 at elev. 591.00	No	No	No
3	Apply surcharge no.2 at elev. 591.00	Yes	Yes	Yes
4	Apply surcharge no.3 at elev. 591.00	Yes	Yes	Yes
5	Change soil type 2 to soil type 7	No	No	No
6	Change soil type 3 to soil type 4	Yes	Yes	Yes
*	Summary output	Yes	-	Yes


Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1

| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.1 Apply load no.1 at elev. 581.50



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.1

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Stage No. 1 Apply load no.1 at elevation 581.50

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
1	591.00	591.00	Cant.	1.920	563.07	561.83	29.17	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.180	1.12E-02	0.0	0.0	
2	589.50	0.00	0.164	1.12E-02	0.0	0.0	
3	588.00	0.00	0.147	1.12E-02	0.0	-0.0	
4	586.50	0.00	0.130	1.12E-02	0.0	0.0	
5	585.00	0.00	0.113	1.12E-02	0.0	-0.0	
		-2401.87	0.113	1.12E-02	0.0	0.0	
6	583.25	-2633.97	0.093	1.13E-02	-4406.4	-3727.1	
7	581.50	-2641.45	0.073	1.18E-02	-9022.3	-15520.7	34500.0
		-2641.45	0.073	1.18E-02	25477.7	-15520.7	
8	581.00	-2598.10	0.067	1.19E-02	24167.8	-3113.2	
		-5250.00	0.067	1.19E-02	24167.8	-3113.2	
9	579.00	-5510.00	0.044	1.10E-02	13407.8	34549.0	
10	577.00	-4661.97	0.024	8.52E-03	3235.8	53427.8	
		-4716.84	0.024	8.52E-03	3235.8	53427.8	
11	575.50	-3011.66	0.013	6.22E-03	-2560.6	52954.9	
12	574.00	-1581.47	0.005	4.07E-03	-6005.4	46102.5	
13	572.00	269.90	-0.001	1.84E-03	-7317.0	30928.8	
14	570.00	1005.82	-0.003	4.62E-04	-6041.3	16834.6	
15	568.00	1055.10	-0.003	-2.20E-04	-3980.4	6763.6	
16	566.00	811.49	-0.002	-4.42E-04	-2113.8	913.1	
17	564.00	510.84	-0.001	-4.19E-04	-791.4	-1691.5	
18	562.00	263.19	-0.001	-3.05E-04	-17.4	-2252.7	
19	560.00	97.01	-0.000	-1.89E-04	342.8	-1761.1	
20	558.00	-21.76	0.000	-1.12E-04	418.0	-881.5	
21	556.50	-143.83	0.000	-8.77E-05	293.8	-279.0	
22	555.00	-247.96	0.000	-8.17E-05	-0.0	-0.0	

(continued)

Stage No.1 Apply load no.1 at elevation 581.50

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	764
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	4586
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	9173
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	13759
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	18346
		0.00	750.00	0.00	4750.00	0.00	0.00a	159067
6	583.25	0.00	977.50	0.00	4977.50	0.00	0.00a	159067
7	581.50	0.00	1205.00	0.00	5205.00	0.00	0.00a	159067
8	581.00	0.00	1270.00	0.00	5270.00	0.00	0.00a	159067
9	579.00	0.00	1530.00	0.00	5530.00	0.00	0.00a	159067
10	577.00	0.00	1790.00	0.00	5790.00	0.00	0.00a	159067
11	575.50	93.60	1891.40	0.00	5891.40	0.00	93.60a	159067
12	574.00	187.20	1992.80	0.00	5992.80	262.13	449.33	159067
13	572.00	312.00	2128.00	0.00	6128.00	1259.61	1571.61	169536
14	570.00	436.80	2263.20	0.00	6263.20	1699.36	2136.16	169536
15	568.00	561.60	2398.40	0.00	6398.40	1795.79	2357.39	169536
16	566.00	686.40	2533.60	0.00	6533.60	1745.78	2432.18	169536
17	564.00	811.20	2668.80	0.00	6668.80	1667.24	2478.44	169536
18	562.00	936.00	2804.00	0.00	6804.00	1615.21	2551.21	169536
19	560.00	1060.80	2939.20	0.00	6939.20	1603.91	2664.71	169536
20	558.00	1185.60	3074.40	0.00	7074.40	1616.32	2801.92	414445
21	556.50	1279.20	3175.80	0.00	7175.80	1609.12	2888.32	414445
22	555.00	1372.80	3277.20	0.00	7277.20	1610.91	2983.71	414445

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	764
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	4586
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	9173
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	13759
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	18346
		0.00	750.00	212.25	2652.75	2401.87	2401.87	18346
6	583.25	0.00	968.75	274.16	3426.47	2633.97	2633.97	23697
7	581.50	0.00	1187.50	336.06	4200.19	2641.45	2641.45	29047
8	581.00	0.00	1250.00	353.75	4421.25	2598.10	2598.10	30576
		0.00	1250.00	0.00	5250.00	5250.00	5250.00p	159067
9	579.00	0.00	1510.00	0.00	5510.00	5510.00	5510.00p	159067
10	577.00	0.00	1770.00	0.00	5770.00	4661.97	4661.97	159067
		0.00	1770.00	0.00	5770.00	4716.84	4716.84	159067
11	575.50	93.60	1871.40	0.00	5871.40	3011.66	3105.26	159067
12	574.00	187.20	1972.80	0.00	5972.80	1843.60	2030.80	159067
13	572.00	312.00	2108.00	0.00	6108.00	989.71	1301.71	169536
14	570.00	436.80	2243.20	0.00	6243.20	693.54	1130.34	169536
15	568.00	561.60	2378.40	0.00	6378.40	740.69	1302.29	169536
16	566.00	686.40	2513.60	0.00	6513.60	934.29	1620.69	169536
17	564.00	811.20	2648.80	0.00	6648.80	1156.40	1967.60	169536
18	562.00	936.00	2784.00	0.00	6784.00	1352.02	2288.02	169536
19	560.00	1060.80	2919.20	0.00	6919.20	1506.90	2567.70	169536
20	558.00	1185.60	3054.40	0.00	7054.40	1638.08	2823.68	414445
21	556.50	1279.20	3155.80	0.00	7155.80	1752.96	3032.16	414445
22	555.00	1372.80	3257.20	0.00	7257.20	1858.86	3231.66	414445

Run ID. REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)

Stage No.1 Apply load no.1 at elevation 581.50


Note: 93.60a Soil pressure at active limit
 5510.00p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1


Sheet No.
Job No. 2201593
Made by : AJG
Date:16-07-2025
Checked :

Units: lb, ft

Stage No.1 Apply load no.1 at elev. 581.50



Stage No.1 Apply load no.1 at elev. 581.50




GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
 Pulliam Dock Wall - Deadman
 SSP Deadman - BL-14-22_LCX.1

| Sheet No.
 | Job No. 2201593
 | Made by : AJG
 | Date:16-07-2025
 | Checked :

Units: lb, ft

Stage No.3 Apply surcharge no.2 at elev. 591.00



GEI CONSULTANTS, INC.	Sheet No.
Program: WALLAP Version 6.06 Revision A52.B71.R55	Job No. 2201593
Licensed from GEOSOLVE	Made by : AJG
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1	
Pulliam Dock Wall - Deadman	Date:16-07-2025
SSP Deadman - BL-14-22_LCX.1	Checked :

Units: lb,ft

Stage No. 3 Apply surcharge no.2 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>of</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
3	591.00	591.00	Cant.	3.074	561.47	***	***	L to R

Legend: *** Result not found

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.197	1.19E-02	0.0	0.0	
2	589.50	0.00	0.179	1.19E-02	0.0	-0.0	
3	588.00	0.00	0.161	1.19E-02	0.0	0.0	
4	586.50	0.00	0.143	1.19E-02	0.0	0.0	
5	585.00	0.00	0.125	1.19E-02	0.0	-0.0	
		-2585.00	0.125	1.19E-02	0.0	0.0	
6	583.25	-2647.63	0.104	1.20E-02	-4578.6	-3162.4	
7	581.50	-2386.80	0.083	1.25E-02	-8983.7	-15212.3	34500.0
		-2386.80	0.083	1.25E-02	25516.3	-15212.3	
8	581.00	-2266.38	0.077	1.26E-02	24353.0	-2752.1	
		-5935.76	0.077	1.26E-02	24353.0	-2752.1	
9	579.00	-5698.91	0.052	1.17E-02	12718.3	34004.5	
10	577.00	-4338.20	0.031	9.29E-03	2681.2	51219.2	
		-4262.66	0.031	9.29E-03	2681.2	51219.2	
11	575.50	-2181.10	0.018	7.08E-03	-2151.6	50447.1	
12	574.00	-706.14	0.009	5.01E-03	-4317.0	45025.9	
13	572.00	-193.45	0.002	2.74E-03	-5216.6	33761.2	
14	570.00	235.06	-0.002	1.11E-03	-5175.0	22463.2	
15	568.00	540.07	-0.003	1.01E-04	-4399.9	12560.4	
16	566.00	709.67	-0.003	-4.06E-04	-3150.1	5010.6	
17	564.00	658.74	-0.002	-5.61E-04	-1781.7	335.3	
18	562.00	490.86	-0.001	-5.20E-04	-632.1	-1742.3	
19	560.00	260.69	0.000	-4.14E-04	119.4	-1912.5	
20	558.00	30.04	0.001	-3.28E-04	410.2	-1072.9	
21	556.50	-137.35	0.001	-2.96E-04	329.7	-378.4	
22	555.00	-302.24	0.002	-2.88E-04	-0.0	-0.0	

(continued)

Stage No.3 Apply surcharge no.2 at elevation 591.00

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	2143.00	0.00	0.00	0.00	0.00	612
2	589.50	0.00	2371.23	0.00	0.00	0.00	0.00	3671
3	588.00	0.00	2598.57	0.00	0.00	0.00	0.00	7341
4	586.50	0.00	2824.07	0.00	0.00	0.00	0.00	11012
5	585.00	0.00	3046.91	0.00	0.00	0.00	0.00	14682
		0.00	3046.91	0.00	7046.91	0.00	0.00a	129887
6	583.25	0.00	3311.33	0.00	7311.33	199.01	199.01	129887
7	581.50	0.00	3570.26	0.00	7570.26	486.98	486.98	129887
8	581.00	0.00	3643.13	0.00	7643.13	567.90	567.90	129887
9	579.00	0.00	3929.38	0.00	7929.38	887.89	887.89	129887
10	577.00	0.00	4206.98	206.98	8206.98	1213.63	1213.63	129887
		0.00	4206.98	206.98	8206.98	1344.04	1344.04	129887
11	575.50	93.60	4315.86	315.86	8315.86	1561.14	1654.74	129887
12	574.00	187.20	4419.97	419.97	8419.97	1794.46	1981.66	129887
13	572.00	312.00	4551.71	551.71	8551.71	2108.85	2420.85	129887
14	570.00	436.80	4675.99	675.99	8675.99	2379.51	2816.31	129887
15	568.00	561.60	4793.59	793.59	8793.59	2586.99	3148.59	232599
16	566.00	686.40	4905.39	905.39	8905.39	2725.60	3412.00	232599
17	564.00	811.20	5012.28	1012.28	9012.28	2753.00	3564.20	232599
18	562.00	936.00	5115.09	1115.09	9115.09	2721.23	3657.23	232599
19	560.00	1060.80	5214.63	1214.63	9214.63	2657.81	3718.61	261629
20	558.00	1185.60	5311.63	1311.63	9311.63	2593.85	3779.45	261629
21	556.50	1279.20	5383.10	1383.10	9383.10	2548.59	3827.79	261629
22	555.00	1372.80	5453.73	1453.73	9453.73	2504.56	3877.36	261629

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	2143.00	0.00	0.00	0.00	0.00	612
2	589.50	0.00	2289.55	0.00	0.00	0.00	0.00	3671
3	588.00	0.00	2436.22	0.00	0.00	0.00	0.00	7341
4	586.50	0.00	2583.03	0.00	0.00	0.00	0.00	11012
5	585.00	0.00	2730.05	0.00	0.00	0.00	0.00	14682
		0.00	2730.05	772.60	9656.18	2585.00	2585.00	14682
6	583.25	0.00	2901.94	821.25	10264.16	2846.64	2846.64	18964
7	581.50	0.00	3074.33	870.03	10873.89	2873.78	2873.78	23247
8	581.00	0.00	3123.68	884.00	11048.46	2834.29	2834.29	24470
		0.00	3123.68	0.00	7123.68	6503.66	6503.66	129887
9	579.00	0.00	3331.64	0.00	7331.64	6586.80	6586.80	129887
10	577.00	0.00	3540.52	0.00	7540.52	5551.83	5551.83	129887
		0.00	3540.52	0.00	7540.52	5606.70	5606.70	129887
11	575.50	93.60	3604.27	0.00	7604.27	3742.24	3835.84	129887
12	574.00	187.20	3668.66	0.00	7668.66	2500.60	2687.80	129887
13	572.00	312.00	3755.55	0.00	7755.55	2302.30	2614.30	129887
14	570.00	436.80	3843.71	0.00	7843.71	2144.45	2581.25	129887
15	568.00	561.60	3933.19	0.00	7933.19	2046.92	2608.52	232599
16	566.00	686.40	4024.03	24.03	8024.03	2015.93	2702.33	232599
17	564.00	811.20	4116.28	116.28	8116.28	2094.26	2905.46	232599
18	562.00	936.00	4209.93	209.93	8209.93	2230.36	3166.36	232599
19	560.00	1060.80	4305.00	305.00	8305.00	2397.12	3457.92	261629
20	558.00	1185.60	4401.49	401.49	8401.49	2563.81	3749.41	261629
21	556.50	1279.20	4474.77	474.77	8474.77	2685.94	3965.14	261629

(continued)

Stage No.3 Apply surcharge no.2 at elevation 591.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
22	555.00	1372.80	4548.82	548.82	8548.82	2806.80	4179.60	261629


Note: 0.00a Soil pressure at active limit
 123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1


| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.3 Apply surcharge no.2 at elev. 591.00



Stage No.3 Apply surcharge no.2 at elev. 591.00




GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1

| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.4 Apply surcharge no.3 at elev. 591.00



GEI CONSULTANTS, INC.	Sheet No.
Program: WALLAP Version 6.06 Revision A52.B71.R55	Job No. 2201593
Licensed from GEOSOLVE	Made by : AJG
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1	
Pulliam Dock Wall - Deadman	Date:16-07-2025
SSP Deadman - BL-14-22_LCX.1	Checked :

Units: lb,ft

Stage No. 4 Apply surcharge no.3 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u>	<u>Pass.</u>	<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
				<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
4	591.00	591.00	Cant.	3.044	560.17	***	***	L to R

Legend: *** Result not found

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft ²	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.197	1.19E-02	0.0	0.0	
2	589.50	0.00	0.179	1.19E-02	0.0	-0.0	
3	588.00	0.00	0.161	1.19E-02	0.0	0.0	
4	586.50	0.00	0.143	1.19E-02	0.0	0.0	
5	585.00	0.00	0.125	1.19E-02	0.0	-0.0	
		-2581.95	0.125	1.19E-02	0.0	0.0	
6	583.25	-2646.53	0.104	1.20E-02	-4574.9	-3153.2	
7	581.50	-2384.02	0.083	1.25E-02	-8976.6	-15188.2	34500.0
		-2384.02	0.083	1.25E-02	25523.4	-15188.2	
8	581.00	-2262.42	0.077	1.26E-02	24361.7	-2724.0	
		-5952.67	0.077	1.26E-02	24361.7	-2724.0	
9	579.00	-5715.72	0.052	1.17E-02	12693.4	34031.6	
10	577.00	-4348.84	0.031	9.26E-03	2628.8	51182.5	
		-4273.30	0.031	9.26E-03	2628.8	51182.5	
11	575.50	-2181.67	0.019	7.06E-03	-2212.4	50329.8	
12	574.00	-690.09	0.010	4.99E-03	-4366.2	44828.0	
13	572.00	-142.52	0.002	2.73E-03	-5198.9	33527.4	
14	570.00	325.42	-0.002	1.11E-03	-5016.0	22394.3	
15	568.00	514.15	-0.003	9.46E-05	-4176.4	12913.2	
16	566.00	619.91	-0.002	-4.44E-04	-3042.3	5726.6	
17	564.00	585.42	-0.001	-6.42E-04	-1837.0	1128.8	
18	562.00	458.57	-0.000	-6.42E-04	-793.0	-1125.9	
19	560.00	273.35	0.001	-5.64E-04	-61.1	-1581.8	
20	558.00	72.06	0.002	-4.90E-04	284.3	-977.7	
21	556.50	-80.32	0.003	-4.60E-04	278.1	-383.7	
22	555.00	-290.52	0.004	-4.52E-04	-0.0	-0.0	

(continued)

Stage No.4 Apply surcharge no.3 at elevation 591.00

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	2143.00	0.00	0.00	0.00	0.00	1617
2	589.50	0.00	2371.36	0.00	0.00	0.00	0.00	9704
3	588.00	0.00	2599.60	0.00	0.00	0.00	0.00	19407
4	586.50	0.00	2827.51	0.00	0.00	0.00	0.00	29111
5	585.00	0.00	3054.95	0.00	0.00	0.00	0.00	22524
		0.00	3054.95	0.00	7054.95	3.57	3.57	192662
6	583.25	0.00	3328.24	0.00	7328.24	202.19	202.19	192662
7	581.50	0.00	3600.50	0.00	7600.50	494.05	494.05	192662
8	581.00	0.00	3678.06	0.00	7678.06	576.91	576.91	192662
9	579.00	0.00	3987.27	0.00	7987.27	908.43	908.43	192662
10	577.00	0.00	4294.61	294.61	8294.61	1252.13	1252.13	192662
		0.00	4294.61	294.61	8294.61	1382.54	1382.54	192662
11	575.50	93.60	4430.21	430.21	8430.21	1618.03	1711.63	192662
12	574.00	187.20	4564.63	564.63	8564.63	1874.82	2062.02	192662
13	572.00	312.00	4741.97	741.97	8741.97	2229.44	2541.44	192662
14	570.00	436.80	4917.12	917.12	8917.12	2540.43	2977.23	192662
15	568.00	561.60	5090.07	1090.07	9090.07	2631.95	3193.55	192662
16	566.00	686.40	5260.86	1260.86	9260.86	2714.68	3401.08	192662
17	564.00	811.20	5429.51	1429.51	9429.51	2781.37	3592.57	192662
18	562.00	936.00	5596.11	1596.11	9596.11	2830.23	3766.23	192662
19	560.00	1060.80	5760.71	1760.71	9760.71	2864.70	3925.50	192662
20	558.00	1185.60	5923.40	1923.40	9923.40	2890.60	4076.20	192662
21	556.50	1279.20	6044.21	2044.21	10044.21	2907.55	4186.75	192662
22	555.00	1372.80	6164.03	2164.03	10164.03	2865.57	4238.37	192662

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	2143.00	0.00	0.00	0.00	0.00	1617
2	589.50	0.00	2289.55	0.00	0.00	0.00	0.00	9704
3	588.00	0.00	2436.22	0.00	0.00	0.00	0.00	19407
4	586.50	0.00	2583.03	0.00	0.00	0.00	0.00	29111
5	585.00	0.00	2730.05	0.00	0.00	0.00	0.00	22524
		0.00	2730.05	772.60	9656.18	2585.53	2585.53	22524
6	583.25	0.00	2901.94	821.25	10264.16	2848.72	2848.72	29094
7	581.50	0.00	3074.33	870.03	10873.89	2878.07	2878.07	35663
8	581.00	0.00	3123.68	884.00	11048.46	2839.34	2839.34	37540
		0.00	3123.68	0.00	7123.68	6529.58	6529.58	192662
9	579.00	0.00	3331.64	0.00	7331.64	6624.15	6624.15	192662
10	577.00	0.00	3540.52	0.00	7540.52	5600.97	5600.97	192662
		0.00	3540.52	0.00	7540.52	5655.84	5655.84	192662
11	575.50	93.60	3604.27	0.00	7604.27	3799.70	3893.30	192662
12	574.00	187.20	3668.66	0.00	7668.66	2564.90	2752.10	192662
13	572.00	312.00	3755.55	0.00	7755.55	2371.97	2683.97	192662
14	570.00	436.80	3843.71	0.00	7843.71	2215.01	2651.81	192662
15	568.00	561.60	3933.19	0.00	7933.19	2117.80	2679.40	192662
16	566.00	686.40	4024.03	24.03	8024.03	2094.77	2781.17	192662
17	564.00	811.20	4116.28	116.28	8116.28	2195.96	3007.16	192662
18	562.00	936.00	4209.93	209.93	8209.93	2371.66	3307.66	192662
19	560.00	1060.80	4305.00	305.00	8305.00	2591.35	3652.15	192662
20	558.00	1185.60	4401.49	401.49	8401.49	2818.54	4004.14	192662
21	556.50	1279.20	4474.77	474.77	8474.77	2987.87	4267.07	192662

Run ID. REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)

Stage No.4 Apply surcharge no.3 at elevation 591.00


<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>RIGHT side</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
22	555.00	1372.80	4548.82	548.82	8548.82	3156.09	4528.89	192662

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1


| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.4 Apply surcharge no.3 at elev. 591.00



Stage No.4 Apply surcharge no.3 at elev. 591.00




GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
 Pulliam Dock Wall - Deadman
 SSP Deadman - BL-14-22_LCX.1

| Sheet No.
 | Job No. 2201593
 | Made by : AJG
 | Date:16-07-2025
 | Checked :

Units: lb, ft

Stage No.6 Change soil type 3 to soil type 4



GEI CONSULTANTS, INC.	Sheet No.
Program: WALLAP Version 6.06 Revision A52.B71.R55	Job No. 2201593
Licensed from GEOSOLVE	Made by : AJG
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1	
Pulliam Dock Wall - Deadman	Date:16-07-2025
SSP Deadman - BL-14-22_LCX.1	Checked :

Units: lb,ft

Stage No. 6 Change properties of soil type 3 to soil type 4
Ko pressures will not be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u>	<u>Prop</u> <u>Elev.</u>	<u>Factor</u> <u>of</u> <u>Safety</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>	<u>Toe elev. for</u> <u>FoS = 1.500</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	<u>Direction</u> <u>of</u> <u>failure</u>
				<u>Moment</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>		
6	591.00	591.00	Cant.	2.690	560.12	***	*** L to R

Legend: *** Result not found

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft
Subgrade reaction model - Boussinesq Influence coefficients
Soil deformations are elastic until the active or passive limit is reached
Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.226	1.40E-02	0.0	0.0	
2	589.50	0.00	0.205	1.40E-02	0.0	-0.0	
3	588.00	0.00	0.184	1.40E-02	0.0	0.0	
4	586.50	0.00	0.163	1.40E-02	0.0	0.0	
5	585.00	0.00	0.142	1.40E-02	0.0	0.0	
		-1899.22	0.142	1.40E-02	0.0	0.0	
6	583.25	-2077.04	0.118	1.40E-02	-3479.2	-2162.7	
7	581.50	-1983.74	0.093	1.44E-02	-7032.4	-11510.8	34500.0
		-1983.74	0.093	1.44E-02	27467.6	-11510.8	
8	581.00	-1904.34	0.086	1.44E-02	26495.6	1973.2	
		-6809.83	0.086	1.44E-02	26495.6	1973.2	
9	579.00	-6226.37	0.057	1.32E-02	13459.4	41129.8	
10	577.00	-4658.59	0.034	1.03E-02	2574.4	58630.7	
		-4594.50	0.034	1.03E-02	2574.4	58630.7	
11	575.50	-2452.07	0.020	7.84E-03	-2710.5	57265.1	
12	574.00	-870.45	0.010	5.49E-03	-5202.4	50719.0	
13	572.00	-87.34	0.002	2.94E-03	-6160.2	37385.3	
14	570.00	462.52	-0.002	1.16E-03	-5785.0	24439.9	
15	568.00	650.74	-0.003	5.90E-05	-4671.7	13695.0	
16	566.00	722.32	-0.003	-5.04E-04	-3298.7	5790.9	
17	564.00	648.54	-0.002	-6.97E-04	-1927.8	885.2	
18	562.00	490.19	-0.000	-6.81E-04	-789.1	-1424.8	
19	560.00	284.17	0.001	-5.88E-04	-14.7	-1809.7	
20	558.00	69.07	0.002	-5.04E-04	338.5	-1091.2	
21	556.50	-99.13	0.003	-4.71E-04	316.0	-419.3	
22	555.00	-322.16	0.004	-4.62E-04	-0.0	-0.0	

(continued)

Stage No.6 Change properties of soil type 3 to soil type 4
 Ko pressures will not be reset

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	2143.00	0.00	0.00	0.00	0.00	821
2	589.50	0.00	2371.36	0.00	0.00	0.00	0.00	4924
3	588.00	0.00	2599.60	0.00	0.00	0.00	0.00	9849
4	586.50	0.00	2827.51	0.00	0.00	0.00	0.00	14773
5	585.00	0.00	3054.95	0.00	0.00	0.00	0.00	19697
		0.00	3054.95	1018.32	9164.84	1018.32	1018.32a	169911
6	583.25	0.00	3328.24	1109.41	9984.73	1109.41	1109.41a	169911
7	581.50	0.00	3600.50	1200.17	10801.49	1200.17	1200.17a	169911
8	581.00	0.00	3678.06	1226.02	11034.19	1226.02	1226.02a	169911
9	579.00	0.00	3987.27	1329.09	11961.80	1329.09	1329.09a	169911
10	577.00	0.00	4294.61	1431.54	12883.84	1431.54	1431.54a	169911
		0.00	4294.61	1550.50	11895.33	1550.50	1550.50a	169911
11	575.50	93.60	4430.21	1599.45	12270.91	1599.45	1693.05a	169911
12	574.00	187.20	4564.63	1647.98	12643.23	1784.64	1971.84	169911
13	572.00	312.00	4741.97	1712.01	13134.43	2257.04	2569.04	166712
14	570.00	436.80	4917.12	1775.24	13619.56	2608.98	3045.78	166712
15	568.00	561.60	5090.07	1837.69	14098.62	2700.25	3261.85	166712
16	566.00	686.40	5260.86	1899.35	14571.66	2765.88	3452.28	166712
17	564.00	811.20	5429.51	1960.24	15038.81	2812.94	3624.14	166712
18	562.00	936.00	5596.11	2020.38	15500.24	2846.04	3782.04	166712
19	560.00	1060.80	5760.71	2079.81	15956.16	2870.11	3930.91	166712
20	558.00	1185.60	5923.40	2138.54	16406.78	2889.10	4074.70	339433
21	556.50	1279.20	6044.21	2182.16	16741.41	2898.14	4177.34	415850
22	555.00	1372.80	6164.03	2225.42	17073.30	2849.75	4222.55	415850

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
		Water press. lb/ft2	Vertic -al lb/ft2	Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	2143.00	0.00	0.00	0.00	0.00	821
2	589.50	0.00	2289.55	0.00	0.00	0.00	0.00	4924
3	588.00	0.00	2436.22	0.00	0.00	0.00	0.00	9849
4	586.50	0.00	2583.03	0.00	0.00	0.00	0.00	14773
5	585.00	0.00	2730.05	0.00	0.00	0.00	0.00	19697
		0.00	2730.05	772.60	9656.18	2917.53	2917.53	19697
6	583.25	0.00	2901.94	821.25	10264.16	3186.45	3186.45	25442
7	581.50	0.00	3074.33	870.03	10873.89	3183.90	3183.90	31188
8	581.00	0.00	3123.68	884.00	11048.46	3130.37	3130.37	32829
		0.00	3123.68	1041.23	9371.05	8035.85	8035.85	169911
9	579.00	0.00	3331.64	1110.55	9994.91	7555.46	7555.46	169911
10	577.00	0.00	3540.52	1180.17	10621.57	6090.13	6090.13	169911
		0.00	3540.52	1278.25	9806.64	6145.00	6145.00	169911
11	575.50	93.60	3604.27	1301.26	9983.21	4051.52	4145.12	169911
12	574.00	187.20	3668.66	1324.51	10161.54	2655.08	2842.28	169911
13	572.00	312.00	3755.55	1355.88	10402.22	2344.38	2656.38	166712
14	570.00	436.80	3843.71	1387.71	10646.40	2146.46	2583.26	166712
15	568.00	561.60	3933.19	1420.01	10894.24	2049.51	2611.11	166712
16	566.00	686.40	4024.03	1452.81	11145.88	2043.56	2729.96	166712
17	564.00	811.20	4116.28	1486.11	11401.37	2164.39	2975.59	166712
18	562.00	936.00	4209.93	1519.93	11660.78	2355.85	3291.85	166712
19	560.00	1060.80	4305.00	1554.25	11924.11	2585.94	3646.74	166712
20	558.00	1185.60	4401.49	1589.08	12191.35	2820.03	4005.63	339433

Run ID. REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)

Stage No.6 Change properties of soil type 3 to soil type 4
 Ko pressures will not be reset

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
21	556.50	1279.20	4474.77	1615.54	12394.32	2997.27	4276.47	415850
22	555.00	1372.80	4548.82	1642.28	12599.45	3171.91	4544.71	415850


Note: 1693.05a Soil pressure at active limit
 123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1


Sheet No.
Job No. 2201593
Made by : AJG
Date:16-07-2025
Checked :

Units: lb, ft

Stage No.6 Change soil type 3 to soil type 4



Stage No.6 Change soil type 3 to soil type 4



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.1

| Sheet No.

| Job No. 2201593

| Made by : AJG

|

| Date:16-07-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
1	591.00	591.00	Cant.	1.920	563.07	561.83	29.17	L to R
2	591.00	591.00		No analysis at this stage				
3	591.00	591.00	Cant.	3.074	561.47	***	***	L to R
4	591.00	591.00	Cant.	3.044	560.17	***	***	L to R
5	591.00	591.00		No analysis at this stage				
6	591.00	591.00	Cant.	2.690	560.12	***	***	L to R

Legend: *** Result not found

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.1

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	591.00	0.226	0.000	0.0	0.0	0.0	0.0
2	589.50	0.205	0.000	0.0	-0.0	0.0	0.0
3	588.00	0.184	0.000	0.0	-0.0	0.0	0.0
4	586.50	0.163	0.000	0.0	-0.0	0.0	0.0
5	585.00	0.142	0.000	0.0	-0.0	0.0	0.0
6	583.25	0.118	0.000	0.0	-3727.1	0.0	-4578.6
7	581.50	0.093	0.000	0.0	-15520.7	27467.6	-9022.3
8	581.00	0.086	0.000	1973.2	-3113.2	26495.6	0.0
9	579.00	0.057	0.000	41129.8	0.0	13459.4	0.0
10	577.00	0.034	0.000	58630.7	0.0	3235.8	0.0
11	575.50	0.020	0.000	57265.1	0.0	0.0	-2710.5
12	574.00	0.010	0.000	50719.0	0.0	0.0	-6005.4
13	572.00	0.002	-0.001	37385.3	0.0	0.0	-7317.0
14	570.00	0.000	-0.003	24439.9	0.0	0.0	-6041.3
15	568.00	0.000	-0.003	13695.0	0.0	0.0	-4671.7
16	566.00	0.000	-0.003	5790.9	0.0	0.0	-3298.7
17	564.00	0.000	-0.002	1128.8	-1691.5	0.0	-1927.8
18	562.00	0.000	-0.001	0.0	-2252.7	0.0	-793.0
19	560.00	0.001	-0.000	0.0	-1912.5	342.8	-61.1
20	558.00	0.002	0.000	0.0	-1091.2	418.0	0.0
21	556.50	0.003	0.000	0.0	-419.3	329.7	0.0
22	555.00	0.004	0.000	0.0	-0.0	0.0	-0.0

Maximum and minimum bending moment and shear force at each stage

Stage no.	Bending moment				Shear force			
	maximum	elev.	minimum	elev.	maximum	elev.	minimum	elev.
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	53427.8	577.00	-15520.7	581.50	25477.7	581.50	-9022.3	581.50
2	No calculation at this stage							
3	51219.2	577.00	-15212.3	581.50	25516.3	581.50	-8983.7	581.50
4	51182.5	577.00	-15188.2	581.50	25523.4	581.50	-8976.6	581.50
5	No calculation at this stage							
6	58630.7	577.00	-11510.8	581.50	27467.6	581.50	-7032.4	581.50

Run ID. REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1

| Sheet No.
| Date:16-07-2025
| Checked :

Summary of results (continued)

Maximum and minimum displacement at each stage

Stage ----- Displacement -----


no.	<u>maximum</u> ft	<u>elev.</u>	<u>minimum</u> ft	<u>elev.</u>	<u>Stage description</u>
1	0.180	591.00	-0.003	568.00	Apply load no.1 at elev. 581.50
2	No calculation at this stage				Apply surcharge no.1 at elev. 591.00
3	0.197	591.00	-0.003	568.00	Apply surcharge no.2 at elev. 591.00
4	0.197	591.00	-0.003	568.00	Apply surcharge no.3 at elev. 591.00
5	No calculation at this stage				Change soil type 2 to soil type 7
6	0.226	591.00	-0.003	568.00	Change soil type 3 to soil type 4

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.1

| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
DEADMAN WALLAP ANALYSIS: BL-14-22 – X.3						

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_Fill_LCX-3

Pulliam Dock Wall - Deadman

SSP Deadman - Fill_LCX.3

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	591.00	9 Struc Fill_null	9 Struc Fill_null
2	585.00	2 Granular Fill - BW	1 Struc Fill
3	581.00	2 Granular Fill - BW	2 Granular Fill - BW
4	553.00	5 Clay IIA_und	5 Clay IIA_und

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft ³	Eh, lb/ft ² (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	lb/ft ² (dc/dy)
1 Struc Fill	125.0	1000000	0.441	OC (0.300)	0.283 (0.000)	3.537 (0.000)	
2 Granular Fill - BW	125.0	0 (15000)	0.500	NC (0.330)	0.333 (0.000)	3.000 (0.000)	
3 Clay I_und	130.0	1200000	0.531	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000d
4 Clay I_drnd	130.0	1200000	0.531	OC (0.490)	0.361 (0.000)	2.770 (0.000)	
5 Clay IIA_und	130.0	600000	0.561	NC (0.490)	1.000 (2.000)	1.000 (2.000)	1000d
6 Clay IIA_drnd	130.0	600000	0.561	OC (0.490)	0.390 (0.000)	2.561 (0.000)	
7 Exist. Fill_drnd	130.0	1200000	0.500	NC (0.490)	0.333 (1.155)	3.000 (3.464)	0.0d
8 Limestone	100.0	0 (21000)	0.293	NC (0.290)	0.172 (0.000)	5.828 (0.000)	
9 Struc Fill_null	125.0	0 (31000)	0.000	NC (0.300)	0.000 (0.000)	0.000 (0.000)	
10 Existing Fill_null	130.0	0 (21000)	0.000	NC (0.290)	0.000 (0.000)	0.000 (0.000)	

Additional soil parameters associated with Ka and Kp

No. Description	--- parameters for Ka ---			--- parameters for Kp ---		
	Soil friction angle	Wall adhesion coeff.	Back-fill angle	Soil friction angle	Wall adhesion coeff.	Back-fill angle
1 Struc Fill	34.00	0.000	0.00	34.00	0.000	0.00
2 Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00
3 Clay I_und	0.00	0.000	0.00	0.00	0.000	0.00
4 Clay I_drnd	28.00	0.000	0.00	28.00	0.000	0.00
5 Clay IIA_und	0.00	0.000	0.00	0.00	0.000	0.00
6 Clay IIA_drnd	26.00	0.000	0.00	26.00	0.000	0.00
7 Exist. Fill_drnd	30.00	0.000	0.00	30.00	0.000	0.00
8 Limestone	45.00	0.000	0.00	45.00	0.000	0.00
9 Struc Fill_null	Incompatible values			Incompatible values		
10 Existing Fill_null	0.00	0.000	0.00	0.00	0.000	0.00

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	577.00	577.00

Automatic water pressure balancing at toe of wall : No

Water		Left side			Right side			
press.	-----							
profile	Point	Elev.	Piezo	Water	Point	Elev.	Piezo	
no.	no.		elev.	press.	no.		elev.	
		ft	ft	lb/ft2		ft	ft	
							lb/ft2	
	1	582.00	582.00	0.0	1	582.00	582.00	0.0

WALL PROPERTIES

Type of structure = Fully Embedded Wall
 Elevation of toe of wall = 555.00
 Maximum finite element length = 2.00 ft
 Youngs modulus of wall E = 4.1760E+09 lb/ft2
 Moment of inertia of wall I = 0.013653 ft4/ft run
 E.I = 5.7013E+07 lb.ft2/ft run
 Yield Moment of wall = Not defined

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load	Horizontal	Moment	Moment	Partial
no.	Elevation	load	load	factor
		lb/ft run	lb.ft/ft run	lb.ft/ft/rad
				(Category)
1	581.50	34500	0	0
				N/A

SURCHARGE LOADS

Surch	Distance	Length	Width	Surcharge		Equiv.	Partial
-arge	from	parallel	perpend.	-----	lb/ft2	-----	soil
no.	Elev.	wall	to wall	Near edge	Far edge	type	factor/
							Category
1	591.00	0.00 (L)	1000.00	45.00	0.00	4000.00	N/A
2	591.00	45.00 (L)	1000.00	100.00	4000.00	=	N/A

Note: L = Left side, R = Right side

A trapezoidal surcharge is defined by two values:

N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction	Stage description
stage no.	-----
1	Apply load no.1 at elevation 581.50
2	Apply surcharge no.1 at elevation 591.00
	No analysis at this stage
3	Apply surcharge no.2 at elevation 591.00
4	Apply water pressure profile no.1

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - CP2

Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density = 0.00 lb/ft3

Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 33.00 ft

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft

Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft

Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Apply load no.1 at elev. 581.50	No	No	No
2	Apply surcharge no.1 at elev. 591.00	No	No	No
3	Apply surcharge no.2 at elev. 591.00	Yes	Yes	Yes
4	Apply water pressure profile no.1	No	No	No
*	Summary output	Yes	-	Yes


Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_Fill_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.3

| Sheet No.
| Job No. 2201593
| Made by : AJG
|
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.3 Apply surcharge no.2 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_Fill_LCX-3

Pulliam Dock Wall - Deadman

SSP Deadman - Fill_LCX.3

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Stage No. 3 Apply surcharge no.2 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
3	591.00	591.00	Cant.	1.611	559.59	557.30	33.70	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.448	2.10E-02	0.0	0.0	
2	589.50	0.00	0.417	2.10E-02	0.0	0.0	
3	588.00	0.00	0.385	2.10E-02	0.0	0.0	
4	586.50	0.00	0.354	2.10E-02	0.0	0.0	
5	585.00	0.00	0.322	2.10E-02	0.0	-0.0	
		-2290.28	0.322	2.10E-02	0.0	-0.0	
6	583.50	-2863.33	0.291	2.10E-02	-3865.2	-2791.5	
7	582.00	-3436.71	0.259	2.12E-02	-8590.2	-12025.5	
8	581.50	-3627.91	0.249	2.13E-02	-10356.4	-16758.2	34500.0
		-3627.91	0.249	2.13E-02	24143.6	-16758.2	
9	581.00	-3819.16	0.238	2.14E-02	22281.8	-5147.9	
		-3086.60	0.238	2.14E-02	22281.8	-5147.9	
10	579.00	-3035.19	0.195	2.09E-02	16160.0	33238.5	
11	577.00	-2790.67	0.155	1.93E-02	10334.2	59763.1	
12	575.50	-2496.60	0.127	1.76E-02	6368.7	72139.2	
13	574.00	-2152.63	0.102	1.56E-02	2881.8	78897.6	
14	572.00	-1656.49	0.073	1.28E-02	-927.3	80388.1	
15	570.00	-1159.46	0.051	1.00E-02	-3743.3	75251.6	
16	568.00	-695.06	0.033	7.63E-03	-5597.8	65476.1	
17	566.00	-282.50	0.020	5.55E-03	-6575.4	53044.7	
18	564.00	83.79	0.010	3.93E-03	-6774.1	39193.0	
19	562.00	428.54	0.004	2.79E-03	-6261.7	25701.4	
20	560.00	725.49	-0.001	2.09E-03	-5107.7	13965.1	
21	558.00	979.02	-0.005	1.75E-03	-3403.2	5481.0	
22	556.50	1132.04	-0.007	1.66E-03	-1819.9	1467.1	
23	555.00	1294.50	-0.010	1.64E-03	-0.0	0.0	

(continued)

Stage No.3 Apply surcharge no.2 at elevation 591.00

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	517
2	589.50	0.00	272.35	0.00	0.00	0.00	0.00	3102
3	588.00	0.00	544.50	0.00	0.00	0.00	0.00	6203
4	586.50	0.00	816.25	0.00	0.00	0.00	0.00	9305
5	585.00	0.00	1087.42	0.00	0.00	0.00	0.00	12406
		0.00	1087.42	362.47	3262.25	362.47	362.47a	6239
6	583.50	0.00	1357.81	452.60	4073.43	452.60	452.60a	7799
7	582.00	0.00	1627.26	542.42	4881.77	542.42	542.42a	9358
8	581.50	0.00	1716.83	572.28	5150.50	572.28	572.28a	9878
9	581.00	0.00	1806.28	602.09	5418.84	602.09	602.09a	10398
10	579.00	0.00	2162.66	720.89	6487.97	720.89	720.89a	12478
11	577.00	0.00	2516.55	838.85	7549.64	849.63	849.63	14558
12	575.50	93.60	2686.55	895.52	8059.66	924.09	1017.69	16117
13	574.00	187.20	2854.89	951.63	8564.67	1002.60	1189.80	17677
14	572.00	312.00	3076.59	1025.53	9229.78	1113.40	1425.40	19757
15	570.00	436.80	3295.00	1098.33	9885.00	1231.55	1668.35	21836
16	568.00	561.60	3509.99	1170.00	10529.96	1357.84	1919.44	23916
17	566.00	686.40	3721.46	1240.49	11164.39	1492.93	2179.33	25996
18	564.00	811.20	3929.38	1309.79	11788.14	1636.71	2447.91	28075
19	562.00	936.00	4133.72	1377.91	12401.16	1788.36	2724.36	30155
20	560.00	1060.80	4334.49	1444.83	13003.47	1947.02	3007.82	32235
21	558.00	1185.60	4531.73	1510.58	13595.18	2112.34	3297.94	34314
22	556.50	1279.20	4677.37	1559.12	14032.10	2240.91	3520.11	35874
23	555.00	1372.80	4821.08	1607.03	14463.23	2373.72	3746.52	37434

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	517
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	3102
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	6203
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	9305
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	12406
		0.00	750.00	212.25	2652.75	2652.75	2652.75p	66699
6	583.50	0.00	937.50	265.31	3315.94	3315.94	3315.94p	66699
7	582.00	0.00	1125.00	318.38	3979.13	3979.13	3979.13p	66699
8	581.50	0.00	1187.50	336.06	4200.19	4200.19	4200.19p	66699
9	581.00	0.00	1250.00	353.75	4421.25	4421.25	4421.25p	66699
		0.00	1250.00	416.67	3750.00	3688.69	3688.69	10398
10	579.00	0.00	1500.00	500.00	4500.00	3756.08	3756.08	12478
11	577.00	0.00	1750.00	583.33	5250.00	3640.30	3640.30	14558
12	575.50	93.60	1843.90	614.63	5531.70	3420.69	3514.29	16117
13	574.00	187.20	1937.80	645.93	5813.40	3155.23	3342.43	17677
14	572.00	312.00	2063.00	687.67	6189.00	2769.89	3081.89	19757
15	570.00	436.80	2188.20	729.40	6564.60	2391.01	2827.81	21836
16	568.00	561.60	2313.40	771.13	6940.20	2052.91	2614.51	23916
17	566.00	686.40	2438.60	812.87	7315.80	1775.43	2461.83	25996
18	564.00	811.20	2563.80	854.60	7691.40	1552.92	2364.12	28075
19	562.00	936.00	2689.00	896.33	8067.00	1359.82	2295.82	30155
20	560.00	1060.80	2814.20	938.07	8442.60	1221.53	2282.33	32235
21	558.00	1185.60	2939.40	979.80	8818.20	1133.32	2318.92	34314
22	556.50	1279.20	3033.30	1011.10	9099.90	1108.87	2388.07	35874

Run ID. REV1_Ddmn_Fill_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.3

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)

Stage No.3 Apply surcharge no.2 at elevation 591.00

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
23	555.00	1372.80	3127.20	1042.40	9381.60	1079.22	2452.02	37434


Note: 720.89a Soil pressure at active limit
 4421.25p Soil pressure at passive limit

GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: REV1_Ddmn_Fill_LCX-3
 Pulliam Dock Wall - Deadman
 SSP Deadman - Fill_LCX.3


Sheet No.
 Job No. 2201593
 Made by : AJG
 Date:16-07-2025
 Checked :

Units: lb, ft

Stage No.3 Apply surcharge no.2 at elev. 591.00



Stage No.3 Apply surcharge no.2 at elev. 591.00



GEI CONSULTANTS, INC.	Sheet No.
Program: WALLAP Version 6.06 Revision A52.B71.R55	Job No. 2201593
Licensed from GEOSOLVE	Made by : AJG
Data filename/Run ID: REV1_Ddmn_Fill_LCX-3	
Pulliam Dock Wall - Deadman	Date:16-07-2025
SSP Deadman - Fill_LCX.3	Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
1	591.00	591.00	Cant.	1.573	562.33	556.50	34.50	L to R
2	591.00	591.00	No analysis at this stage					
3	591.00	591.00	Cant.	1.611	559.59	557.30	33.70	L to R
4	591.00	591.00	Cant.	1.470	559.33	***	***	L to R

Legend: *** Result not found

Units: lb,ft

Summary of results**BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall****Analysis options**

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Displacement</u>		<u>Bending moment</u>		<u>Shear force</u>	
		<u>maximum</u>	<u>minimum</u>	<u>maximum</u>	<u>minimum</u>	<u>maximum</u>	<u>minimum</u>
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	591.00	0.455	0.000	0.0	0.0	0.0	0.0
2	589.50	0.423	0.000	0.0	0.0	0.0	0.0
3	588.00	0.391	0.000	0.0	0.0	0.0	0.0
4	586.50	0.359	0.000	0.0	0.0	0.0	0.0
5	585.00	0.327	0.000	0.0	-0.0	0.0	0.0
6	583.50	0.295	0.000	0.0	-2928.4	0.0	-4054.6
7	582.00	0.263	0.000	0.0	-12614.4	0.0	-9010.3
8	581.50	0.252	0.000	0.0	-17578.5	24168.6	-10862.4
9	581.00	0.241	0.000	0.0	-6243.6	22381.8	0.0
10	579.00	0.198	0.000	33631.7	0.0	16348.9	0.0
11	577.00	0.157	0.000	60507.6	0.0	10503.7	0.0
12	575.50	0.129	0.000	73127.7	0.0	6602.7	0.0
13	574.00	0.103	0.000	80091.7	0.0	3249.2	0.0
14	572.00	0.074	0.000	81751.8	0.0	0.0	-927.3
15	570.00	0.051	0.000	76590.8	0.0	0.0	-3788.3
16	568.00	0.033	0.000	66659.8	0.0	0.0	-5694.5
17	566.00	0.020	0.000	53996.9	0.0	0.0	-6787.1
18	564.00	0.010	-0.001	39883.3	0.0	0.0	-7049.9
19	562.00	0.004	-0.005	26135.1	0.0	0.0	-6409.6
20	560.00	0.000	-0.008	14182.0	0.0	0.0	-5200.0
21	558.00	0.000	-0.009	5545.7	0.0	0.0	-3457.9
22	556.50	0.000	-0.010	1473.7	0.0	0.0	-1839.9
23	555.00	0.000	-0.011	0.0	0.0	0.0	-0.0

Maximum and minimum bending moment and shear force at each stage

Stage no.	Bending moment				Shear force			
	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	79401.1	572.00	-17578.5	581.50	23637.6	581.50	-10862.4	581.50
2	No calculation at this stage							
3	80388.1	572.00	-16758.2	581.50	24143.6	581.50	-10356.4	581.50
4	81751.8	572.00	-16754.0	581.50	24168.6	581.50	-10331.4	581.50

Maximum and minimum displacement at each stage

Stage no.	Displacement				<u>Stage description</u>
	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	
	ft		ft		
1	0.399	591.00	-0.011	555.00	Apply load no.1 at elev. 581.50
2	No calculation at this stage				Apply surcharge no.1 at elev. 591.00
3	0.448	591.00	-0.010	555.00	Apply surcharge no.2 at elev. 591.00
4	0.455	591.00	-0.010	555.00	Apply water pressure profile no.1

Run ID. REV1_Ddmn_Fill_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.3

| Sheet No.
| Date:16-07-2025
| Checked :


Summary of results (continued)

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_Fill_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.3

| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
DEADMAN WALLAP ANALYSIS: Fill – X.1						

GEI CONSULTANTS, INC. | Sheet No.
 Program: WALLAP Version 6.06 Revision A52.B71.R55 | Job No. 2201593
 Licensed from GEOSOLVE | Made by : AJG
 Data filename/Run ID: REV1_Ddmn_Fill_LCX-1 |
 Pulliam Dock Wall - Deadman | Date:16-07-2025
 SSP Deadman - Fill_LCX.1 | Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	591.00	9 Struc Fill_null	9 Struc Fill_null
2	585.00	2 Granular Fill - BW	1 Struc Fill
3	581.00	2 Granular Fill - BW	2 Granular Fill - BW
4	553.00	5 Clay IIA_und	5 Clay IIA_und

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	lb/ft3	Eh, lb/ft2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	lb/ft2 (dc/dy)
1 Struc Fill	125.0	0 (31000)	0.441	NC (0.300)	0.283 (0.000)	3.537 (0.000)	
2 Granular Fill - BW	125.0	0 (15000)	0.500	NC (0.330)	0.333 (0.000)	3.000 (0.000)	
3 Clay I_und	130.0	1200000	0.531	NC (0.490)	1.000 (2.000)	1.000 (2.000)	2000d
4 Clay I_drnd	130.0	1200000	0.531	OC (0.490)	0.361 (0.000)	2.770 (0.000)	
5 Clay IIA_und	130.0	600000	0.561	NC (0.490)	1.000 (2.000)	1.000 (2.000)	1000d
6 Clay IIA_drnd	130.0	600000	0.561	OC (0.490)	0.390 (0.000)	2.561 (0.000)	
7 Exist. Fill_drnd	130.0	1200000	0.500	NC (0.490)	0.333 (1.155)	3.000 (3.464)	0.0d
8 Limestone	100.0	0 (21000)	0.293	NC (0.290)	0.172 (0.000)	5.828 (0.000)	
9 Struc Fill_null	125.0	0 (31000)	0.000	NC (0.300)	0.000 (0.000)	0.000 (0.000)	
10 Existing Fill_null	130.0	0 (21000)	0.000	NC (0.290)	0.000 (0.000)	0.000 (0.000)	

Additional soil parameters associated with Ka and Kp

----- Soil type -----	--- parameters for Ka ---			--- parameters for Kp ---		
	Soil friction angle	Wall adhesion coeff.	Back-fill angle	Soil friction angle	Wall adhesion coeff.	Back-fill angle
1 Struc Fill	34.00	0.000	0.00	34.00	0.000	0.00
2 Granular Fill - BW	30.00	0.000	0.00	30.00	0.000	0.00
3 Clay I_und	0.00	0.000	0.00	0.00	0.000	0.00
4 Clay I_drnd	28.00	0.000	0.00	28.00	0.000	0.00
5 Clay IIA_und	0.00	0.000	0.00	0.00	0.000	0.00
6 Clay IIA_drnd	26.00	0.000	0.00	26.00	0.000	0.00
7 Exist. Fill_drnd	30.00	0.000	0.00	30.00	0.000	0.00
8 Limestone	45.00	0.000	0.00	45.00	0.000	0.00
9 Struc Fill_null	Incompatible values			Incompatible values		
10 Existing Fill_null	0.00	0.000	0.00	0.00	0.000	0.00

GROUND WATER CONDITIONS

Density of water = 62.40 lb/ft3

	Left side	Right side
Initial water table elevation	577.00	577.00

Automatic water pressure balancing at toe of wall : No

WALL PROPERTIES

Type of structure = Fully Embedded Wall
 Elevation of toe of wall = 555.00
 Maximum finite element length = 2.00 ft
 Youngs modulus of wall E = 4.1760E+09 lb/ft2
 Moment of inertia of wall I = 0.013653 ft4/ft run
 E.I = 5.7013E+07 lb.ft2/ft run
 Yield Moment of wall = Not defined

HORIZONTAL and MOMENT LOADS/RESTRAINTS

Load no.	Elevation	Horizontal load lb/ft run	Moment load lb.ft/ft run	Moment restraint lb.ft/ft/rad	Partial factor (Category)
1	581.50	34500	0	0	N/A

SURCHARGE LOADS

Surch -arge no.	Elev.	Distance from wall	Length parallel to wall	Width perpend. to wall	Surcharge ----- lb/ft2 ----- Near edge Far edge		Equiv. soil type	Partial factor/ Category
1	591.00	-0.00 (R)	1000.00	50.00	2143.00	0.00	N/A	N/A
2	591.00	0.00 (L)	1000.00	34.00	2143.00	3600.00	N/A	N/A
3	591.00	34.00 (L)	1000.00	150.00	3600.00	=	N/A	N/A

Note: L = Left side, R = Right side
 A trapezoidal surcharge is defined by two values:
 N = at edge near to wall, F = at edge far from wall

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Apply load no.1 at elevation 581.50
2	Apply surcharge no.1 at elevation 591.00 No analysis at this stage
3	Apply surcharge no.2 at elevation 591.00 No analysis at this stage

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:
 Method of analysis - CP2
 Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:
 Minimum equivalent fluid density = 0.00 lb/ft3
 Maximum depth of water filled tension crack = 0.00 ft

Bending moment and displacement calculation:
 Method - Subgrade reaction model using Influence Coefficients
 Open Tension Crack analysis? - No
 Non-linear Modulus Parameter (L) = 33.00 ft

Boundary conditions:
 Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft
 Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft
 Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Displacement	Active, Passive pressures	Graph. output
1	Apply load no.1 at elev. 581.50	Yes	Yes	Yes
2	Apply surcharge no.1 at elev. 591.00	No	No	No
3	Apply surcharge no.2 at elev. 591.00	Yes	Yes	Yes
*	Summary output	Yes	-	Yes


Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_Fill_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.1

| Sheet No.
| Job No. 2201593
| Made by : AJG
|
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.1 Apply load no.1 at elev. 581.50



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_Fill_LCX-1

Pulliam Dock Wall - Deadman

SSP Deadman - Fill_LCX.1

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Stage No. 1 Apply load no.1 at elevation 581.50

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
1	591.00	591.00	Cant.	1.573	562.33	556.50	34.50	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.399	1.94E-02	0.0	0.0	
2	589.50	0.00	0.370	1.94E-02	0.0	0.0	
3	588.00	0.00	0.340	1.94E-02	0.0	0.0	
4	586.50	0.00	0.311	1.94E-02	0.0	-0.0	
5	585.00	0.00	0.282	1.94E-02	0.0	0.0	
		-2402.75	0.282	1.94E-02	0.0	-0.0	
6	583.25	-3103.55	0.248	1.94E-02	-4818.0	-4036.9	
7	581.50	-3804.35	0.214	1.98E-02	-10862.4	-17578.5	34500.0
		-3804.35	0.214	1.98E-02	23637.6	-17578.5	
8	581.00	-4004.58	0.204	1.99E-02	21685.3	-6243.6	
		-2918.37	0.204	1.99E-02	21685.3	-6243.6	
9	579.00	-2869.55	0.164	1.94E-02	15897.4	31262.6	
10	577.00	-2648.23	0.127	1.79E-02	10379.6	57290.5	
11	575.50	-2386.82	0.101	1.62E-02	6603.3	69874.8	
12	574.00	-2084.46	0.078	1.43E-02	3249.9	77088.8	
13	572.00	-1657.38	0.052	1.15E-02	-492.0	79405.7	
14	570.00	-1245.76	0.032	8.87E-03	-3395.1	75093.1	
15	568.00	-884.74	0.016	6.40E-03	-5525.6	65797.5	
16	566.00	-376.90	0.006	4.32E-03	-6787.2	53233.8	
17	564.00	113.70	-0.001	2.70E-03	-7050.4	38905.5	
18	562.00	526.30	-0.005	1.58E-03	-6410.4	25032.0	
19	560.00	811.70	-0.008	9.10E-04	-5072.4	13263.7	
20	558.00	1001.35	-0.009	5.89E-04	-3259.4	5068.9	
21	556.50	1086.47	-0.010	5.05E-04	-1693.5	1312.1	
22	555.00	1171.57	-0.011	4.88E-04	-0.0	-0.0	

(continued)

Stage No.1 Apply load no.1 at elevation 581.50

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	663
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	3978
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	7956
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	11934
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	15912
		0.00	750.00	250.00	2250.00	250.00	250.00a	7977
6	583.25	0.00	968.75	322.92	2906.25	322.92	322.92a	10304
7	581.50	0.00	1187.50	395.83	3562.50	395.83	395.83a	12630
8	581.00	0.00	1250.00	416.67	3750.00	416.67	416.67a	13295
9	579.00	0.00	1500.00	500.00	4500.00	500.00	500.00a	15954
10	577.00	0.00	1750.00	583.33	5250.00	583.33	583.33a	18613
11	575.50	93.60	1843.90	614.63	5531.70	614.63	708.23a	20607
12	574.00	187.20	1937.80	645.93	5813.40	645.93	833.13a	22602
13	572.00	312.00	2063.00	687.67	6189.00	687.67	999.67a	25261
14	570.00	436.80	2188.20	729.40	6564.60	729.40	1166.20a	27920
15	568.00	561.60	2313.40	771.13	6940.20	771.13	1332.73a	30579
16	566.00	686.40	2438.60	812.87	7315.80	1030.85	1717.25	33238
17	564.00	811.20	2563.80	854.60	7691.40	1338.75	2149.95	44741
18	562.00	936.00	2689.00	896.33	8067.00	1607.65	2543.65	48055
19	560.00	1060.80	2814.20	938.07	8442.60	1812.95	2873.75	51369
20	558.00	1185.60	2939.40	979.80	8818.20	1981.15	3166.75	54684
21	556.50	1279.20	3033.30	1011.10	9099.90	2097.57	3376.77	57169
22	555.00	1372.80	3127.20	1042.40	9381.60	2213.97	3586.77	59655

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	663
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	3978
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	7956
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	11934
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	15912
		0.00	750.00	212.25	2652.75	2652.75	2652.75p	15912
6	583.25	0.00	968.75	274.16	3426.47	3426.47	3426.47p	20552
7	581.50	0.00	1187.50	336.06	4200.19	4200.19	4200.19p	25193
8	581.00	0.00	1250.00	353.75	4421.25	4421.25	4421.25p	26519
		0.00	1250.00	416.67	3750.00	3335.04	3335.04	13295
9	579.00	0.00	1500.00	500.00	4500.00	3369.55	3369.55	15954
10	577.00	0.00	1750.00	583.33	5250.00	3231.56	3231.56	18613
11	575.50	93.60	1843.90	614.63	5531.70	3001.46	3095.06	20607
12	574.00	187.20	1937.80	645.93	5813.40	2730.39	2917.59	22602
13	572.00	312.00	2063.00	687.67	6189.00	2345.05	2657.05	25261
14	570.00	436.80	2188.20	729.40	6564.60	1975.16	2411.96	27920
15	568.00	561.60	2313.40	771.13	6940.20	1655.88	2217.48	30579
16	566.00	686.40	2438.60	812.87	7315.80	1407.75	2094.15	33238
17	564.00	811.20	2563.80	854.60	7691.40	1225.05	2036.25	44741
18	562.00	936.00	2689.00	896.33	8067.00	1081.35	2017.35	48055
19	560.00	1060.80	2814.20	938.07	8442.60	1001.25	2062.05	51369
20	558.00	1185.60	2939.40	979.80	8818.20	979.80	2165.40a	54684
21	556.50	1279.20	3033.30	1011.10	9099.90	1011.10	2290.30a	57169
22	555.00	1372.80	3127.20	1042.40	9381.60	1042.40	2415.20a	59655

Run ID. REV1_Ddmn_Fill_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.1

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)


Stage No.1 Apply load no.1 at elevation 581.50
Note: 2415.20a Soil pressure at active limit
 4421.25p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_Fill_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.1


| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.1 Apply load no.1 at elev. 581.50



Stage No.1 Apply load no.1 at elev. 581.50




GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: REV1_Ddmn_Fill_LCX-1
 Pulliam Dock Wall - Deadman
 SSP Deadman - Fill_LCX.1

| Sheet No.
 | Job No. 2201593
 | Made by : AJG
 |
 | Date:16-07-2025
 | Checked :

Units: lb, ft

Stage No.3 Apply surcharge no.2 at elev. 591.00



GEI CONSULTANTS, INC.	Sheet No.
Program: WALLAP Version 6.06 Revision A52.B71.R55	Job No. 2201593
Licensed from GEOSOLVE	Made by : AJG
Data filename/Run ID: REV1_Ddmn_Fill_LCX-1	
Pulliam Dock Wall - Deadman	Date:16-07-2025
SSP Deadman - Fill_LCX.1	Checked :

Units: lb,ft

Stage No. 3 Apply surcharge no.2 at elevation 591.00
No analysis at this stage

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method
Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u>	<u>Pass.</u>	<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
				<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
3	591.00	591.00	Cant.	2.792	561.17	***	***	L to R

Legend: *** Result not found

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft
Subgrade reaction model - Boussinesq Influence coefficients
Soil deformations are elastic until the active or passive limit is reached
Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall
Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.481	2.18E-02	0.0	0.0	
2	589.50	0.00	0.448	2.18E-02	0.0	0.0	
3	588.00	0.00	0.415	2.18E-02	0.0	0.0	
4	586.50	0.00	0.383	2.18E-02	0.0	-0.0	
5	585.00	0.00	0.350	2.18E-02	0.0	0.0	
		-2380.80	0.350	2.18E-02	0.0	-0.0	
6	583.25	-3291.93	0.312	2.18E-02	-4963.6	-3975.3	
7	581.50	-4160.69	0.273	2.22E-02	-11484.7	-18033.5	34500.0
		-4160.69	0.273	2.22E-02	23015.3	-18033.5	
8	581.00	-4401.07	0.262	2.23E-02	20874.9	-7053.6	
		-2722.46	0.262	2.23E-02	20874.9	-7053.6	
9	579.00	-2729.21	0.218	2.19E-02	15423.2	28826.7	
10	577.00	-2539.69	0.175	2.04E-02	10154.3	54190.9	
11	575.50	-2286.57	0.145	1.89E-02	6534.6	66827.0	
12	574.00	-1963.98	0.118	1.70E-02	3346.7	74057.1	
13	572.00	-1467.81	0.087	1.44E-02	-85.1	76821.5	
14	570.00	-937.77	0.061	1.17E-02	-2490.6	73712.1	
15	568.00	-688.88	0.040	9.30E-03	-4117.3	66663.9	
16	566.00	-480.17	0.023	7.13E-03	-5286.3	56977.0	
17	564.00	-241.80	0.011	5.34E-03	-6008.3	45121.9	
18	562.00	13.76	0.002	3.98E-03	-6236.3	32349.6	
19	560.00	277.26	-0.005	3.07E-03	-5945.3	19715.7	
20	558.00	844.49	-0.011	2.57E-03	-4823.6	8579.9	
21	556.50	1674.52	-0.015	2.43E-03	-2934.3	2268.2	
22	555.00	2237.92	-0.018	2.40E-03	-0.0	-0.0	

(continued)

Stage No.3 Apply surcharge no.2 at elevation 591.00
 No analysis at this stage

		LEFT side					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	2143.00	0.00	0.00	0.00	0.00	512
2	589.50	0.00	2371.23	0.00	0.00	0.00	0.00	3070
3	588.00	0.00	2598.57	0.00	0.00	0.00	0.00	6139
4	586.50	0.00	2824.07	0.00	0.00	0.00	0.00	9209
5	585.00	0.00	3046.91	0.00	0.00	0.00	0.00	12278
		0.00	3046.91	1015.64	9140.72	1104.63	1104.63	6176
6	583.25	0.00	3302.58	1100.86	9907.75	1143.71	1143.71	7977
7	581.50	0.00	3552.76	1184.25	10658.28	1195.13	1195.13	9778
8	581.00	0.00	3623.13	1207.71	10869.39	1212.07	1212.07	10293
9	579.00	0.00	3899.38	1299.79	11698.13	1299.79	1299.79a	12352
10	577.00	0.00	4166.98	1388.99	12500.93	1388.99	1388.99a	14410
11	575.50	93.60	4268.36	1422.79	12805.09	1424.53	1518.13	15954
12	574.00	187.20	4364.97	1454.99	13094.92	1474.45	1661.65	17498
13	572.00	312.00	4486.71	1495.57	13460.14	1560.30	1872.30	19557
14	570.00	436.80	4600.99	1533.66	13802.96	1668.94	2105.74	21615
15	568.00	561.60	4708.59	1569.53	14125.77	1799.76	2361.36	23674
16	566.00	686.40	4810.39	1603.46	14431.18	1949.77	2636.17	25732
17	564.00	811.20	4907.28	1635.76	14721.83	2113.74	2924.94	27791
18	562.00	936.00	5000.09	1666.70	15000.27	2285.64	3221.64	29849
19	560.00	1060.80	5089.63	1696.54	15268.90	2461.04	3521.84	31908
20	558.00	1185.60	5176.63	1725.54	15529.89	2788.02	3973.62	132849
21	556.50	1279.20	5240.60	1746.87	15721.79	3235.48	4514.68	138888
22	555.00	1372.80	5303.73	1767.91	15911.20	3710.86	5083.66	144926

		RIGHT side					Total earth pressure lb/ft2	Coeff. of subgrade reaction lb/ft3
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	2143.00	0.00	0.00	0.00	0.00	512
2	589.50	0.00	2289.55	0.00	0.00	0.00	0.00	3070
3	588.00	0.00	2436.22	0.00	0.00	0.00	0.00	6139
4	586.50	0.00	2583.03	0.00	0.00	0.00	0.00	9209
5	585.00	0.00	2730.05	0.00	0.00	0.00	0.00	12278
		0.00	2730.05	772.60	9656.18	3485.44	3485.44	12278
6	583.25	0.00	2901.94	821.25	10264.16	4435.63	4435.63	15860
7	581.50	0.00	3074.33	870.03	10873.89	5355.81	5355.81	19441
8	581.00	0.00	3123.68	884.00	11048.46	5613.14	5613.14	20464
		0.00	3123.68	1041.23	9371.05	3934.53	3934.53	10293
9	579.00	0.00	3321.64	1107.21	9964.91	4029.00	4029.00	12352
10	577.00	0.00	3520.52	1173.51	10561.57	3928.68	3928.68	14410
11	575.50	93.60	3576.77	1192.26	10730.32	3711.10	3804.70	15954
12	574.00	187.20	3633.66	1211.22	10900.97	3438.43	3625.63	17498
13	572.00	312.00	3710.55	1236.85	11131.65	3028.11	3340.11	19557
14	570.00	436.80	3788.71	1262.90	11366.12	2606.71	3043.51	21615
15	568.00	561.60	3868.19	1289.40	11604.56	2488.63	3050.23	23674
16	566.00	686.40	3949.03	1316.34	11847.10	2429.94	3116.34	25732
17	564.00	811.20	4031.28	1343.76	12093.83	2355.54	3166.74	27791
18	562.00	936.00	4114.93	1371.64	12344.80	2271.87	3207.87	29849
19	560.00	1060.80	4200.00	1400.00	12600.01	2183.78	3244.58	31908
20	558.00	1185.60	4286.49	1428.83	12859.46	1943.54	3129.14	132849
21	556.50	1279.20	4352.27	1450.76	13056.80	1560.96	2840.16	138888
22	555.00	1372.80	4418.82	1472.94	13256.47	1472.94	2845.74a	144926

Run ID. REV1_Ddmn_Fill_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.1

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)


Stage No.3 Apply surcharge no.2 at elevation 591.00
 No analysis at this stage
Note: 2845.74a Soil pressure at active limit
 123.45p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_Fill_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.1


Sheet No.
Job No. 2201593
Made by : AJG
Date:16-07-2025
Checked :

Units: lb, ft

Stage No.3 Apply surcharge no.2 at elev. 591.00



Stage No.3 Apply surcharge no.2 at elev. 591.00



GEI CONSULTANTS, INC.	Sheet No.
Program: WALLAP Version 6.06 Revision A52.B71.R55	Job No. 2201593
Licensed from GEOSOLVE	Made by : AJG
Data filename/Run ID: REV1_Ddmn_Fill_LCX-1	
Pulliam Dock Wall - Deadman	Date:16-07-2025
SSP Deadman - Fill_LCX.1	Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u>	<u>Pass.</u>	<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u> <u>Factor of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe elev. for</u> <u>FoS = 1.500</u> <u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	<u>Direction</u> <u>of</u> <u>failure</u>
1	591.00	591.00	Cant.	1.573	562.33	556.50	34.50	L to R
2	591.00	591.00		No analysis at this stage				
3	591.00	591.00	Cant.	2.792	561.17	***	***	L to R

Legend: *** Result not found

Units: lb,ft

Summary of results**BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall****Analysis options**

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Displacement</u>		<u>Bending moment</u>		<u>Shear force</u>	
		<u>maximum</u>	<u>minimum</u>	<u>maximum</u>	<u>minimum</u>	<u>maximum</u>	<u>minimum</u>
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	591.00	0.481	0.000	0.0	0.0	0.0	0.0
2	589.50	0.448	0.000	0.0	0.0	0.0	0.0
3	588.00	0.415	0.000	0.0	0.0	0.0	0.0
4	586.50	0.383	0.000	0.0	-0.0	0.0	0.0
5	585.00	0.350	0.000	0.0	-0.0	0.0	0.0
6	583.25	0.312	0.000	0.0	-4036.9	0.0	-4963.6
7	581.50	0.273	0.000	0.0	-18033.5	23637.6	-11484.7
8	581.00	0.262	0.000	0.0	-7053.6	21685.3	0.0
9	579.00	0.218	0.000	31262.6	0.0	15897.4	0.0
10	577.00	0.175	0.000	57290.5	0.0	10379.6	0.0
11	575.50	0.145	0.000	69874.8	0.0	6603.3	0.0
12	574.00	0.118	0.000	77088.8	0.0	3346.7	0.0
13	572.00	0.087	0.000	79405.7	0.0	0.0	-492.0
14	570.00	0.061	0.000	75093.1	0.0	0.0	-3395.1
15	568.00	0.040	0.000	66663.9	0.0	0.0	-5525.6
16	566.00	0.023	0.000	56977.0	0.0	0.0	-6787.2
17	564.00	0.011	-0.001	45121.9	0.0	0.0	-7050.4
18	562.00	0.002	-0.005	32349.6	0.0	0.0	-6410.4
19	560.00	0.000	-0.008	19715.7	0.0	0.0	-5945.3
20	558.00	0.000	-0.011	8579.9	0.0	0.0	-4823.6
21	556.50	0.000	-0.015	2268.2	0.0	0.0	-2934.3
22	555.00	0.000	-0.018	0.0	-0.0	0.0	-0.0

Maximum and minimum bending moment and shear force at each stage

Stage no.	Bending moment				Shear force			
	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	79405.7	572.00	-17578.5	581.50	23637.6	581.50	-10862.4	581.50
2	No calculation at this stage							
3	76821.5	572.00	-18033.5	581.50	23015.3	581.50	-11484.7	581.50

Maximum and minimum displacement at each stage

Stage no.	Displacement				<u>Stage description</u>
	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	
	ft		ft		
1	0.399	591.00	-0.011	555.00	Apply load no.1 at elev. 581.50
2	No calculation at this stage				Apply surcharge no.1 at elev. 591.00
3	0.481	591.00	-0.018	555.00	Apply surcharge no.2 at elev. 591.00

Run ID. REV1_Ddmn_Fill_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.1

| Sheet No.
| Date:16-07-2025
| Checked :


Summary of results (continued)

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_Fill_LCX-1
Pulliam Dock Wall - Deadman
SSP Deadman - Fill_LCX.1

| Sheet No.
| Job No. 2201593
| Made by : AJG
|
| Date:16-07-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
DEADMAN WALLAP ANALYSIS: Fill – X.3						

GEI CONSULTANTS, INC.	Sheet No.
Program: WALLAP Version 6.06 Revision A52.B71.R55	Job No. 2201593
Licensed from GEOSOLVE	Made by : AJG
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3	
Pulliam Dock Wall - Deadman	Date:16-07-2025
SSP Deadman - BL-14-22_LCX.3	Checked :

Units: lb,ft

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	591.00	9 Struc Fill_null	9 Struc Fill_null
2	585.00	2 Existing Fill_und	1 Struc Fill
3	581.00	2 Existing Fill_und	2 Existing Fill_und
4	577.00	3 Clay I_und	3 Clay I_und
5	554.00	5 Clay IIA_und	5 Clay IIA_und

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description	lb/ft3	Eh, lb/ft2	Ko	NC/OC	Ka	Kp	lb/ft2
(Datum elev.)		(dEh/dy)	(dKo/dy)	(Nu)	(Kac)	(Kpc)	(dc/dy)
1 Struc Fill	125.0	0	0.441	NC	0.283	3.537	
		(31000)		(0.300)	(0.000)	(0.000)	
2 Existing Fill_und	130.0	1200000	0.500	NC	1.000	1.000	2000d
				(0.490)	(2.000)	(2.000)	
3 Clay I_und	130.0	1200000	0.531	NC	1.000	1.000	2000d
				(0.490)	(2.000)	(2.000)	
4 Clay I_drnd	130.0	1200000	0.531	OC	0.361	2.770	
				(0.490)	(0.000)	(0.000)	
5 Clay IIA_und	130.0	600000	0.561	NC	1.000	1.000	1000d
				(0.490)	(2.000)	(2.000)	
6 Clay IIA_drnd	130.0	600000	0.561	OC	0.390	2.561	
				(0.490)	(0.000)	(0.000)	
7 Exist. Fill_drnd	130.0	1200000	0.500	NC	0.333	3.000	0.0d
				(0.490)	(1.155)	(3.464)	
8 Limestone	100.0	0	0.293	NC	0.172	5.828	
		(21000)		(0.290)	(0.000)	(0.000)	
9 Struc Fill_null	125.0	0	0.000	NC	0.000	0.000	
		(31000)		(0.300)	(0.000)	(0.000)	
10 Existing Fill_null	130.0	0	0.000	NC	0.000	0.000	
		(21000)		(0.290)	(0.000)	(0.000)	

Additional soil parameters associated with Ka and Kp

			--- parameters for Ka ---			--- parameters for Kp ---		
			Soil friction	Wall adhesion	Back-fill	Soil friction	Wall adhesion	Back-fill
----- Soil type -----			angle	coeff.	angle	angle	coeff.	angle
No. Description								
1 Struc Fill			34.00	0.000	0.00	34.00	0.000	0.00
2 Existing Fill_und			0.00	0.000	0.00	0.00	0.000	0.00
3 Clay I_und			0.00	0.000	0.00	0.00	0.000	0.00
4 Clay I_drnd			28.00	0.000	0.00	28.00	0.000	0.00
5 Clay IIA_und			0.00	0.000	0.00	0.00	0.000	0.00
6 Clay IIA_drnd			26.00	0.000	0.00	26.00	0.000	0.00
7 Exist. Fill_drnd			30.00	0.000	0.00	30.00	0.000	0.00
8 Limestone			45.00	0.000	0.00	45.00	0.000	0.00
9 Struc Fill_null			Incompatible values			Incompatible values		
10 Existing Fill_null			0.00	0.000	0.00	0.00	0.000	0.00

Density of water = 62.40 lb/ft³

Automatic water pressure balancing at toe of wall : No

```

Type of structure = Fully Embedded Wall
Elevation of toe of wall = 555.00
Maximum finite element length = 2.00 ft
Youngs modulus of wall E = 4.1760E+09 lb/ft2
Moment of inertia of wall I = 8.2800E-03 ft4/ft run
E.I = 3.4577E+07 lb.ft2/ft run
Yield Moment of wall = Not defined

```

Load no.	Elevation	Horizontal load lb/ft run	Moment load lb.ft/ft run	Moment restraint lb.ft/ft/rad	Partial factor (Category)
1	581.50	34500	0	0	N/A

Surcharge no.	Elev.	Distance	Length	Width	Surcharge		Equiv. soil type	Partial factor/Category
		from wall	parallel to wall	perpend. to wall	----- lb/ft2 -----	-----		
1	591.00	0.00 (L)	1000.00	45.00	0.00	4000.00	N/A	N/A
2	591.00	45.00 (L)	1000.00	100.00	4000.00	=	N/A	N/A

Note: L = Left side, R = Right side
A trapezoidal surcharge is defined by two values:
N = at edge near to wall, F = at edge far from wall

Construction stage no.	Stage description
1	Apply load no.1 at elevation 581.50
2	Apply surcharge no.1 at elevation 591.00 No analysis at this stage
3	Apply surcharge no.2 at elevation 591.00
4	Change properties of soil type 2 to soil type 7 No analysis at this stage Ko pressures will not be reset
5	Change properties of soil type 3 to soil type 4 Ko pressures will not be reset

Stability analysis:
Method of analysis - CP2
Factor on passive for calculating wall depth = 1.50

Parameters for undrained strata:

Minimum equivalent fluid density	=	0.00 lb/ft3
Maximum depth of water filled tension crack	=	0.00 ft

Bending moment and displacement calculation:
Method - Subgrade reaction model using Influence Coefficients
Open Tension Crack analysis? - No
Non-linear Modulus Parameter (L) = 33.00 ft

Boundary conditions:
Length of wall (normal to plane of analysis) = 1000.00 ft

Width of excavation on Left side of wall = 1000.00 ft
Width of excavation on Right side of wall = 1000.00 ft

Distance to rigid boundary on Left side = 1000.00 ft
Distance to rigid boundary on Right side = 1000.00 ft

OUTPUT OPTIONS

Stage no.	Stage description	Displacement Bending mom. Shear force	Active, Passive pressures	Graph. output
1	Apply load no.1 at elev. 581.50	Yes	Yes	Yes
2	Apply surcharge no.1 at elev. 591.00	No	No	No
3	Apply surcharge no.2 at elev. 591.00	Yes	Yes	Yes
4	Change soil type 2 to soil type 7	No	No	No
5	Change soil type 3 to soil type 4	Yes	Yes	Yes
*	Summary output	Yes	-	Yes


Program WALLAP - Copyright (C) 2017 by DL Borin, distributed by GEOSOLVE
150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

GEI CONSULTANTS, INC.
 Program: WALLAP Version 6.06 Revision A52.B71.R55
 Licensed from GEOSOLVE
 Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3
 Pulliam Dock Wall - Deadman
 SSP Deadman - BL-14-22_LCX.3

| Sheet No.
 | Job No. 2201593
 | Made by : AJG
 | Date:16-07-2025
 | Checked :

Units: lb, ft

Stage No.1 Apply load no.1 at elev. 581.50



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.3

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Stage No. 1 Apply load no.1 at elevation 581.50

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
1	591.00	591.00	Cant.	1.920	563.07	561.83	29.17	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.180	1.12E-02	0.0	0.0	
2	589.50	0.00	0.164	1.12E-02	0.0	0.0	
3	588.00	0.00	0.147	1.12E-02	0.0	-0.0	
4	586.50	0.00	0.130	1.12E-02	0.0	0.0	
5	585.00	0.00	0.113	1.12E-02	0.0	-0.0	
		-2401.87	0.113	1.12E-02	0.0	0.0	
6	583.25	-2633.97	0.093	1.13E-02	-4406.4	-3727.1	
7	581.50	-2641.45	0.073	1.18E-02	-9022.3	-15520.7	34500.0
		-2641.45	0.073	1.18E-02	25477.7	-15520.7	
8	581.00	-2598.10	0.067	1.19E-02	24167.8	-3113.2	
		-5250.00	0.067	1.19E-02	24167.8	-3113.2	
9	579.00	-5510.00	0.044	1.10E-02	13407.8	34549.0	
10	577.00	-4661.97	0.024	8.52E-03	3235.8	53427.8	
		-4716.84	0.024	8.52E-03	3235.8	53427.8	
11	575.50	-3011.66	0.013	6.22E-03	-2560.6	52954.9	
12	574.00	-1581.47	0.005	4.07E-03	-6005.4	46102.5	
13	572.00	269.90	-0.001	1.84E-03	-7317.0	30928.8	
14	570.00	1005.82	-0.003	4.62E-04	-6041.3	16834.6	
15	568.00	1055.10	-0.003	-2.20E-04	-3980.4	6763.6	
16	566.00	811.49	-0.002	-4.42E-04	-2113.8	913.1	
17	564.00	510.84	-0.001	-4.19E-04	-791.4	-1691.5	
18	562.00	263.19	-0.001	-3.05E-04	-17.4	-2252.7	
19	560.00	97.01	-0.000	-1.89E-04	342.8	-1761.1	
20	558.00	-21.76	0.000	-1.12E-04	418.0	-881.5	
21	556.50	-143.83	0.000	-8.77E-05	293.8	-279.0	
22	555.00	-247.96	0.000	-8.17E-05	-0.0	-0.0	

(continued)

Stage No.1 Apply load no.1 at elevation 581.50

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	764
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	4586
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	9173
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	13759
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	18346
		0.00	750.00	0.00	4750.00	0.00	0.00a	159067
6	583.25	0.00	977.50	0.00	4977.50	0.00	0.00a	159067
7	581.50	0.00	1205.00	0.00	5205.00	0.00	0.00a	159067
8	581.00	0.00	1270.00	0.00	5270.00	0.00	0.00a	159067
9	579.00	0.00	1530.00	0.00	5530.00	0.00	0.00a	159067
10	577.00	0.00	1790.00	0.00	5790.00	0.00	0.00a	159067
11	575.50	93.60	1891.40	0.00	5891.40	0.00	93.60a	159067
12	574.00	187.20	1992.80	0.00	5992.80	262.13	449.33	159067
13	572.00	312.00	2128.00	0.00	6128.00	1259.61	1571.61	169536
14	570.00	436.80	2263.20	0.00	6263.20	1699.36	2136.16	169536
15	568.00	561.60	2398.40	0.00	6398.40	1795.79	2357.39	169536
16	566.00	686.40	2533.60	0.00	6533.60	1745.78	2432.18	169536
17	564.00	811.20	2668.80	0.00	6668.80	1667.24	2478.44	169536
18	562.00	936.00	2804.00	0.00	6804.00	1615.21	2551.21	169536
19	560.00	1060.80	2939.20	0.00	6939.20	1603.91	2664.71	169536
20	558.00	1185.60	3074.40	0.00	7074.40	1616.32	2801.92	414445
21	556.50	1279.20	3175.80	0.00	7175.80	1609.12	2888.32	414445
22	555.00	1372.80	3277.20	0.00	7277.20	1610.91	2983.71	414445

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	764
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	4586
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	9173
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	13759
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	18346
		0.00	750.00	212.04	2652.75	2401.87	2401.87	18346
6	583.25	0.00	968.75	273.88	3426.47	2633.97	2633.97	23697
7	581.50	0.00	1187.50	335.72	4200.19	2641.45	2641.45	29047
8	581.00	0.00	1250.00	353.39	4421.25	2598.10	2598.10	30576
		0.00	1250.00	0.00	5250.00	5250.00	5250.00p	159067
9	579.00	0.00	1510.00	0.00	5510.00	5510.00	5510.00p	159067
10	577.00	0.00	1770.00	0.00	5770.00	4661.97	4661.97	159067
		0.00	1770.00	0.00	5770.00	4716.84	4716.84	159067
11	575.50	93.60	1871.40	0.00	5871.40	3011.66	3105.26	159067
12	574.00	187.20	1972.80	0.00	5972.80	1843.60	2030.80	159067
13	572.00	312.00	2108.00	0.00	6108.00	989.71	1301.71	169536
14	570.00	436.80	2243.20	0.00	6243.20	693.54	1130.34	169536
15	568.00	561.60	2378.40	0.00	6378.40	740.69	1302.29	169536
16	566.00	686.40	2513.60	0.00	6513.60	934.29	1620.69	169536
17	564.00	811.20	2648.80	0.00	6648.80	1156.40	1967.60	169536
18	562.00	936.00	2784.00	0.00	6784.00	1352.02	2288.02	169536
19	560.00	1060.80	2919.20	0.00	6919.20	1506.90	2567.70	169536
20	558.00	1185.60	3054.40	0.00	7054.40	1638.08	2823.68	414445
21	556.50	1279.20	3155.80	0.00	7155.80	1752.96	3032.16	414445
22	555.00	1372.80	3257.20	0.00	7257.20	1858.86	3231.66	414445

Run ID. REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)


Stage No.1 Apply load no.1 at elevation 581.50
Note: 93.60a Soil pressure at active limit
 5510.00p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3


Sheet No.
Job No. 2201593
Made by : AJG
Date:16-07-2025
Checked :

Units: lb, ft

Stage No.1 Apply load no.1 at elev. 581.50



Stage No.1 Apply load no.1 at elev. 581.50




GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3

| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.3 Apply surcharge no.2 at elev. 591.00



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.3

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Stage No. 3 Apply surcharge no.2 at elevation 591.00

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
3	591.00	591.00	Cant.	2.015	561.99	562.82	28.18	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> lb/ft2	<u>Wall</u> <u>disp.</u> ft	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> lb/ft	<u>Bending</u> <u>moment</u> lb.ft/ft	<u>Prop</u> <u>forces</u> lb/ft
1	591.00	0.00	0.189	1.15E-02	0.0	0.0	
2	589.50	0.00	0.172	1.15E-02	0.0	0.0	
3	588.00	0.00	0.155	1.15E-02	0.0	-0.0	
4	586.50	0.00	0.137	1.15E-02	0.0	0.0	
5	585.00	0.00	0.120	1.15E-02	0.0	-0.0	
		-2465.50	0.120	1.15E-02	0.0	0.0	
6	583.25	-2710.23	0.100	1.16E-02	-4528.8	-3824.5	
7	581.50	-2727.00	0.079	1.21E-02	-9286.3	-15679.0	34500.0
		-2727.00	0.079	1.21E-02	25213.7	-15679.0	
8	581.00	-2645.84	0.073	1.22E-02	23870.5	-3413.0	
		-5209.34	0.073	1.22E-02	23870.5	-3413.0	
9	579.00	-5307.80	0.049	1.14E-02	13353.3	33806.8	
10	577.00	-4693.74	0.028	8.89E-03	3351.8	53050.4	
		-4748.61	0.028	8.89E-03	3351.8	53050.4	
11	575.50	-2869.78	0.017	6.59E-03	-2362.0	52744.2	
12	574.00	-1265.81	0.008	4.44E-03	-5463.7	46377.2	
13	572.00	201.24	0.002	2.16E-03	-6528.3	32579.2	
14	570.00	710.09	-0.001	6.53E-04	-5617.0	19712.8	
15	568.00	818.95	-0.001	-2.03E-04	-4087.9	9914.4	
16	566.00	718.78	-0.000	-5.91E-04	-2550.2	3488.2	
17	564.00	537.45	0.001	-6.90E-04	-1294.0	-45.1	
18	562.00	347.19	0.002	-6.47E-04	-409.3	-1447.6	
19	560.00	178.51	0.004	-5.62E-04	116.4	-1489.7	
20	558.00	25.14	0.005	-4.95E-04	320.0	-834.8	
21	556.50	-108.67	0.005	-4.71E-04	257.4	-293.3	
22	555.00	-234.51	0.006	-4.64E-04	-0.0	-0.0	

(continued)

Stage No.3 Apply surcharge no.2 at elevation 591.00

		LEFT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	374
2	589.50	0.00	272.35	0.00	0.00	0.00	0.00	2242
3	588.00	0.00	544.50	0.00	0.00	0.00	0.00	4484
4	586.50	0.00	816.25	0.00	0.00	0.00	0.00	6727
5	585.00	0.00	1087.42	0.00	0.00	0.00	0.00	8969
		0.00	1087.42	0.00	5087.42	0.00	0.00a	87198
6	583.25	0.00	1411.54	0.00	5411.54	0.00	0.00a	87198
7	581.50	0.00	1734.33	0.00	5734.33	0.56	0.56	87198
8	581.00	0.00	1826.28	0.00	5826.28	40.66	40.66	87198
9	579.00	0.00	2192.66	0.00	6192.66	202.20	202.20	87198
10	577.00	0.00	2556.55	0.00	6556.55	367.39	367.39	87198
11	575.50	93.60	2734.05	0.00	6734.05	492.27	585.87	87198
12	574.00	187.20	2909.89	0.00	6909.89	878.51	1065.71	87198
13	572.00	312.00	3141.59	0.00	7141.59	1429.57	1741.57	87198
14	570.00	436.80	3370.00	0.00	7370.00	1596.55	2033.35	87198
15	568.00	561.60	3594.99	0.00	7594.99	1734.29	2295.89	87198
16	566.00	686.40	3816.46	0.00	7816.46	1839.81	2526.21	87198
17	564.00	811.20	4034.38	34.38	8034.38	1918.05	2729.25	87198
18	562.00	936.00	4248.72	248.72	8248.72	1977.64	2913.64	87198
19	560.00	1060.80	4459.49	459.49	8459.49	2026.70	3087.50	87198
20	558.00	1185.60	4666.73	666.73	8666.73	2070.62	3256.22	87198
21	556.50	1279.20	4819.87	819.87	8819.87	2101.82	3381.02	87198
22	555.00	1372.80	4971.08	971.08	8971.08	2132.00	3504.80	87198

		RIGHT side					Total earth pressure	Coeff. of subgrade reaction
Node no.	Y coord	Water press. lb/ft2	Vertic -al lb/ft2	Effective stresses Active limit lb/ft2	Passive limit lb/ft2	Earth pressure lb/ft2		
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	374
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	2242
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	4484
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	6727
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	8969
		0.00	750.00	212.04	2652.75	2465.50	2465.50	8969
6	583.25	0.00	968.75	273.88	3426.47	2710.23	2710.23	11585
7	581.50	0.00	1187.50	335.72	4200.19	2727.56	2727.56	14201
8	581.00	0.00	1250.00	353.39	4421.25	2686.50	2686.50	14948
		0.00	1250.00	0.00	5250.00	5250.00	5250.00p	87198
9	579.00	0.00	1510.00	0.00	5510.00	5510.00	5510.00p	87198
10	577.00	0.00	1770.00	0.00	5770.00	5061.13	5061.13	87198
		0.00	1770.00	0.00	5770.00	5116.00	5116.00	87198
11	575.50	93.60	1871.40	0.00	5871.40	3362.05	3455.65	87198
12	574.00	187.20	1972.80	0.00	5972.80	2144.32	2331.52	87198
13	572.00	312.00	2108.00	0.00	6108.00	1228.33	1540.33	87198
14	570.00	436.80	2243.20	0.00	6243.20	886.46	1323.26	87198
15	568.00	561.60	2378.40	0.00	6378.40	915.34	1476.94	87198
16	566.00	686.40	2513.60	0.00	6513.60	1121.02	1807.42	87198
17	564.00	811.20	2648.80	0.00	6648.80	1380.61	2191.81	87198
18	562.00	936.00	2784.00	0.00	6784.00	1630.45	2566.45	87198
19	560.00	1060.80	2919.20	0.00	6919.20	1848.19	2908.99	87198
20	558.00	1185.60	3054.40	0.00	7054.40	2045.48	3231.08	87198
21	556.50	1279.20	3155.80	0.00	7155.80	2210.49	3489.69	87198
22	555.00	1372.80	3257.20	0.00	7257.20	2366.51	3739.31	87198

Run ID. REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)

Stage No.3 Apply surcharge no.2 at elevation 591.00


Note: 0.00a Soil pressure at active limit
 5510.00p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3


| Sheet No.
| Job No. 2201593
| Made by : AJG
|
| Date:16-07-2025
Checked :


Units: lb, ft

Stage No.3 Apply surcharge no.2 at elev. 591.00



Stage No.3 Apply surcharge no.2 at elev. 591.00





GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.3

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Stage No. 5 Change properties of soil type 3 to soil type 4

Ko pressures will not be reset

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

			FoS for toe elev. = 555.00		Toe elev. for FoS = 1.500			
<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u>	<u>level</u> <u>Pass.</u>	<u>Prop</u> <u>Elev.</u>	<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	<u>Direction</u> <u>of</u> <u>failure</u>
5	591.00	591.00	Cant.	1.538	559.50	555.87	35.13	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Node	Y	Nett	Wall	Wall	Shear	Bending	Prop
no.	coord	pressure	disp.	rotation	force	moment	forces
		lb/ft ²	ft	rad.	lb/ft	lb.ft/ft	lb/ft
1	591.00	0.00	0.282	1.65E-02	0.0	0.0	
2	589.50	0.00	0.257	1.65E-02	0.0	0.0	
3	588.00	0.00	0.232	1.65E-02	0.0	-0.0	
4	586.50	0.00	0.208	1.65E-02	0.0	0.0	
5	585.00	0.00	0.183	1.65E-02	0.0	-0.0	
		-2290.28	0.183	1.65E-02	0.0	0.0	
6	583.25	-2955.96	0.154	1.66E-02	-4590.5	-3771.1	
7	581.50	-3356.97	0.125	1.70E-02	-10114.3	-15689.5	34500.0
		-3356.97	0.125	1.70E-02	24385.7	-15689.5	
8	581.00	-3279.67	0.116	1.72E-02	22726.6	-3916.7	
		-3141.24	0.116	1.72E-02	22726.6	-3916.7	
9	579.00	-3799.11	0.082	1.63E-02	15786.2	34778.6	
10	577.00	-4457.82	0.052	1.35E-02	7529.3	61056.9	
		-3979.59	0.052	1.35E-02	7529.3	61056.9	
11	575.50	-4196.37	0.033	1.07E-02	1397.3	67096.3	
12	574.00	-2699.80	0.019	7.92E-03	-3774.8	65437.9	
13	572.00	-845.71	0.007	4.53E-03	-7320.3	51838.0	
14	570.00	284.74	0.001	2.00E-03	-7881.3	35490.6	
15	568.00	948.98	-0.002	3.90E-04	-6647.6	20350.6	
16	566.00	1091.49	-0.001	-4.59E-04	-4607.1	9027.4	
17	564.00	913.03	-0.000	-7.81E-04	-2602.6	2125.7	
18	562.00	632.43	0.002	-8.10E-04	-1057.1	-1142.8	
19	560.00	354.34	0.003	-7.22E-04	-70.3	-1910.0	
20	558.00	103.24	0.004	-6.29E-04	387.2	-1276.9	
21	556.50	-79.90	0.005	-5.90E-04	404.8	-546.7	
22	555.00	-459.77	0.006	-5.78E-04	-0.0	-0.0	

(continued)

Stage No.5 Change properties of soil type 3 to soil type 4
 Ko pressures will not be reset

LEFT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press.	Vertic -al	Active limit	Passive limit	Earth pressure		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	698
2	589.50	0.00	272.35	0.00	0.00	0.00	0.00	4187
3	588.00	0.00	544.50	0.00	0.00	0.00	0.00	8373
4	586.50	0.00	816.25	0.00	0.00	0.00	0.00	12560
5	585.00	0.00	1087.42	0.00	0.00	0.00	0.00	16747
		0.00	1087.42	362.47	3262.25	362.47	362.47a	146282
6	583.25	0.00	1411.54	470.51	4234.62	470.51	470.51a	146282
7	581.50	0.00	1734.33	578.11	5203.00	578.11	578.11a	146282
8	581.00	0.00	1826.28	608.76	5478.84	608.76	608.76a	146282
9	579.00	0.00	2192.66	730.89	6577.97	730.89	730.89a	146282
10	577.00	0.00	2556.55	852.18	7669.64	852.18	852.18a	146282
		0.00	2556.55	923.00	7081.19	923.00	923.00a	146282
11	575.50	93.60	2734.05	987.08	7572.85	987.08	1080.68a	146282
12	574.00	187.20	2909.89	1050.57	8059.89	1050.57	1237.77a	146282
13	572.00	312.00	3141.59	1134.22	8701.67	1134.22	1446.22a	146282
14	570.00	436.80	3370.00	1216.68	9334.32	1383.88	1820.68	146282
15	568.00	561.60	3594.99	1297.91	9957.49	1807.66	2369.26	166413
16	566.00	686.40	3816.46	1377.87	10570.94	2026.16	2712.56	166413
17	564.00	811.20	4034.38	1456.55	11174.53	2105.84	2917.04	166413
18	562.00	936.00	4248.72	1533.93	11768.21	2120.26	3056.26	166413
19	560.00	1060.80	4459.49	1610.03	12352.01	2114.62	3175.42	166413
20	558.00	1185.60	4666.73	1684.84	12926.02	2109.67	3295.27	166413
21	556.50	1279.20	4819.87	1740.13	13350.19	2116.20	3395.40	315249
22	555.00	1372.80	4971.08	1794.73	13769.02	2019.37	3392.17	882551

RIGHT side								
Node no.	Y coord	Effective stresses					Total earth pressure	Coeff. of subgrade reaction
		Water press.	Vertic -al	Active limit	Passive limit	Earth pressure		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
1	591.00	0.00	0.00	0.00	0.00	0.00	0.00	698
2	589.50	0.00	187.50	0.00	0.00	0.00	0.00	4187
3	588.00	0.00	375.00	0.00	0.00	0.00	0.00	8373
4	586.50	0.00	562.50	0.00	0.00	0.00	0.00	12560
5	585.00	0.00	750.00	0.00	0.00	0.00	0.00	16747
		0.00	750.00	212.04	2652.75	2652.75	2652.75p	16747
6	583.25	0.00	968.75	273.88	3426.47	3426.47	3426.47p	21631
7	581.50	0.00	1187.50	335.72	4200.19	3935.08	3935.08	26516
8	581.00	0.00	1250.00	353.39	4421.25	3888.43	3888.43	27911
		0.00	1250.00	416.67	3750.00	3750.00	3750.00p	146282
9	579.00	0.00	1510.00	503.33	4530.00	4530.00	4530.00p	146282
10	577.00	0.00	1770.00	590.00	5310.00	5310.00	5310.00p	146282
		0.00	1770.00	639.03	4902.59	4902.59	4902.59p	146282
11	575.50	93.60	1871.40	675.64	5183.45	5183.45	5277.05p	146282
12	574.00	187.20	1972.80	712.25	5464.31	3750.37	3937.57	146282
13	572.00	312.00	2108.00	761.06	5838.79	1979.93	2291.93	146282
14	570.00	436.80	2243.20	809.87	6213.27	1099.14	1535.94	146282
15	568.00	561.60	2378.40	858.68	6587.75	858.68	1420.28a	166413
16	566.00	686.40	2513.60	907.49	6962.24	934.67	1621.07	166413
17	564.00	811.20	2648.80	956.31	7336.72	1192.81	2004.01	166413
18	562.00	936.00	2784.00	1005.12	7711.20	1487.83	2423.83	166413
19	560.00	1060.80	2919.20	1053.93	8085.68	1760.27	2821.07	166413
20	558.00	1185.60	3054.40	1102.74	8460.16	2006.43	3192.03	166413

Run ID. REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3

| Sheet No.
| Date:16-07-2025
| Checked :

(continued)

Stage No.5 Change properties of soil type 3 to soil type 4
 Ko pressures will not be reset

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft2	lb/ft3
21	556.50	1279.20	3155.80	1139.35	8741.02	2196.11	3475.31	315249
22	555.00	1372.80	3257.20	1175.96	9021.88	2479.14	3851.94	882551


Note: 1420.28a Soil pressure at active limit
 5277.05p Soil pressure at passive limit

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3


| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Stage No.5 Change soil type 3 to soil type 4



Stage No.5 Change soil type 3 to soil type 4



GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.3

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Summary of results

STABILITY ANALYSIS of Fully Embedded Wall according to CP2 method

Factor of safety on gross pressure (excluding water pressure)

<u>Stage</u> <u>No.</u>	<u>Ground level</u>		<u>Prop</u> <u>Elev.</u>	<u>FoS for toe</u> <u>elev. = 555.00</u>		<u>Toe elev. for</u> <u>FoS = 1.500</u>		<u>Direction</u> <u>of</u> <u>failure</u>
	<u>Act.</u>	<u>Pass.</u>		<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	
1	591.00	591.00	Cant.	1.920	563.07	561.83	29.17	L to R
2	591.00	591.00		No analysis at this stage				
3	591.00	591.00	Cant.	2.015	561.99	562.82	28.18	L to R
4	591.00	591.00		No analysis at this stage				
5	591.00	591.00	Cant.	1.538	559.50	555.87	35.13	L to R

GEI CONSULTANTS, INC.

Program: WALLAP Version 6.06 Revision A52.B71.R55

Licensed from GEOSOLVE

Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3

Pulliam Dock Wall - Deadman

SSP Deadman - BL-14-22_LCX.3

| Sheet No.

| Job No. 2201593

| Made by : AJG

| Date:16-07-2025

| Checked :

Units: lb,ft

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Fully Embedded Wall

Analysis options

Length of wall perpendicular to section = 1000.00ft

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Open Tension Crack analysis - No

Rigid boundaries: Left side 1000.00 from wall

Right side 1000.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		ft	ft	lb.ft/ft	lb.ft/ft	lb/ft	lb/ft
1	591.00	0.282	0.000	0.0	0.0	0.0	0.0
2	589.50	0.257	0.000	0.0	0.0	0.0	0.0
3	588.00	0.232	0.000	0.0	-0.0	0.0	0.0
4	586.50	0.208	0.000	0.0	-0.0	0.0	0.0
5	585.00	0.183	0.000	0.0	-0.0	0.0	0.0
6	583.25	0.154	0.000	0.0	-3824.5	0.0	-4590.5
7	581.50	0.125	0.000	0.0	-15689.5	25477.7	-10114.3
8	581.00	0.116	0.000	0.0	-3916.7	24167.8	0.0
9	579.00	0.082	0.000	34778.6	0.0	15786.2	0.0
10	577.00	0.052	0.000	61056.9	0.0	7529.3	0.0
11	575.50	0.033	0.000	67096.3	0.0	1397.3	-2560.6
12	574.00	0.019	0.000	65437.9	0.0	0.0	-6005.4
13	572.00	0.007	-0.001	51838.0	0.0	0.0	-7320.3
14	570.00	0.001	-0.003	35490.6	0.0	0.0	-7881.3
15	568.00	0.000	-0.003	20350.6	0.0	0.0	-6647.6
16	566.00	0.000	-0.002	9027.4	0.0	0.0	-4607.1
17	564.00	0.001	-0.001	2125.7	-1691.5	0.0	-2602.6
18	562.00	0.002	-0.001	0.0	-2252.7	0.0	-1057.1
19	560.00	0.004	-0.000	0.0	-1910.0	342.8	-70.3
20	558.00	0.005	0.000	0.0	-1276.9	418.0	0.0
21	556.50	0.005	0.000	0.0	-546.7	404.8	0.0
22	555.00	0.006	0.000	0.0	-0.0	0.0	-0.0

Maximum and minimum bending moment and shear force at each stage

Stage no.	Bending moment				Shear force			
	maximum	elev.	minimum	elev.	maximum	elev.	minimum	elev.
	lb.ft/ft		lb.ft/ft		lb/ft		lb/ft	
1	53427.8	577.00	-15520.7	581.50	25477.7	581.50	-9022.3	581.50
2	No calculation at this stage							
3	53050.4	577.00	-15679.0	581.50	25213.7	581.50	-9286.3	581.50
4	No calculation at this stage							
5	67096.3	575.50	-15689.5	581.50	24385.7	581.50	-10114.3	581.50

Maximum and minimum displacement at each stage

Stage no.	Displacement				Stage description
	maximum	elev.	minimum	elev.	
	ft		ft		
1	0.180	591.00	-0.003	568.00	Apply load no.1 at elev. 581.50
2	No calculation at this stage				Apply surcharge no.1 at elev. 591.00
3	0.189	591.00	-0.001	568.00	Apply surcharge no.2 at elev. 591.00
4	No calculation at this stage				Change soil type 2 to soil type 7
5	0.282	591.00	-0.002	568.00	Change soil type 3 to soil type 4

Run ID. REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3

| Sheet No.
| Date:16-07-2025
| Checked :


Summary of results (continued)

GEI CONSULTANTS, INC.
Program: WALLAP Version 6.06 Revision A52.B71.R55
Licensed from GEOSOLVE
Data filename/Run ID: REV1_Ddmn_BL-14-22_LCX-3
Pulliam Dock Wall - Deadman
SSP Deadman - BL-14-22_LCX.3

| Sheet No.
| Job No. 2201593
| Made by : AJG
| Date:16-07-2025
Checked :

Units: lb, ft

Bending moment, shear force, displacement envelopes



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
TIEROD AND DEADMAN DESIGN						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	E. Burton	Chk.		App.	
	Date	10/22/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Design					
TIEROD DESIGN Brown County Anchored Bulkhead - Tierod and Deadman System References: - Federal Highway Administration - Geotechnical Circular No. 4, 1999 - Federal Highway Administration - Geotechnical Circular No. 7 2015 - Nucor Skyline Material Cutsheet - North American Steel Sheet Piling Association (NASSPA), Guidance on Corrosion - USS Steel Sheet Piling Manual (1984) INPUT PARAMETERS Bar diameter: $D_b := 3.5\text{in}$ Min. net area: $A_b := 9.6\text{in}^2$ Min. Yield Strength: $f_y := \frac{768.8\text{kip}}{A_b} = 80 \cdot \text{ksi}$ Min. Ultimate Strength: $f_u := \frac{961\text{kip}}{A_b} = 100 \cdot \text{ksi}$ Design life: $t := 50\text{yr}$ Yield Tensile Load of Bar: $P_{b.\text{max}} := A_b \cdot f_y = 768.80 \cdot \text{kip}$						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	E. Burton	Chk.		App.	
	Date	10/22/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Design					
Structural Capacity of Tierod						
Tierod Line Load:		$w_{tie} := 34.5 \cdot \frac{\text{kip}}{\text{ft}}$		From WALLAP dockwall analyses		
Load Amplification Factor (USS, 1984):		$LF_{tie} := 1.3$				
Design Line Load:		$w_{LF} := w_{tie} \cdot LF_{tie} = 44.85 \cdot \frac{\text{kip}}{\text{ft}}$				
Tierod spacing:		$s_{tie} := 9.3\text{ft}$				
Design load:		$P_{tie.DL} := w_{LF} \cdot s_{tie} = 417.11 \cdot \text{kip}$				
Allowable Yield Load: FHWA GEC No. 7		$P_{b.allow} := 0.56 \cdot P_{b.max} = 430.53 \cdot \text{kip}$				
Check := if		$(P_{tie.DL} < P_{b.allow}, \text{"Bar and Spacing OK"}, \text{"Reduce spacing or change bar size"})$				
		Check = "Bar and Spacing OK"				
Use No. 28, 3.5" nominal diameter Bar, Grade 75/80 thread bar with ultimate strength of 961 kips.						
Elongation of Tierod due to Design Tensile Load						
Tierod Line Load:		$P_{LL} := w_{tie} \cdot s_{tie} = 320.85 \cdot \text{kip}$				
Length of Tierod:		$L := 75\text{ft}$				
Minimum Net Area:		$A := A_b = 9.60 \cdot \text{in}^2$				
Young's Modulus of Steel:		$E := 29000\text{ksi}$				
Elastic Deformation Due to Tension Load:		$D := \frac{P_{LL} \cdot L}{A \cdot E} = 1.04 \cdot \text{in}$				
This elastic deformation, considering that the tierod will be pre-stressed, will be removed from the overall deflection of the deadman wall.						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	E. Burton	Chk.		App.	
	Date	10/22/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Design					
Elongation of Tierod due to Testing Conditions Performance Test Tierod Line Load: $P_{\text{test}} := P_{\text{LL}} \cdot 1.33 = 426.73 \cdot \text{kip}$ Allowable Yield Load: <i>FHWA GEC No. 4</i> $P_{\text{test.allow}} := 0.9 \cdot P_{\text{b.max}} = 691.92 \cdot \text{kip}$ Length of Tierod: $L := 75\text{ft}$ Minimum Net Area: $A := A_b = 9.60 \cdot \text{in}^2$ Young's Modulus of Steel: $E := 29000\text{ksi}$ Elastic Deformation Due to Performance Test Load: $D_{\text{test}} := \frac{P_{\text{test}} \cdot L}{A \cdot E} = 1.38 \cdot \text{in}$						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Deadman Sheeting Design					
Sheet Pile Anchor Wall Design References - USS Steel Sheet Piling Design Manual - AISC Steel Construction Manual 14th Edition - North American Steel Sheet Piling Association (NASSPA), Guidance on Corrosion Input Data Max Moment: $M := 65 \text{ kip} \cdot \frac{\text{ft}}{\text{ft}}$ Output from Wallap Sheet Pile: NZ19 Elastic Section Modulus: $S_x := 35.08 \frac{\text{in}^3}{\text{ft}}$ Yield Stress: $F_y := 60 \text{ ksi}$ Flange Thickness: $t_f := 0.375 \cdot \text{in}$ Corroded Section Properties Design Life: $t := 50 \text{ yr}$ Recommended Value for Loss of Thickness due to Corrosion $c_t := 0.0005 \frac{\text{in}}{\text{yr}}$ (undisturbed nat'l soils) Estimated Corrosion Thickness: $t_c := t \cdot c_t = 0.03 \cdot \text{in}$ Corroded Elastic Section Elastic Modulus: $S_{cr} := \frac{S_x \cdot (t_f - 2 \cdot t_c)}{t_f}$ $S_{cr} = 30.40 \cdot \frac{\text{in}^3}{\text{ft}}$ Approximate Section Loss: $S_{loss} := (S_x - S_{cr})$ $S_{loss} = 4.68 \cdot \frac{\text{in}^3}{\text{ft}}$ Percent Remaining Section Modulus after 50 years: $S_{per} := \frac{(S_{cr} - S_{loss})}{S_{cr}} = 85 \cdot \%$						

		Client	BROWN COUNTY WI			Page	
		Project	Port Property Development			Pg. Rev.	X
		By	E. Burton	Chk.	C. Englert	App.	A. Pepin
		Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A				
Subject	Deadman Sheeting Design						
Strength Check							
Allowable Bending Stress:		$F_a := 0.60 \cdot F_y = 36.0 \cdot \text{ksi}$					
Allowable Bending Capacity:		$M_a := S_{cr} \cdot F_a = 91.2 \cdot \text{kip} \cdot \frac{\text{ft}}{\text{ft}}$					
Check :=		"Okay" if $M \leq M_a$ "Not Okay" otherwise			Check = "Okay"		
Minimum Elastic Section Modulus (No Corrosion):		$S_{min} := 1.67 \cdot M \div F_y = 21.7 \cdot \frac{\text{in}^3}{\text{ft}}$					
Utilization := $\frac{M}{M_a} = 71\%$		is less than			$S_{per} = 85\%$ OK		

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					

Tieback System Design - Wales and Connections

References

- AISC360-22 Specification for Structural Steel Buildings
- USS Steel Sheet Piling Design Manual, July 1984
- PTI Anchorage Zone Design, 6th Edition
- ACI 318-19, Building Code Requirements for Structural Concrete

Input Data

Yield Stress of Steel:	$F_y := 50\text{ksi}$	
Ultimate Stress of Steel:	$F_u := 65\text{ksi}$	
Modulus of Elasticity of Steel:	$E := 29000\text{ksi}$	
Weld Electrodes:	$F_{EXX} := 70\text{ksi}$	
Safety Factor for Tension/Flexure/Shear:	$\Omega := 1.67$	
Safety Factor for Welds:	$\Omega_w := 2.00$	
Spacing of King Piles:	$s_{kp} := 9.3\text{ft}$	
Wale Load from Wall Analysis:	$\omega := 31.8\text{klf}$	Max From GEI Wallap Analyses

Design Loads:

Working loads for the wall analysis will be factored to included effects such as load uncertainty and eccentricities at the connections. The following load factors have been selected for design and are from the USS Steel Pile Design Manual:


Wale Load Amplification Factor:	$LF_{wale} := 1.3$
Tieback Load Amplification Factor:	$LF_{tbck} := 1.3$
Connection Load Amplification Factor:	$LF_{conn} := 1.3$
Wale Design Load:	$\omega_{wale} := LF_{wale} \cdot \omega = 41.3 \cdot \text{klf}$
Tieback Design Load:	$\omega_{tbck} := LF_{tbck} \cdot \omega = 41.3 \cdot \text{klf}$
Connection Design Load:	$\omega_{conn} := LF_{conn} \cdot \omega = 41.3 \cdot \text{klf}$

Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	

Project No.	2201593	Document No.	N/A
Subject	Tierod Wales and Connections Design		

COMPRESSION BEARING STRESSES PTI Anchorage Zone Design, 6th Edition

Bearing Plate Check



Bearing Plate Load: $P := \omega_{\text{conn}} \cdot s_{kp} = 384.5 \cdot \text{kip}$

Bearing Plate Width: $W_{\text{plate}} := 14\text{in}$

Bearing Plate Hole: $ID_{\text{plate}} := 3.75\text{in} + \frac{1}{8}\text{in}$

Plate Hole Area: $A_{\text{plate_h}} := 0.25 \cdot \pi \cdot ID_{\text{plate}}^2 = 11.79 \cdot \text{in}^2$

Bearing Plate Area: $A_{\text{plate}} := W_{\text{plate}}^2 = 196.00 \cdot \text{in}^2$

Bearing Area: $A_b := A_{\text{plate}} - A_{\text{plate_h}} = 184.21 \cdot \text{in}^2$

Embedment of plate: $\text{emb} := 30\text{in}$

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					

Concrete Compressive Strength: $f_c := 5000 \text{ psi}$

Design Bearing Capacity: $\sigma_{nom} := f_c = 5000 \text{ psi}$

Diam. of the Dome/Nut $G := 5.0 \text{ in}$

Modulus of elasticity $E := 29000 \text{ ksi}$

Steel yield stress $f_y := 50 \text{ ksi}$

Bearing Stress: $q := \frac{P}{A_b} = 2087 \text{ psi}$

Check_Bearing_Stress := $\begin{cases} \text{"OK"} & \text{if } \sigma_{nom} \geq q \\ \text{"Not Good"} & \text{otherwise} \end{cases} = \text{"OK"}$

Cantilevered Length: $n := \frac{W_{plate} - G}{2} = 4.50 \cdot \text{in}$

from PTI - Chapter VIII pg.5 $f_{bi} := q$

Min Plate Thickness (1): $t_1 := \left(\frac{3 \cdot \frac{P \cdot n^2}{2}}{A_b \cdot f_y} \right)^{0.5} = 1.13 \cdot \text{in}$ PTI Eq. 3.4
(rewritten solving for t)

Min Plate Thickness (2): $t_2 := \frac{n}{0.08 \cdot \left(\frac{E \cdot A_b}{P} \right)^{0.333}} = 2.35 \cdot \text{in}$ PTI Eq. 3.5
(rewritten solving for t)

Min Plate Thickness: $t_{req} := \max(t_1, t_2) = 2.35 \cdot \text{in}$

Plate Thickness: $t := 2.5 \text{ in}$

Check_Plate_Thickness := $\begin{cases} \text{"OK"} & \text{if } t \geq t_{req} \\ \text{"Not Good"} & \text{otherwise} \end{cases} = \text{"OK"}$ **Use 2.5" thick plate**

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	
93	Document No.	N/A			
Wales and Connections Design					

$$f_s := \frac{4P}{\pi \cdot (G^2 - ID_{plate}^2)} = 49.0 \cdot \text{ksi} \quad \text{PTI Eq. 3.4} \quad < \quad 1.5 \cdot f_y = 75.0 \cdot \text{ksi} \quad \text{OKAY}$$

Check_Plate_Stress := "OK" if $1.5 \cdot f_y \geq f_s$ = "OK"
 "Not Good" otherwise

Punching Shear Check- ACI 318-19:

$$d_{eff} := 22.75 \text{ in}$$

compression plate embedment- perpendicular to the plate

$$b_o := 4 \left(\frac{36.75 \text{ in} + 14 \text{ in}}{2} \right) = 101.50 \cdot \text{in}$$

$$\lambda := 1$$


Normal Weight Concrete

$$\alpha_s := 40$$

Internal Pile

$$\beta := 1$$

Ratio of long and short length of plate



GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	
93	Document No.	N/A			
Wales and Connections Design					

Shear Strength in Concrete: (Tow-Way members without shear reinforcement, ACI 318.19 table 22.6.5.2)

$$V_{c1} := \left(2 + \frac{4}{\beta}\right) \cdot \lambda \cdot \sqrt{\frac{f_c}{\text{psi}}} \cdot b_o \cdot d_{\text{eff}} \text{ psi}$$

$$V_{c1} = 979.68 \cdot \text{kip}$$

$$V_{c2} := \left(\frac{\alpha_s \cdot \text{emb}}{b_o} + 2\right) \cdot \lambda \cdot \left(\sqrt{\frac{f_c}{\text{psi}}} \cdot b_o \cdot d_{\text{eff}} \text{ psi}\right)$$

$$V_{c2} = 2256.96 \cdot \text{kip}$$

$$V_{c3} := 4 \cdot \lambda \cdot \left(\sqrt{\frac{f_c}{\text{psi}}} \cdot b_o \cdot d_{\text{eff}} \text{ psi}\right)$$

$$V_{c3} = 653.12 \cdot \text{kip}$$

$$V_c := \min(V_{c1}, V_{c2}, V_{c3})$$

$$V_c = 653.12 \cdot \text{kip}$$

Resistance factor:

$$\phi_s := 0.75$$

$$V_{c_nom} := \phi_s \cdot V_c$$

$$V_{c_nom} = 489.84 \cdot \text{kip}$$

Pipe pile thickness:

$$t_{w_pipe} := \frac{5}{8} \text{ in}$$

Pipe pile cross sectional area contributing in shear strength:

$$A_{p_pile} := 36.75 \text{ in} \cdot t_{w_pipe} \cdot 2 = 45.94 \cdot \text{in}^2$$

Resistance factor:

$$\phi_{\text{pipe}} := 0.75$$

Steel Shear strength:

$$V_s := \phi_v \cdot F_y \cdot A_{p_pile} = 2067.19 \cdot \text{kip}$$

Load Factor:

$$LF := 1.6$$

$$V_{c_check} := \begin{cases} \text{"OK, Factored Shear < Nominal Punching Shear"} & \text{if } LF \cdot P < V_{c_nom} + V_s \\ \text{"NG"} & \text{otherwise} \end{cases}$$

$$V_{c_check} = \text{"OK, Factored Shear < Nominal Punching Shear"}$$

$$LF \cdot P = 615.14 \cdot \text{kip}$$

$$DCR := \frac{P}{V_{c_nom} + V_s} = 0.15$$

GEI




Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	
93	Document No.	N/A			
Wales and Connections Design					

Design Wale at Deadman Wall

Wale Load:	$\omega_{\text{wale}} = 41.3 \cdot \text{klf}$
Wale Shear:	$V_{\text{wale}} := 0.6 \cdot \omega_{\text{wale}} \cdot s_{\text{kp}} = 230.7 \cdot \text{kip}$
Wale Moment:	$M_{\text{wale}} := 0.10 \cdot \omega_{\text{wale}} \cdot s_{\text{kp}}^2 = 357.5 \cdot \text{kip} \cdot \text{ft}$

See attached Tedds analysis for the wale design



W 21x73 (AISC 15th Edn (v15.0))


Section depth, d , 21.2 in
 Section breadth, b_f , 8.3 in
 Weight of section, Weight, 73 lbf/ft
 Flange thickness, t_f , 0.74 in
 Web thickness, t_w , 0.455 in
 Root radius, $k - t_r$, 0.5 in
 Area of section, A , 21.5 in²
 Radius of gyration about x-axis, r_x , 8.64 in
 Radius of gyration about y-axis, r_y , 1.81 in
 Elastic section modulus about x-axis, S_x , 151 in³
 Elastic section modulus about y-axis, S_y , 17 in³
 Plastic section modulus about x-axis, Z_x , 172 in³
 Plastic section modulus about y-axis, Z_y , 26.6 in³
 Second moment of area about x-axis, I_x , 1800 in⁴
 Second moment of area about y-axis, I_y , 70.6 in⁴

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	
93	Document No.	N/A			
Wales and Connections Design					

Design Bearing Plate at Deadman Wall- AISC 360



Steel ASD Design Factors of Safety

Plate Thickness:

$$t_p := 3.5\text{in}$$

Plate Length:

$$l_p := 20\text{in}$$

Plate width:

$$w_p := 12\text{in}$$

Hole Size:

$$\phi_{\text{hole}} := 3.75\text{in} + \frac{1}{8}\text{in}$$

Bar Nut Width (across flats):

$$w_{\text{nut}} := 5.0\text{in}$$

Clear Space Between Channels

$$\text{clr} := 6\text{in}$$

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	
93	Document No.	N/A			
Wales and Connections Design					

Flexure

$$\Omega_f := 1.67$$

Shear

$$\Omega_s := 1.5$$

Max shear:

$$V_{\max} := 0.5 \cdot P = 192.23 \cdot \text{kip}$$

Max moment:
$$M_{\max} := 0.5 \cdot P \cdot \left(\frac{\text{clr}}{4} + \frac{l_p}{4} - \frac{w_{\text{nut}} - \phi_{\text{hole}}}{4} \right) = 1195.44 \cdot \text{kip} \cdot \text{in}$$




Plate Mid Span Elastic Section Modulus:

$$S_p := \frac{t_p^2 \cdot (l_p - \phi_{\text{hole}})}{6} = 32.92 \cdot \text{in}^3$$

Plate Mid Span Plastic Section Modulus:

$$Z_p := \frac{t_p^2 \cdot (l_p - \phi_{\text{hole}})}{4} = 49.38 \cdot \text{in}^3$$

Nominal Shear Capacity:

$$V_n := 0.6 \cdot F_y \cdot t_p \cdot l_p = 2100.00 \cdot \text{kip}$$

Allowable Shear Capacity:

$$V_a := V_n \div \Omega_s = 1400.0 \cdot \text{kip} > V_{\max} = 192.2 \cdot \text{kip}$$

Check_shear := "OK" if $V_a \geq V_{\max}$ = "OK"
"Not Good" otherwise

Nominal Moment Capacity

$$M_n := \min(F_y \cdot Z_p, 1.6 \cdot F_y \cdot S_p) = 2469.1 \cdot \text{kip} \cdot \text{in}$$

(AISC Eq. F11-1):

Allowable Moment Capacity:

$$M_a := M_n \div \Omega_f = 1478.5 \cdot \text{kip} \cdot \text{in}$$

$$M_{\max} = 1195.4 \cdot \text{kip} \cdot \text{in}$$

Check_shear := "OK" if $M_a \geq M_{\max}$ = "OK"
"Not Good" otherwise

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					

Flanges & Webs with Concentrated Forces (AISC §J10)

References

- AISC Steel Construction Manual, 13th Ed.

Discussion

This Mathcad sheet presents the calculation of the allowable concentrated loads on the flanges of wide-flange sections and similar built-up shapes for the following limit states:

1. Flange Local Bending
2. Web Local Yielding
3. Web Crippling
4. Web Sidesway Buckling
5. Web Compression Buckling

Where the applied load will exceed the allowable load, stiffeners or doubler plates must be provided, sized for the difference between the applied load and the allowable load.

Material Properties

Specified Minimum Yield Stress of Steel: $F_y := 50\text{ksi}$

Note: The AISC Specification is written to account for the situation in which the flanges and the web have different yield strengths, as may be the case for a built-up section. For rolled sections, the web and flanges will have the same yield strength. Assuming a rolled section:



Specified Minimum Yield Stress of Flange: $F_{yf} := F_y = 50 \cdot \text{ksi}$

Specified Minimum Yield Stress of Web: $F_{yw} := F_y = 50 \cdot \text{ksi}$

Modulus of Elasticity of Steel: $E := 29000\text{ksi}$

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					

Input Dimensions

Member Size:	W21x73		
Overall Depth of Member:	$d := 21.2\text{in}$		
Thickness of Loaded Flange:	$t_f := 0.74\text{in}$		
Flange Width:	$b_f := 8.3\text{in}$		
Web Thickness:	$t_w := 0.455\text{in}$		
k-Distance:	$k := 1.24\text{in}$	k_{des} from AISC Table 1-1	
Laterally Unbraced Length:	$L := 40\text{in} = 3.33\text{ft}$	Largest of either flange at point of load. (SSP belly width)	
Length of Bearing:	$N := w_p = 12.00\text{in}$		
Concentrated Load: (per W section)	$P := 0.5\omega_{conn} \cdot s_{kp} = 192.2 \cdot \text{kip}$		

Flange Local Bending (AISC §J10.1)

Safety Factor:	$\Omega := 1.67$
Nominal Strength:	$R_n := 6.25 \cdot F_{yw} \cdot (t_f)^2 = 171.13 \cdot \text{kip}$
Allowable Load:	$R_n \div \Omega = 102.47 \cdot \text{kip}$

Check_Flange_Local_Bending :=	"OK" if $\frac{(R_n)}{\Omega} \geq P$ = "Not Good" "Not Good" otherwise
-------------------------------	--

Add two pairs of transverse stiffener (PL 18.72" x 3.5" x 7/8") on each W section at tierod location.

Width of stiffener:	$w_{p_sti} := 3.5\text{in}$
Thickness of stiffener:	$t_{p_sti} := \frac{7}{8}\text{in}$
Length of stiffener:	$L_{p_sti} := 18.72\text{in}$
Number of stiffeners per W section:	$n_{sti} := 4$

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	

Project No.	2201593	Document No.	N/A
-------------	---------	--------------	-----

Subject	Tierod Wales and Connections Design
---------	-------------------------------------

Gyration radius of plate:

$$r := \sqrt{\frac{\frac{w_{p_sti} \cdot t_{p_sti}^3}{12}}{w_{p_sti} \cdot t_{p_sti}}} = 0.25 \cdot \text{in}$$

Elastic Buckling stress:

$$F_e := \frac{\pi^2 \cdot E}{\left(\frac{L_{p_sti}}{r}\right)^2} = 52.11 \cdot \text{ksi}$$

Critical Stress:

$$F_{cr} := \begin{cases} \left[\left(\frac{F_y}{F_e} \right) \cdot F_y \right] & \text{if } 4.71 \cdot \sqrt{\frac{E}{F_y}} \geq \frac{L_{p_sti}}{r} \\ (0.8777 F_e) & \text{otherwise} \end{cases} = 33.46 \cdot \text{ksi} \quad \text{AISC §E3}$$

Added strength from stiffeners:

$$P_{n_sti} := n_{sti} \cdot F_{cr} \cdot t_{p_sti} \cdot w_{p_sti} = 409.91 \cdot \text{kip}$$

Check_Flange_Local_Bending :=

$$\begin{aligned} & \text{"OK"} \quad \text{if} \quad \frac{(R_n) + P_{n_sti}}{\Omega} \geq P \quad = \text{"OK"} \\ & \text{"Not Good"} \quad \text{otherwise} \end{aligned}$$

	Client	BROWN COUNTY WI			Page			
	Project	Port Property Development			Pg. Rev.	X		
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin		
	Date	07/25/2025	Date		Date			
Project No.	2201593	Document No.	N/A					
Subject	Tierod Wales and Connections Design							
Web Local Yielding (AISC §J10.2) <i>Applies to single-concentrated forces and both components of double-concentrated forces.</i> Safety Factor: $\Omega := 1.50$ <i>When the force is applied at a distance from the end of the member that is <u>greater than the depth, d</u>:</i> Nominal Strength: $R_{n1} := (5k + N) \cdot F_{yw} \cdot t_w + P_{n_sti} = 823.96 \cdot \text{kip}$ Allowable Load: $R_{n1} \div \Omega = 549.31 \cdot \text{kip}$ <i>When the force is applied at a distance from the end of the member that is <u>less than or equal to the depth, d</u>:</i> Nominal Strength: $R_{n2} := (2.5k + N) \cdot F_{yw} \cdot t_w + P_{n_sti} = 753.44 \cdot \text{kip}$ Allowable Load: $R_{n2} \div \Omega = 502.29 \cdot \text{kip}$ <table border="1"> <tr> <td>Check_Web_Local_Yield :=</td> <td> "OK" if $\frac{\min(R_{n1}, R_{n2})}{\Omega} \geq P$ = "OK" "Not Good" otherwise </td> </tr> </table>							Check_Web_Local_Yield :=	"OK" if $\frac{\min(R_{n1}, R_{n2})}{\Omega} \geq P$ = "OK" "Not Good" otherwise
Check_Web_Local_Yield :=	"OK" if $\frac{\min(R_{n1}, R_{n2})}{\Omega} \geq P$ = "OK" "Not Good" otherwise							

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					

Web Crippling (AISC §J10.3)

When the force is applied at a distance from the end of the member that is greater than or equal to d/2:

Nominal Strength: $R_{n1} := 0.80 (t_w)^2 \cdot \left[1 + 3 \cdot \left(\frac{N}{d} \right) \cdot \left(\frac{t_w}{t_f} \right)^{1.5} \right] \cdot \sqrt{\frac{E \cdot F_{yw} \cdot t_f}{t_w}}$

$R_{n1} = 462.57 \cdot \text{kip}$ Allowable Load: $R_{n1} \div \Omega = 308.38 \cdot \text{kip}$

When the force is applied at a distance from the end of the member that is less than d/2:

Nominal Strength: $R_{n2} := \begin{cases} 0.40 (t_w)^2 \cdot \left[1 + 3 \cdot \left(\frac{N}{d} \right) \cdot \left(\frac{t_w}{t_f} \right)^{1.5} \right] \cdot \sqrt{\frac{E \cdot F_{yw} \cdot t_f}{t_w}} & \text{if } \frac{N}{d} \leq 0.2 \\ 0.40 (t_w)^2 \cdot \left[1 + \left(\frac{4N}{d} - 0.2 \right) \cdot \left(\frac{t_w}{t_f} \right)^{1.5} \right] \cdot \sqrt{\frac{E \cdot F_{yw} \cdot t_f}{t_w}} & \text{otherwise} \end{cases}$

$R_{n2} = 253.73 \cdot \text{kip}$ Allowable Load: $R_{n2} \div \Omega = 169.15 \cdot \text{kip}$

Check_Web_Crippling := "OK" if $\frac{\min(R_{n1}, R_{n2}) + P_{n_sti}}{\Omega} \geq P$ = "OK"

"Not Good" otherwise

$\frac{\min(R_{n1}, R_{n2}) + P_{n_sti}}{\Omega} = 442.43 \cdot \text{kip}$

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					

Web Sidesway Buckling (AISC §J10.4)

Applies only to single-concentrated forces applied to members where relative lateral movement between the loaded compression flange the tension flange is not restrained at the point of application of the force.

Safety Factor: $\Omega := 1.76$

Distance between Flanges, less Fillets: $h := d - 2k$ $h = 18.72 \cdot \text{in}$ *See AISC manual for built-up sections.*

Assume: $C_r := 960000 \text{ksi}$ *Valid as long as conventional AISC elastic design provisions are used.*

Note: $\frac{h}{t_w} \div \frac{L}{b_f} = 8.54$ *If this ratio is greater than 2.3 with the compression flange restrained against rotation, or 1.7 with the compression flange not restrained against rotation, the limit state of web sidesway buckling does not apply.*

If the compression flange is restrained against rotation:

Nominal Strength: $R_n := \frac{C_r \cdot t_w^3 \cdot t_f}{h^2} \cdot \left[1 + 0.4 \cdot \left(\frac{h}{t_w} \div \frac{L}{b_f} \right)^3 \right]$

$R_n = 47716.06 \cdot \text{kip}$ Allowable Load: $R_n \div \Omega = 27111.40 \cdot \text{kip}$

If the compression flange is not restrained against rotation:

Nominal Strength: $R_n := \frac{C_r \cdot t_w^3 \cdot t_f}{h^2} \cdot \left[0.4 \cdot \left(\frac{h}{t_w} \div \frac{L}{b_f} \right)^3 \right]$

$R_n = 47525.11 \cdot \text{kip}$ Allowable Load: $R_n \div \Omega = 27002.90 \cdot \text{kip}$

Web Compression Buckling (AISC §J10.5) $P = 192.2 \cdot \text{kip}$ **OKAY**

Applies to a pair of compressive single-concentrated forces or the compressive components in a pair of double-concentrated forces, applied to both flanges of a member at the same location.

Safety Factor: $\Omega := 1.67$

Nominal Strength: $R_n := \frac{24(t_w)^3 \cdot \sqrt{E \cdot F_{yw}}}{h} + P_{n_sti} = 555.33 \cdot \text{kip}$


	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					
Allowable Load: $R_n \div \Omega = 332.53 \cdot \text{kip}$						
Check_Web_compression := "OK" if $\frac{R_n}{\Omega} \geq P$ = "OK" "Not Good" otherwise						

GEI  Consultants	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					

Design Wale Splice

*The wale splice will be located within an area of negligible moment, therefore design for shear only.
The maximum shear will be used. See attached analysis for the splice design.*

Design Shear Load on each splice: $V_{splice} := 0.5V_{wale} = 115.3 \cdot \text{kip}$



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					

Lacing Design- AISC 360 - Section E6

In accordance with AISC Chapter E6 for built-up members, individual component shall be connected to one another at intervals "a" such that the slenderness ratio "a/r" of each component does not exceed 3/4 of the governing slenderness ratio of the built-up member.

Radius of gyration of individual component- Y axis:

$r_y := 1.81\text{in}$

Radius of gyration of individual component- x axis:

$r_x := 8.64\text{in}$

minimum radius of gyration of individual component

$r_i := \min(r_x, r_y) = 1.81\text{in}$

Distance between lacings:

$a_{\text{lacing}} := 6\text{ft}$
 $\frac{a_{\text{lacing}}}{r_i} = 39.78$

Effective length:

$L_c := 9.25\text{ft}$ tierod spacing

Modified slenderness ratio of built-up member:

$L_{r_m} := \frac{L_c}{r_x} = 12.85$

Maximum connector spacing:

$a := \frac{3 \cdot \max(r_x, r_y) \cdot L_{r_m}}{4} = 6.94\text{ft}$

Check :=

"OK, Connector spacing is adequate" if $a_{\text{lacing}} \leq a$ = "OK, Connector spacing is adequate"

"Reduce spacing" otherwise

Width of the lacing plate:

$W_p := b_f + \text{clr} = 14.30\text{in}$ Say $W_{pl} := 16\text{in}$

Use 16"x6"x0.5" plates welded to the top and bottom flanges every 6 ft.


	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					
Design Wale at Return Wall The return wall will have diagonal tiebacks. As a result the wall needs to be checked for the following: 1. Wall Stability to overturning and sliding 2. A wale will be designed to resist compressive loads that develop in the wall as a result of the diagonal tie force. 3. The wall interlocks will be welded to make the wall act as a diaphragm and prevent racking of the system. 1. Wall Stability <i>The wall is checked for stability assuming a rigid structure. We computed the overturning moment resulting from the wale load at Elev. 582 relative to the toe of the wall. Restoring moments included the weight of the wall, weight of the fill inside the pipes (assumed to be a loose sand), and frictional forces on the wall due to the active and passive pressures.</i> We conservatively assumed an interface friction angle between the soil and wall of 14 degrees or approximately 1/2 the friction angle for the soils modeled. We also conservatively idealized the wall as a planar structure ignoring the additional surface area gained from the radius of the pipe and bent shape of the sheet piles. Additionally, the friction angle is considered conservative for a sliding limit state since the areas between the pipe piles would plug with soil and the interface friction angle would be equal to the soil friction angle. The wall pressures during the critical stage were used and are presented below. The wall forces were graphically integrated in CAD based on the Wallap pressure diagram A minimum factor of safety of 1.5 was assumed for the overturning and sliding limit states.						

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	

Project No.	2201593	Document No.	N/A
Subject	Tierod Wales and Connections Design		




VERTICAL SCALE: 1:1
HORIZONTAL SCALE: 40:10,000

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	

Project No.	2201593	Document No.	N/A
Subject	Tierod Wales and Connections Design		



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
	Date	07/25/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Tierod Wales and Connections Design					
Wale Design <i>The wale will be designed for the compressive load resulting from the diagonal component of the tierods. Additionally, this connection will be eccentric and therefore also needs to be designed for bending moment resulting from this eccentricity. To analyze the load demand of the wale, a STAAD model was built. The load inputs are computed below. The STAAD report is provided at the end of this calculation.</i> Point Load (Typ Pile): $P_1 := \omega_{wale} \div LF_{wale} \cdot s_{kp} = 295.7 \cdot \text{kip}$ Point Load (Corner Pile): $P_2 := 0.5 \cdot P_1 = 147.9 \cdot \text{kip}$ Connection Eccentricity: $e := 24\text{in}$ (CL Wale to Ctr Br PL) Moment (Typ Pile): $M_1 := P_1 \cdot e = 591.5 \cdot \text{kip} \cdot \text{ft}$ Moment (Corner Pile): $M_2 := P_2 \cdot e = 295.7 \cdot \text{kip} \cdot \text{ft}$ <u>STAAD Results</u> Max Axial Compression: $P_{max} := 2024\text{kip}$ Max Moment: $M_{max} := 321.2\text{kip} \cdot \text{ft}$ <u>Member Capacity Check</u> Tekla Tedds is used to check the capacity of the wale for combined axial load and bending. The calculation is provided on the following pages. The wale consists of (3) HSS 16"x16"x3/4" spaced vertically at 24-inch on-center. The design input loads are therefore as follows: Number of Wales: $No_{wale} := 3$ Design Axial Compression: $P_{dsgn_HSS} := P_{max} \cdot LF_{wale} \div No_{wale} = 877 \cdot \text{kip}$ Design Moment: $M_{dsgn_HSS} := M_{max} \cdot LF_{wale} \div No_{wale} = 139 \text{ft} \cdot \text{kip}$						

GEI



Consultants

Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	E. Burton	Chk.	C. Englert	App.	A. Pepin
Date	08/19/2025	Date		Date	
93	Document No.	N/A			
ment to Wale and Connection Design					




GEI Consultants, Inc
124 Grove Street, Suite 300
Franklin, MA, 02038

Project				Job Ref.	
Section				Sheet no./rev. 1	
Calc. by A	Date 10/22/2024	Chk'd by	Date	App'd by	Date

STEEL COLUMN DESIGN

In accordance with AISC360-10 and the ASD method

Tedds calculation version 1.0.10



Column and loading details

Column details

Column section

HSS 16x16x3/4

Design loading

Required axial strength

$P_r = 877$ kips (Compression)

Moment about x axis at end 1

$M_{x1} = 139.2$ kips_ft

Moment about x axis at end 2

$M_{x2} = 139.2$ kips_ft

Single curvature bending about x axis

Maximum moment about x axis

$M_x = \max(\text{abs}(M_{x1}), \text{abs}(M_{x2})) = 139.2$ kips_ft

Moment about y axis at end 1

$M_{y1} = 0.0$ kips_ft

Moment about y axis at end 2

$M_{y2} = 0.0$ kips_ft

Maximum moment about y axis

$M_y = \max(\text{abs}(M_{y1}), \text{abs}(M_{y2})) = 0.0$ kips_ft

Maximum shear force parallel to y axis

$V_{ry} = 26.8$ kips

Maximum shear force parallel to x axis

$V_{rx} = 0.0$ kips

Material details

Steel grade

A500 Gr. C

Yield strength

$F_y = 50$ ksi

Ultimate strength

$F_u = 62$ ksi

Modulus of elasticity

$E = 29000$ ksi

Shear modulus of elasticity

$G = 11200$ ksi

Unbraced lengths

For buckling about x axis

$L_x = 112$ in

For buckling about y axis

$L_y = 112$ in

For torsional buckling

$L_z = 112$ in



Consultants

Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	E. Burton	Chk.	C. Englert	App.	A. Pepin
Date	08/19/2025	Date		Date	
93	Document No.	N/A			
ment to Wale and Connection Design					



GEI Consultants, Inc
124 Grove Street, Suite 300
Franklin, MA, 02038

Project				Job Ref.	
Section				Sheet no./rev. 2	
Calc. by A	Date 10/22/2024	Chk'd by	Date	App'd by	Date

Effective length factors

For buckling about x axis $K_x = 0.65$
 For buckling about y axis $K_y = 0.65$
 For torsional buckling $K_z = 0.50$

Section classification**Section classification for local buckling (cl. B4)**

Critical flange width $b = b_f - 3 \times t = 13.906$ in
 Critical web width $h = d - 3 \times t = 13.906$ in
 Width to thickness ratio of flange (compression) $\lambda_{t,c} = b / t = 19.923$
 Width to thickness ratio of web (compression) $\lambda_{w,c} = h / t = 19.923$
 Width to thickness ratio of flange (major flexure) $\lambda_{t,fx} = b / t = 19.923$
 Width to thickness ratio of web (major flexure) $\lambda_{w,fx} = h / t = 19.923$
 Width to thickness ratio of flange (minor flexure) $\lambda_{t,fy} = h / t = 19.923$
 Width to thickness ratio of web (minor flexure) $\lambda_{w,fy} = b / t = 19.923$

Compression

Limit for nonslender section $\lambda_{t,c} = 1.40 \times \sqrt{E / F_y} = 33.716$

*The section is nonslender in compression***Flexure**

Limit for compact flange $\lambda_{pft} = 1.12 \times \sqrt{E / F_y} = 26.973$
 Limit for noncompact flange $\lambda_{rtf} = 1.40 \times \sqrt{E / F_y} = 33.716$
 Limit for compact web $\lambda_{pwt} = 2.42 \times \sqrt{E / F_y} = 58.281$
 Limit for noncompact web $\lambda_{rwt} = 5.70 \times \sqrt{E / F_y} = 137.274$

*The section is compact in flexure about the major axis***Slenderness****Member slenderness**

Slenderness ratio about x axis $SR_x = K_x \times L_x / r_x = 11.7$
 Slenderness ratio about y axis $SR_y = K_y \times L_y / r_y = 11.7$

Second order effects**Second order effects for bending about y axis (cl. C2.1b)**

Second order effects are already included or do not need to be considered therefore:-

P-δ amplifier $B_{1x} = B_{1y} = 1.0$
 Required flexural strength (x axis) $M_{rx} = B_{1x} \times M_x = 139.2$ kips_ft
 Required flexural strength (y axis) $M_{ry} = B_{1y} \times M_y = 0.0$ kips_ft

Design of members for shear parallel to y axis - Chapter G

Required shear strength $V_{ry} = 26.800$ kips
 Web area $A_w = 2 \times (d - 3 \times t) \times t = 19.413$ in²
 Web plate buckling coefficient $k_v = 5$
 Web shear coefficient - eq G2-3 $C_v = 1$
 Nominal shear strength – eq G2-1 $V_{ny} = 0.6 \times F_y \times A_w \times C_v = 582.383$ kips



Consultants

Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	E. Burton	Chk.	C. Englert	App.	A. Pepin
Date	08/19/2025	Date		Date	
93	Document No.	N/A			
ment to Wale and Connection Design					



GEI Consultants, Inc
124 Grove Street, Suite 300
Franklin, MA, 02038

Project				Job Ref.	
Section				Sheet no./rev. 3	
Calc. by A	Date 10/22/2024	Chk'd by	Date	App'd by	Date

Safety factor for shear $\Omega_v = 1.67$
Allowable shear strength $V_{cy} = V_{ny} / \Omega_v = 348.733$ kips

Reduction factor for slender elements**Reduction factor for slender elements (E7)**

The section does not contain any slender elements therefore:-

Slender element reduction factor $Q = 1.0$

Compressive strength**Flexural buckling about x axis (cl. E3)**

Elastic critical buckling stress $F_{ex} = (\pi^2 \times E) / (SR_x)^2 = 2084.1$ ksi

Reduction factor $Q_x = Q = 1.000$

Flexural buckling stress about x axis $F_{crx} = Q_x \times (0.658^{Q_x \times F_y / F_{ex}}) \times F_y = 49.5$ ksi

Nominal flexural buckling strength $P_{nx} = F_{crx} \times A_g = 2054.3$ kips

Flexural buckling about y axis (cl. E3)

Elastic critical buckling stress $F_{ey} = (\pi^2 \times E) / (SR_y)^2 = 2084.1$ ksi

Reduction factor $Q_y = Q = 1.000$

Flexural buckling stress about y axis $F_{cry} = Q_y \times (0.658^{Q_y \times F_y / F_{ey}}) \times F_y = 49.5$ ksi

Nominal flexural buckling strength $P_{ny} = F_{cry} \times A_g = 2054.3$ kips

Allowable compressive strength (cl. E1)

Safety factor for compression $\Omega_c = 1.67$

Allowable compressive strength $P_c = \min(P_{nx}, P_{ny}) / \Omega_c = 1230.1$ kips

PASS - The allowable compressive strength exceeds the required compressive strength

Flexural strength about the major axis**Yielding (cl. F7.1)**

Nominal flexural strength $M_{nx_yld} = M_{px} = F_y \times Z_x = 979.2$ kips_ft

Allowable flexural strength about the major axis (cl. F1)

Safety factor for flexure $\Omega_b = 1.67$

Allowable flexural strength $M_{cx} = \min(M_{nx_yld}) / \Omega_b = 586.327$ kip_ft

PASS - The allowable flexural strength about the major axis exceeds the required flexural strength

Library item - Design flex str ASD x RHSC**Combined forces**

Member utilization (cl. H1.1)

Equation H1-1a $UR = \text{abs}(P_r) / P_c + 8 / 9 \times (M_{rx} / M_{cx} + M_{ry} / M_{cy}) = 0.924$


PASS - The member is adequate for the combined forces

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	
93	Document No.	N/A			
Wales and Connections Design					

Wale/ King Pile Connection Design



Total Connection Shear: $V_{conn} := P_1 \cdot LF_{conn} = 384.5 \cdot \text{kip}$

Total Connection Moment: $M_{conn} := P_1 \cdot e \cdot LF_{conn} = 768.9 \cdot \text{kip} \cdot \text{ft}$

Number of Connection Plates: $No_{conn_PL} := 2$
(Per Wale)

Design Shear: $V_{dsgn_conn} := V_{conn} \div (No_{wale} \cdot No_{conn_PL}) = 64.1 \cdot \text{kip}$

Design Moment: $M_{dsgn_conn} := M_{conn} \div (No_{wale} \cdot No_{conn_PL}) = 128.15 \cdot \text{kip} \cdot \text{ft}$


GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	

Project No.	2201593	Document No.	N/A
Subject	Tierod Wales and Connections Design		

Size Connection Plate Between King Pile and Wale

Connection Plate Length: $L_{\text{conn_PL}} := 42\text{in}$ Connection Plate Thickness: $t_{\text{conn_PL}} := 0.75\text{in}$ Safety Factor for Flexure/Shear: $\Omega := 1.67$ Safety Factor for Welds: $\Omega_w = 2.00$ Elastic Section Modulus: $S_x := t_{\text{conn_PL}} \cdot L_{\text{conn_PL}}^2 \div 6 = 220.5 \cdot \text{in}^3$

Allowable Moment: $M_a := F_y \cdot S_x \div \Omega = 550.1 \cdot \text{kip} \cdot \text{ft}$
 $> M_{\text{dsgn_conn}} = 128.2 \cdot \text{kip} \cdot \text{ft}$

Allowable Shear: $V_a := 0.6 \cdot F_y \cdot L_{\text{conn_PL}} \cdot t_{\text{conn_PL}} \div \Omega = 565.9 \cdot \text{kip}$
 $>$
 $V_{\text{dsgn_conn}} = 64.1 \cdot \text{kip}$

Weld Length: $l_w := 2 \cdot L_{\text{conn_PL}} = 84.0 \cdot \text{in}$ Weld Section Modulus: $S_w := L_{\text{conn_PL}}^2 \div 3 = 588.0 \cdot \text{in}^2$ Weld Force:
(Per inch) $r_w := \frac{V_{\text{dsgn_conn}}}{l_w} + \frac{M_{\text{dsgn_conn}}}{S_w} = 3.38 \cdot \frac{\text{kip}}{\text{in}}$ Weld Size: $t_{\text{weld}} := \frac{5}{16}\text{in}$ Nominal Weld Strength (per inch): $R_n := 0.60 \cdot F_{\text{EXX}} \cdot \left(\frac{\sqrt{2}}{2} \right) \cdot t_{\text{weld}} = 9.28 \cdot \frac{\text{kip}}{\text{in}}$

Allowable Weld Strength (per in): $R_a := R_n \div \Omega_w = 4.64 \cdot \frac{\text{kip}}{\text{in}}$
 $> r_w = 3.38 \cdot \frac{\text{kip}}{\text{in}}$

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	

Project No.	2201593	Document No.	N/A
Subject	Tierod Wales and Connections Design		

Size Weld Between Connection Plate and Wale


Minimum Weld Width:

$$w_w := 9\text{in}$$

Design Torsion:

$$T_w := M_{\text{dsgn_conn}}$$

$$T_w = 128.15 \cdot \text{kip} \cdot \text{ft}$$



$$N_x = \frac{d^2}{b+2d} \times \frac{b}{d}$$

$$S_w = \frac{2bd + d^2}{3} = \frac{d^2(2b + d)}{3(b + d)}$$

top bottom

$$J_w = \frac{(b+2d)^3}{12} - \frac{d^2(b+d)^2}{(b+2d)}$$

Distance from top of weld to X-Axis:

$$N_{x1} := \frac{w_w^2}{(2 \cdot L_{\text{conn_PL}} + w_w)} = 0.87 \cdot \text{in}$$

Distance from bot of weld to X-Axis:

$$N_{x2} := w_w - N_{x1} = 8.13 \cdot \text{in}$$

Max Distance from centroid to tip of weld:

$$c := \sqrt{\max(N_{x1}, N_{x2})^2 + 0.5 \cdot L_{\text{conn_PL}}^2} = 30.79 \cdot \text{in}$$

Weld Length:

$$l_w := L_{\text{conn_PL}} + 2 \cdot w_w = 60.0 \cdot \text{in}$$

Weld Polar Moment of Inertia:

$$J_w := \frac{(L_{\text{conn_PL}} + 2 \cdot w_w)^3}{12} - \frac{w_w^2 \cdot (L_{\text{conn_PL}} + w_w)^2}{(L_{\text{conn_PL}} + 2 \cdot w_w)} = 14488.7 \cdot \text{in}^3$$

Weld Force:
(Per inch)

$$r_w := \frac{V_{\text{dsgn_conn}}}{l_w} + \frac{T_w \cdot c}{J_w} = 4.34 \cdot \frac{\text{kip}}{\text{in}}$$

Weld Size:

$$t_{\text{weld}} := \frac{5}{16} \text{in}$$

Nominal Weld Strength (per inch):

$$R_n := 0.60 \cdot F_{\text{EXX}} \cdot \left(\frac{\sqrt{2}}{2} \right) \cdot t_{\text{weld}} = 9.28 \cdot \frac{\text{kip}}{\text{in}}$$

Allowable Weld Strength (per in):

$$R_a := R_n \div \Omega_w = 4.64 \cdot \frac{\text{kip}}{\text{in}}$$

$$> r_w = 4.34 \cdot \frac{\text{kip}}{\text{in}}$$

GEI



Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	A. Nafisi	Chk.	C. Englert	App.	A. Pepin
Date	07/25/2025	Date		Date	
93	Document No.	N/A			
Wales and Connections Design					

Size Welds At Interlocks:

The analysis to assess the stability of the wall assumes the wall acts as a rigid structure (i.e. diaphragm). To prevent racking of the wall (slipage at the interlocks), the interlocks will be welded. This calculation determines the required weld lengths and sizes.

King Pile Diameter:

$$D_{kp} := 54\text{in}$$

King Pile Wall Thickness:

$$t_{kp} := 0.625\text{in}$$

NZ 19 SSP Iy:

$$I_{y-y_NZ19} := 1186614\text{in}^4$$

Computed in AutoCAD

Area of NZ19 SSP:

$$A_{NZ19} := 32.73\text{in}^2$$

System Width:


$$w_{sys} := 9.3\text{ft}$$

Moment of Inertia of King Pile:

$$I_{kp} := \pi \cdot \left[\frac{D_{kp}^4 - (D_{kp} - 2t_{kp})^4}{64} \right] = 37326 \cdot \text{in}^4$$

Cross Sectional Area of King Pile:

$$A_{kp} := 0.25 \cdot \pi \cdot \left[D_{kp}^2 - (D_{kp} - 2 \cdot t_{kp})^2 \right] = 104.80 \cdot \text{in}^2$$



Pile Locations

$$y_{1_KP} := 3.5 \cdot w_{sys} = 32.55 \text{ ft}$$

$$y_{1_SSP} := 3.0 \cdot w_{sys} = 27.90 \text{ ft}$$


$$y_{2_KP} := 2.5 \cdot w_{sys} = 23.25 \text{ ft}$$

$$y_{2_SSP} := 2.0 \cdot w_{sys} = 18.60 \text{ ft}$$

$$y_{3_KP} := 1.5 \cdot w_{sys} = 13.95 \text{ ft}$$

$$y_{3_SSP} := 1.0 \cdot w_{sys} = 9.30 \text{ ft}$$

$$y_{4_KP} := 0.5 \cdot w_{sys} = 4.65 \text{ ft}$$



Compute Moment of Inertia of Wall based on Parallel Axis Theorem

$$I_{\text{wall}} := 2 \cdot \left[4 \cdot I_{\text{kp}} + A_{\text{kp}} \cdot (y_{1_KP}^2 + y_{2_KP}^2 + y_{3_KP}^2 + y_{4_KP}^2) \dots \right. \\ \left. + 3 \cdot I_{y_y_NZ19} + A_{\text{NZ19}} \cdot (y_{1_SSP}^2 + y_{2_SSP}^2 + y_{3_SSP}^2) \right]$$

$$I_{\text{wall}} = 73652961 \cdot \text{in}^4$$

1st Moment of Inertia: $Q := A_{kp} \cdot (y_{1_KP} - 0.5 \cdot D_{kp}) = 38106 \cdot \text{in}^3$

$$\text{Shear Flow: } q := \frac{P_{\max} \cdot Q}{I_{\text{wall}}} = 1.05 \cdot \frac{\text{kip}}{\text{in}}$$

Total Interlock Shear: $V_{lock} := q \cdot (584\text{ft} - 540\text{ft}) = 553 \cdot \text{kip}$

Weld Length (Total - 2 sides): $l_w := 10\text{ft}$


$$r_w := \frac{V_{lock}}{l_w} = 4.61 \cdot \frac{\text{kip}}{\text{in}}$$

Weld Size: $t_{\text{weld}} := \frac{5}{16} \text{ in}$

$$R_n := 0.60 \cdot F_{EXX} \cdot \left(\frac{\sqrt{2}}{2} \right) \cdot t_{\text{weld}} = 9.28 \cdot \frac{\text{kip}}{\text{in}}$$

$$R_a := R_n \div \Omega_w = 4.64 \cdot \frac{\text{kip}}{\text{in}} \\ > r_w = 4.61 \cdot \frac{\text{kip}}{\text{in}}$$

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
APPENDIX B: BORINGS CONSIDERED FOR DOCK WALL ANALYSIS						



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:		BORING STARTED 8/1/2022		GEI OFFICE Green Bay, WI	
		BORING COMPLETED 8/4/2022		ENTERED BY AKL	APPROVED BY SN
NORTHING 576,877.670	EASTING 102,285.623	RIG/FOREMAN D-120 / DM		GEI PROJECT NO. 2201593	
				PAGE NO. 1 OF 4	

**** Based on the field logs; the "Surface Elevation" corresponds to the barge deck which is approximately 2' above the waterline; Reported elevations are incorrect. Mudline = 580.3' - 5.5' = 574.8'; See pages following boring for water level data during drilling**

GEI




CLIENT:
Brown County Purchasing

PROJECT NAME:
Port Property Developments

LOG OF BORING NUMBER **BW-2-22**

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:

BORING STARTED
8/1/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED
8/4/2022

ENTERED BY

AKL

APPROVED BY

SN

NORTHING

576,877.670

EASTING

102,285.623

RIG/FOREMAN
D-120 / DMGEI PROJECT NO.
2201593

PAGE NO. 2 OF 4

MIDWEST BORING LOG 2201593, PORT PROPERTY DEVELOPMENT, PK GPJ GEI DATA TEMPLATE GDT 3/21/23

GEI



CLIENT:


Brown County Purchasing

LOG OF BORING NUMBER **BW-2-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:

BORING STARTED

8/1/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED

8/4/2022

ENTERED BY

AKL

APPROVED BY

SN

NORTHING

576,877.670

EASTING

102,285.623

RIG/FOREMAN

D-120 / DM

GEI PROJECT NO.

2201593

PAGE NO. 3 OF 4

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK GPJ GEI DATA TEMPLATE.GDT 3/21/23

El. 497.3

GEI



CLIENT:


Brown County Purchasing

LOG OF BORING NUMBER **BW-2-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:

BORING STARTED

8/1/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED

8/4/2022

ENTERED BY

AKL

APPROVED BY

SN

NORTHING

576,877.670

EASTING

102,285.623

RIG/FOREMAN

D-120 / DM

GEI PROJECT NO.

2201593

PAGE NO. 4 OF 4

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

El. 455

Elevation Corrects Based on Water Level

Water Level Data from the NOAA Green Bay East, WI - Station ID: 9087077 was reviewed during the dates the Boring BW-2-22 was drilled. Water level data is presented in the IGLD85 vertical datum.

To Convert from IGLD85 to NAVD88 (project datum): $\text{IGLD85} + 0.44' = \text{NAVD88}$

NOAA DATA (Green Bay East) FROM 8/1 TO 8/4 2022 (IGLD 85)

MIN: 578.88

MAX: 580.88

NAVD88

MIN: 579.32

MAX: 581.32

AVERAGE: 580.3

Approximate Mudline: $580.3' - 5.5' = 574.8' \pm 1'$



GEI




CLIENT:
Brown County Purchasing

PROJECT NAME:
Port Property Developments

LOG OF BORING NUMBER **BW-3-22**

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:

BORING STARTED
7/27/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED
7/28/2022

ENTERED BY

AKL

APPROVED BY

SN

NORTHING

576,204.775

EASTING

102,016.225

RIG/FOREMAN
D-120 / DM

GEI PROJECT NO.

2201593

PAGE NO. 1 OF 4

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

GEI



CLIENT:


Brown County Purchasing

LOG OF BORING NUMBER **BW-3-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:

BORING STARTED

7/27/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED

7/28/2022

ENTERED BY

AKL

APPROVED BY

SN

NORTHING

576,204.775

EASTING

102,016.225

RIG/FOREMAN
D-120 / DM

GEI PROJECT NO.

2201593

PAGE NO. 2 OF 4

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23


GEI



CLIENT:
Brown County Purchasing
PROJECT NAME:
Port Property Developments

LOG OF BORING NUMBER **BW-3-22**

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:		BORING STARTED 7/27/2022	GEI OFFICE Green Bay, WI	
		BORING COMPLETED 7/28/2022	ENTERED BY AKL	APPROVED BY SN
NORTHING 576,204.775	EASTING 102,016.225	RIG/FOREMAN D-120 / DM	GEI PROJECT NO. 2201593	
		PAGE NO. 3 OF 4		

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

GEI




CLIENT:
Brown County Purchasing

PROJECT NAME:
Port Property Developments

LOG OF BORING NUMBER **BW-3-22**

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:		BORING STARTED 7/27/2022	GEI OFFICE Green Bay, WI	
		BORING COMPLETED 7/28/2022	ENTERED BY AKL	APPROVED BY SN
NORTHING 576.204.775	EASTING 102.016.225	RIG/FOREMAN D-120 / DM	GEI PROJECT NO. 2201593	
		PAGE NO. 4 OF 4		

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

GEI



CLIENT:
Brown County Purchasing

PROJECT NAME:
Port Property Developments

LOG OF BORING NUMBER **BW-4-22**

ARCHITECT-ENGINEER

DEPTH (FT) ELEVATION (FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE	RECOVERY	LOCATION: DESCRIPTION OF MATERIAL	UNIT DRY WT. LBS/FT ³	UNCONFINED COMPRESSIVE STRENGTH TONS/FT ²					PLASTIC LIMIT (%)			WATER CONTENT (%)			LIQUID LIMIT (%)		
							1	2	3	4	5	10	20	30	40	50	10	20	30	40
SURFACE ELEVATION (ft.) 580.2						⊗ STANDARD PENETRATION BLOWS/FT														
580					Water from 0 to 27.5 feet															
					NOAA - GREEN BAY EAST, WI BUOY IGLD85 TO NAVD88 MAX: 580.8 MIN: 580.15 AVG: 580.5															
570																				
560																				
550	1	SS			27.5 SEDIMENT Dark brown organic silty (CL) - wet - very loose 28.0 Coarse sand (SP) - with gravel - wet - very loose 28.5 Brown silty clay (CL) - trace gravel - wet - stiff															
	2	SS			CLAY IIA															

El. 552.8
El. 551.8

161.5

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:		BORING STARTED 7/25/2022		GEI OFFICE Green Bay, WI	
		BORING COMPLETED 7/26/2022		ENTERED BY AKL	
NORTHING 575,546.365		EASTING 101,809.521		APPROVED BY SN	
		RIG/FOREMAN D-120 / DM		GEI PROJECT NO. 2201593	
				PAGE NO. 1 OF 4	

MIDWEST BORING LOG 2201593, PORT PROPERTY DEVELOPMENT, PK GPJ GEI DATA TEMPLATE.GDT 3/21/23

GEI



CLIENT:


Brown County Purchasing

LOG OF BORING NUMBER **BW-4-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:

BORING STARTED

7/25/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED

7/26/2022

ENTERED BY

AKL

APPROVED BY

SN

NORTHING

575,546.365

EASTING

101,809.521

RIG/FOREMAN

D-120 / DM

GEI PROJECT NO.

2201593

PAGE NO. 2 OF 4

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

El. 532.3

GEI



CLIENT:


Brown County Purchasing

LOG OF BORING NUMBER **BW-4-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:

BORING STARTED

7/25/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED

7/26/2022

ENTERED BY

AKL

APPROVED BY

SN

NORTHING

575,546.365

EASTING

101,809.521

RIG/FOREMAN

D-120 / DM

GEI PROJECT NO.

2201593

PAGE NO. 3 OF 4

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

El. 532.3

GEI



CLIENT:

Brown County Purchasing

LOG OF BORING NUMBER **BW-4-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER

LOCATION:

DESCRIPTION OF MATERIAL

SURFACE ELEVATION (ft.) 580.2

UNCONFINED COMPRESSIVE STRENGTH

TONS/FT²

1	2	3	4	5	
PLASTIC LIMIT (%)	10	20	30	40	50
WATER CONTENT (%)					
LIQUID LIMIT (%)					


10	20	30	40	50	60
STANDARD PENETRATION BLOWS/FT					

UNIT DRY WT.
LBS/FT³

El. 471

El. 456

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL:

BORING STARTED

7/25/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED

7/26/2022

ENTERED BY

AKL

APPROVED BY

SN

NORTHING

575,546.365

EASTING

101,809.521

RIG/FOREMAN

D-120 / DM

GEI PROJECT NO.

2201593

PAGE NO. 4 OF 4



ARCHITECT-ENGINEER


El. 559.75

PAGE NO. 1 OF 1

Date: Jan. 10, 2023
Estimated Water Depth: 0 ft
Rig/Operator: CAP

Northing: 263578.7
Easting: 2488155.8
Elevation:

Total Depth: 51.4 ft
Termination Criteria: Target




- | | | |
|-----------------------------------|--|------------------------------------|
| 1 - Sensitive, Fine Grained Soils | 4 - Silt Mixtures-Clay Silt to Silty Clay | 7 - Gravely Sand to Sand |
| 2 - Organic Soils, Peats | 5 - Sand Mixtures-Silty Sand to Sandy Silt | 8 - Very Stiff Clay to Clayey Sand |
| 3 - Clays-Clay to Silty Clay | 6 - Sands-Clean Sand to Silty Sand | 9 - Very Stiff Fine Grained Soils |



Client	Brown County			Page	16 of 16
Project	Port Property Redevelopment			Pg. Rev.	
By		Chk.		App.	
Date		Date		Date	

GEI Project No.	2201593	Document No.	Geotechnical Data Report - Appendix A.3
Subject	CPTu Undrained Shear Strength Profile Estimations		



GEI



CLIENT:


Brown County Purchasing

LOG OF BORING NUMBER **BL-14-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL: Groundwater observed at 5.0 ft BCI

Avg Lake Level during drilling = 579.4' (12/31/2022
& 1/13/2023) ~ 0.4' lower than lake level

NORTHING
575,843.210EASTING
101,759.370BORING STARTED
12/30/2022BORING COMPLETED
1/13/2023RIG/FOREMAN
D-120 / DJM

GEI OFFICE

Green Bay, WI

ENTERED BY

CAH

APPROVED BY

SN

GEI PROJECT NO.
2201593

PAGE NO. 1 OF 3

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

579.0

GEI



CLIENT:


Brown County Purchasing

LOG OF BORING NUMBER **BL-14-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL: Groundwater observed at 5.0 ft BCI

BORING STARTED
12/30/2022

GEI OFFICE

Green Bay, WI

BORING COMPLETED
1/13/2023

ENTERED BY

CAH

APPROVED BY

SN

NORTHING

575,843.210

EASTING

101,759.370

RIG/FOREMAN
D-120 / DJM

GEI PROJECT NO.

2201593

PAGE NO. 2 OF 3

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

GEI




CLIENT:
Brown County Purchasing

PROJECT NAME:
Port Property Developments

LOG OF BORING NUMBER **BL-14-22**

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL: Groundwater observed at 5.0 ft BCI	BORING STARTED 12/30/2022	GEI OFFICE Green Bay, WI	
	BORING COMPLETED 1/13/2023	ENTERED BY CAH	APPROVED BY SN
NORTHING 575,843.210	EASTING 101,759.370	RIG/FOREMAN D-120 / DJM	GEI PROJECT NO. 2201593
		PAGE NO. 3 OF 3	

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

GEI



CLIENT:


Brown County Purchasing

LOG OF BORING NUMBER **BL-15-22**

PROJECT NAME:

Port Property Developments

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL: Groundwater observed at 6.2 ft BCI
Avg Lake Level during drilling = 579.5'
 ~ 0.9' lower than lake level

NORTHING 576,372.821 EASTING 101,967.695

BORING STARTED
11/16/2022
 BORING COMPLETED
11/17/2022

RIG/FOREMAN
D-50 / JW

GEI OFFICE
Green Bay, WI

ENTERED BY **AKL** APPROVED BY **SN**

GEI PROJECT NO.
2201593

PAGE NO. 1 OF 3

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

GEI




CLIENT:
Brown County Purchasing

PROJECT NAME:
Port Property Developments

LOG OF BORING NUMBER **BL-15-22**

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

WATER LEVEL: Groundwater observed at 6.2 ft BCI

BORING STARTED
11/16/2022

GEI OFFICE
Green Bay, WI

BORING COMPLETED
11/17/2022

ENTERED BY
AKL

APPROVED BY
SN

NORTHING
576,372.821

EASTING
101,967.695

RIG/FOREMAN
D-50 / JW

GEI PROJECT NO.
2201593

PAGE NO. 2 OF 3

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

GEI




CLIENT:
Brown County Purchasing

PROJECT NAME:
Port Property Developments

LOG OF BORING NUMBER **BL-15-22**

ARCHITECT-ENGINEER



The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.


WATER LEVEL: Groundwater observed at 6.2 ft BCI	BORING STARTED 11/16/2022	GEI OFFICE Green Bay, WI	
	BORING COMPLETED 11/17/2022	ENTERED BY AKL	APPROVED BY SN
NORTHING 576,372.821	EASTING 101,967.695	RIG/FOREMAN D-50 / JW	GEI PROJECT NO. 2201593
		PAGE NO. 3 OF 3	

MIDWEST BORING LOG 2201593_PORT PROPERTY DEVELOPMENT_PK.GPJ GEI DATA TEMPLATE.GDT 3/21/23

Date: Jan. 4, 2023
Estimated Water Depth: 0 ft
Rig/Operator: CAP

Northing: 263915.0
Easting: 2488216.7
Elevation:


Total Depth: 69.1 ft
Termination Criteria: Target



- | | | |
|-----------------------------------|--|------------------------------------|
| 1 - Sensitive, Fine Grained Soils | 4 - Silt Mixtures-Clay Silt to Silty Clay | 7 - Gravely Sand to Sand |
| 2 - Organic Soils, Peats | 5 - Sand Mixtures-Silty Sand to Sandy Silt | 8 - Very Stiff Clay to Clayey Sand |
| 3 - Clays-Clay to Silty Clay | 6 - Sands-Clean Sand to Silty Sand | 9 - Very Stiff Fine Grained Soils |



Client	Brown County			Page	13 of 16
Project	Port Property Redevelopment			Pg. Rev.	
By		Chk.		App.	
Date		Date		Date	
01593	Document No.	Geotechnical Data Report - Appendix A.3			
PTu Undrained Shear Strength Profile Estimations					



	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
APPENDIX C: BROWN COUNTY PORT PROPERTY GEOTECHNICAL DATA REPORT (PROVIDED UNDER SEPARATE COVER)						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
APPENDIX D: BROWN COUNTY DOCK WALL GLOBAL STABILITY ANALYSIS						

	Client	Brown County WI			Page	1 of 5
	Project	Port Property Redevelopment			Pg. Rev.	Rev.0
	By	KMK	Chk.		App.	
	Date	06/15/2023	Date		Date	
GEI Project No.	2201593	Document No.				
Subject	Bulkhead Wall Preliminary Design – Global Stability Analysis					
<u>Purpose</u> The purpose of this calculation is to present the global stability of the proposed bulkhead wall with respect to the maximum allowable stockpile offset and height behind the bulkhead wall. <u>References</u> 1. GEI Preliminary Drawings for Pulliam Redevelopment, dated April 19, 2023. 2. Port Property Redevelopment - Geotechnical Data Report, prepared by GEI, dated March 2023. 3. Duncan and Wright, Soil Strength and Slope Stability, John Wiley & Sons Inc. 2005. <u>Assumptions</u> 1. The design site grade is +592 ft. The design dredge grade is +550 feet. The design water level is +578 feet. 2. The water level varies at the site, generally between +575 feet and +582 feet. The design water level is +578 feet. The low-water datum and a high-water datum should be established and checked for the final design. 3. Soil layer and strength properties are identified in the Geotechnical Data report, Section 4.7. 4. For the short-term undrained strength analysis, a nominal surcharge of 500 psf was assumed from the edge of the wall to the edge of the stockpile. 5. The maximum stockpile width extends from the face of the wall to approximately 400 feet behind the wall based on site dimensions. The assumed stockpile slopes were 1.4H:1V. Two stockpile unit weights were considered. For a limestone or gravel stockpile, the total unit weight of the stockpile material was assumed to be 100 pcf. For a coal stockpile, the total unit weight of the stockpile was assumed to be 60 pcf. 6. The stockpile height was assumed to vary between 40 feet and 80 feet. Stockpiles greater than 80 feet in height were not analyzed. The maximum allowable stockpile height was calculated for various assumed toe setbacks from the wall for coal or limestone materials. 7. The stockpile toe setback was varied from the face of the wall in 25-foot increments, from 25 feet to 100 feet offset. Based on the preliminary internal stability calculations, offsets on the order of 25 to 75 feet provide workable solutions for the required sheeting section modulus. 8. The recommended minimum factors of safety for the various scenarios are based on standard geotechnical engineering practice [Duncan and Wright 2005]. For undrained strength analyses, the required minimum factor of safety is 1.30. However, for this analysis, the required minimum factor of safety of 1.50 was also considered due to difficulty in controlling the stockpile geometry.						




Client Brown County WI Project Port Property Redevelopment By KMK Date 06/15/2023	Page 2 of 5 Pg. Rev. Rev.0	
	Chk.	App.
	Date	Date
	GEI Project No. 2201593 Document No.	
Subject Bulkhead Wall Preliminary Design – Global Stability Analysis		

9. The embedment length of the wall was varied for each stockpile condition in order to achieve a minimum factor of safety of 1.50. Global stability failures were assumed to pass below the toe of the wall.
10. Based on the internal stress analysis for the dockwall, the required toe elevation of the wall is +527 if a limestone stockpile is beyond 50 feet from the wall. The required toe elevation of the wall is +519 if a limestone stockpile is set at 15 feet from the wall. For the purpose of this analysis, it was assumed that the toe of the wall cannot practically be installed deeper than +510.

Undrained Strength Analysis


The results of the undrained strength analysis are presented as figures below. Scenario 1 assumes that the wall is installed to elevation +520 feet and a limestone material is stockpiled behind the wall. In this scenario, the stockpile would need to be offset a minimum of 50 feet and the maximum allowable height of the stockpile would be 40 feet in order to maintain a factor of safety of 1.5. If a factor of safety of 1.3 is allowed, the limestone stockpile could be offset a minimum of 25 feet and the maximum allowable height would be approximately 48 feet.





Client Brown County WI Project Port Property Redevelopment By KMK Date 06/15/2023	Page 3 of 5	
	Pg. Rev. Rev.0	
	Chk.	App.
	Date	Date
GEI Project No. 2201593	Document No.	
Subject Bulkhead Wall Preliminary Design – Global Stability Analysis		


Scenario 2 below assumes that the wall is extended to elevation +510 feet and a limestone material is stockpiled behind the wall. In this scenario, the stockpile would still need to be offset a minimum of 50 feet and the maximum allowable height of the stockpile would be 40 feet in order to maintain a factor of safety of 1.5. If a factor of safety of 1.3 is allowed, the limestone stockpile could be offset a minimum of 25 feet and the maximum allowable height would be approximately 52 feet. There is minimal improvement of the factor of safety and minimal gains in the allowable stockpile size by extending the wall length.





Client Brown County WI Project Port Property Redevelopment By KMK Date 06/15/2023	Page 4 of 5	
	Pg. Rev. Rev.0	
	Chk.	App.
	Date	Date
GEI Project No. 2201593	Document No.	
Subject Bulkhead Wall Preliminary Design – Global Stability Analysis		

Scenario 3 below assumes that the wall installed to elevation +520 feet and the stockpile material is coal instead of limestone. In this scenario, the stockpile could be as close as 10 feet from the wall with a maximum height of 60 feet in order to maintain a factor of safety of 1.5. If a factor of safety of 1.3 is allowed, the coal stockpile could be 10 feet from the wall and 80 feet in height. There is minimal improvement of the factor of safety and minimal gains in the allowable stockpile size by extending the wall length below elevation +520.



	Client	Brown County WI			Page	5 of 5																																																						
	Project	Port Property Redevelopment			Pg. Rev.	Rev.0																																																						
	By	KMK	Chk.		App.																																																							
	Date	06/15/2023	Date		Date																																																							
GEI Project No.	2201593	Document No.																																																										
Subject	Bulkhead Wall Preliminary Design – Global Stability Analysis																																																											
<u>Long-Term Steady State Analysis</u> The results of the long-term drained strength analyses are presented in the following table. The minimum acceptable factor of safety for long-term conditions is 1.5. The long-term steady state conditions were checked for the maximum acceptable scenarios identified in the short-term undrained strength analyses. The analysis shows that the toe of the wall would need to be extended to elevation +510 feet to meet the long-term factor of safety requirements for the scenario of a limestone stockpile within 25 feet of the wall. The wall designed with a toe elevation of +520 feet would meet long-term factor of safety requirements for the coal stockpile within 10 feet of the wall or the limestone stockpile within 50 feet of the wall. <table border="1"> <thead> <tr> <th>Stockpile Material</th> <th>Stockpile Offset (ft)</th> <th>Stockpile Height (ft)</th> <th>Sheetpile Toe Elevation (ft)</th> <th>Short-Term Factor of Safety</th> <th>Long-Term Factor of Safety</th> </tr> </thead> <tbody> <tr> <td>Limestone</td> <td>50 ft</td> <td>40 ft</td> <td>+520</td> <td>1.53</td> <td>1.50</td> </tr> <tr> <td>Limestone</td> <td>25 ft</td> <td>48 ft</td> <td>+520</td> <td>1.30</td> <td>1.38</td> </tr> <tr> <td>Limestone</td> <td>25 ft</td> <td>40 ft</td> <td>+520</td> <td>1.43</td> <td>1.43</td> </tr> <tr> <td>Limestone</td> <td>25 ft</td> <td>48 ft</td> <td>+510</td> <td>1.33</td> <td>1.55</td> </tr> <tr> <td>Coal</td> <td>10 ft</td> <td>60 ft</td> <td>+520</td> <td>1.52</td> <td>1.67</td> </tr> <tr> <td>Coal</td> <td>10 ft</td> <td>80 ft</td> <td>+520</td> <td>1.33</td> <td>1.59</td> </tr> </tbody> </table> <u>Conclusion</u> Based on the analyses discussed above, the design sheetpile toe elevation should be +520 feet. A limestone material stockpile may have a maximum height of 40 feet and must be offset a minimum of 50 feet from the wall. A coal stockpile may have a maximum height of 60 feet and be offset a minimum of 10 feet from the wall. <table border="1"> <thead> <tr> <th>Design Sheetpile Toe Elevation (ft)</th> <th>Stockpile Material</th> <th>Max Stockpile Height (ft)</th> <th>Minimum Stockpile Offset (ft)</th> </tr> </thead> <tbody> <tr> <td>+520 feet</td> <td>Limestone</td> <td>40 ft</td> <td>50 ft</td> </tr> <tr> <td></td> <td>Coal</td> <td>60 ft</td> <td>10 ft</td> </tr> </tbody> </table> Stockpile heights and offsets beyond what is described above would have a marginal factor of safety and may result in creep movement and overstressing of the wall. Excessive creep movement could lead to softening of the clay soils and a major global stability failure taking out the entire wall and failing into the river.							Stockpile Material	Stockpile Offset (ft)	Stockpile Height (ft)	Sheetpile Toe Elevation (ft)	Short-Term Factor of Safety	Long-Term Factor of Safety	Limestone	50 ft	40 ft	+520	1.53	1.50	Limestone	25 ft	48 ft	+520	1.30	1.38	Limestone	25 ft	40 ft	+520	1.43	1.43	Limestone	25 ft	48 ft	+510	1.33	1.55	Coal	10 ft	60 ft	+520	1.52	1.67	Coal	10 ft	80 ft	+520	1.33	1.59	Design Sheetpile Toe Elevation (ft)	Stockpile Material	Max Stockpile Height (ft)	Minimum Stockpile Offset (ft)	+520 feet	Limestone	40 ft	50 ft		Coal	60 ft	10 ft
Stockpile Material	Stockpile Offset (ft)	Stockpile Height (ft)	Sheetpile Toe Elevation (ft)	Short-Term Factor of Safety	Long-Term Factor of Safety																																																							
Limestone	50 ft	40 ft	+520	1.53	1.50																																																							
Limestone	25 ft	48 ft	+520	1.30	1.38																																																							
Limestone	25 ft	40 ft	+520	1.43	1.43																																																							
Limestone	25 ft	48 ft	+510	1.33	1.55																																																							
Coal	10 ft	60 ft	+520	1.52	1.67																																																							
Coal	10 ft	80 ft	+520	1.33	1.59																																																							
Design Sheetpile Toe Elevation (ft)	Stockpile Material	Max Stockpile Height (ft)	Minimum Stockpile Offset (ft)																																																									
+520 feet	Limestone	40 ft	50 ft																																																									
	Coal	60 ft	10 ft																																																									

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
APPENDIX E: SETTLEMENT ANALYSIS						

	Client	Brown County, WI			Page	
	Project	Brown County Redevelopment			Pg. Rev.	
	By	E. Burton	Chk.		App.	
	Date	02/10/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Settlement and Time Rate of Consolidation Analysis					
Settlement Resulting from Proposed Dock Wall Construction We used primary consolidation and time rate of consolidation equations, provided by UFC 3-220-10 Soil Mechanics (February 2022), to calculate primary consolidation and the time rate of consolidation in the clay layers associated with constructing the proposed dock wall along Section A on the Fox River in Green Bay, WI particularly as it pertains to clay layers beneath the proposed tierod and deadman system. Section A was considered the most critical section for settlement analysis due to the thickness of the soft Clay II layer compared to Sections B-D. We considered the subsurface profile for Section A, provided in the appendix, to determine the elevations of the top and bottom of each layer. The soil parameters considered were based on the Geotechnical Data Report produced by GEI in March 2023 as well as Boring BW-2-22 which was considered most representative of the soil strata at Section A. The settlement analysis considers the following stages of construction: 1. Immediately after dredging of existing Sediment. 2. Immediately after placement of proposed Granular Fill (Time Rate Consideration: 60 days) 3. Immediately after placement of stockpile surcharge (Time Rate Consideration: 60 days + ½ Year) Because the uniform live load is not anticipated to be a constant load, the effect of the surcharge on the underlying soil was ignored for this analysis. Immediate settlement in the granular fill layer due to surcharge loading was not in the scope of this analysis and was also not considered for the clay layers. The time rates selected for analysis are based on our best estimate of the duration of time between stages or the expected length of time for a stockpile to be retained. The change in vertical effective stress due to the placement of the material stockpile was evaluated at three locations as a function of distance from the water-side face of the proposed limestone stockpile in the considered clay layers beneath the tierod and deadman system: 10', 35' and 60'. These distances from the water-side face of the proposed limestone stockpile correspond to a distance of 25', 50' and 75' from the water-side face of the proposed dock wall. Cases 1 and 2 were conducted to estimate the overconsolidation ratio (OCR) at the midpoint of each considered clay layer for the primary consolidation calculations performed for Case 3. Therefore, the estimated primary consolidation due to the placement of the Granular Fill was considered equal at each considered distance in the analysis. The following pages present a detailed account of our calculations. Estimated settlements are presented in the attached summary tables.						

GEI Consultants	Client	Brown County, WI			Page	
	Project	Brown County Redevelopment			Pg. Rev.	
	By	E. Burton	Chk.		App.	
	Date	02/10/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Settlement and Time Rate of Consolidation Analysis					

Soil Parameters

The following soil parameters from the GEI Geotechnical Data Report were considered for analysis:

Table 1: Summary of Design Soil Parameters

Name	Elevation (ft)	Total Unit Weight (pcf)	Consolidation Parameters					
			e ₀	P _c (psf)	C _c	C _{cr}	S _u (psf)	*E _s (ksf)
Sediment	575 to 542	80	-	-	-	-	-	-
Granular Fill	591 to 542	130	-	-	-	-	-	-
Clay I	542 to 532	130	0.9	6600	0.251	0.064	2000	1200
Clay II	532 to 517	130	1	6000	0.44	0.07	1000	600
Clay III	517 to 492	130	1.2	8200	0.409	0.09	2500	1500

*where $E_s = 600 \times S_u$

Primary Settlement Equations:

1. For overconsolidated soil layers in which the final stress is less than or equal to the preconsolidation stress:

$$S = \left(C_{er} \log \left(\frac{\sigma'_{v0} + \Delta\sigma_v}{\sigma'_{v0}} \right) \right) H_0$$

where C_{er} is the modified recompression index (recompression ratio), σ'_{v0} is the in-situ vertical effective stress, $\Delta\sigma_v$ is the change in vertical stress, H_0 is the soil layer thickness, and S is the primary consolidation for the soil layer under evaluation.

2. For overconsolidated soil layers in which the final stress is greater than the preconsolidation stress:

$$S = \left(C_{er} \log \left(\frac{\sigma'_p}{\sigma'_{v0}} \right) + C_{ec} \log \left(\frac{\sigma'_{v0} + \Delta\sigma_v}{\sigma'_p} \right) \right) H_0$$

where σ'_p is the maximum past pressure and C_{ec} is the modified compression index (compression ratio).

C_{ec} and C_{er} , the compression index and recompression index, are void ratio – log stress-based parameters. The modified compression index (compression ratio) and the modified recompression index (recompression ratio) are strain – log stress-based parameters.



Client	Brown County, WI			Page	
Project	Brown County Redevelopment			Pg. Rev.	
By	E. Burton	Chk.		App.	
Date	02/10/2025	Date		Date	

Project No.	2201593	Document No.	N/A
--------------------	---------	---------------------	-----

Subject	Settlement and Time Rate of Consolidation Analysis
----------------	--

C_c = compression index

$$C_{c\varepsilon} = \frac{C_c}{1 + e_0}$$

C_r = recompression index

$$C_{\varepsilon r} = \frac{C_r}{1 + e_0}$$

Primary Time Rate of Consolidation Equations:

1. Time Factor Equation

$$T_v = \frac{c_v t}{H_{dr}^2}$$

where T_v = time factor for vertical drainage, c_v = coefficient of consolidation for the soil layer in the vertical direction, and H_{dr} = drainage path length.

2. Average Degree of Consolidation Equation

$$\text{For } T_v \leq 0.2: \overline{U_z} \approx \frac{2}{\sqrt{\pi}} \sqrt{T_v}$$

$$\text{For } T_v > 0.2: \overline{U_z} \approx 1 - \frac{8}{\pi} \exp\left(\frac{-\pi^2}{4} T_v\right)$$

where $\overline{U_z}$ = degree of compression.

Summary of Results:

Table 2: Primary Consolidation Results

Distance, X from Dock Wall (ft)	Estimated Total Primary Consolidation (in)
10	9.0
35	10.4
60	10.9



Consultants

Client	Brown County, WI			Page	
Project	Brown County Redevelopment			Pg. Rev.	
By	E. Burton	Chk.		App.	
Date	02/10/2025	Date		Date	

Project No.	2201593	Document No.	N/A
Subject	Settlement and Time Rate of Consolidation Analysis		

Table 3: Time Rate of Consolidation Results


Clay Layer	Case (II or III)	Time (Days)	Distance, X from Dock Wall (ft)	Vertical Effective Stress (tsf)	Coeff of Consol, C_v (ft ² /sec)	H_{dr} (ft)	T_v (-)	Avg. Degree of Consol, U_z (%)	Settlement at time considered (in)	T.v @ $U_z = 75\%$ (-)	Time for 75% of Consol to occur (days)
Clay I	II	60	-	2.3	3.36E-06	4.97	0.71	95%	2.1	0.44	38
Clay III	II	60	-	3.4	2.65E-06	12.46	0.09	34%	0.9	0.44	299
Clay I	III	242.5	10	9	7.21E-07	4.86	0.64	90%	0.3	0.44	168
Clay III	III	242.5	10	8	9.59E-07	12.37	0.13	41%	0.4	0.44	816
Clay I	III	242.5	35	23.5	1.18E-06	4.64	1.15	100%	0.6	0.44	93
Clay III	III	242.5	35	17.6	7.00E-07	12.17	0.10	36%	0.6	0.44	1081
Clay I	III	242.5	60	33.1	1.12E-06	4.48	1.17	100%	0.6	0.44	92
Clay III	III	242.5	60	25.8	8.00E-07	12.00	0.12	39%	0.8	0.44	920

Notes:

1. Coefficients of Consolidation for Clay I and Clay III are selected based on results from Consolidation Test Data from Boring BW-2-22 at similar vertical effective stresses from the primary consolidation analysis.
2. Average Degree of Consolidations, U_z , are based upon the estimated time frame between Case II and Case III (60 days) and the duration of limestone stockpile retention once applied, Case III: (60 days + 6 months).

	Client	Brown County, WI			Page	
	Project	Brown County Redevelopment			Pg. Rev.	0
	By	E. Burton	Chk.		App.	
	Date	02/10/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Settlement and Time Rate of Consolidation Analysis					
Settlement Analysis Cases						


SECTION A



- ASSUMPTIONS:
- ANALYSIS BASED ON FOLLOWING BORING LOGS: BW-2-22
 - NOTE BASED ON WATER LEVELS DURING DRILLING AND FIELD LOGS, THE REPORTED "SURFACE ELEVATION" APPEARS TO BE INCORRECTLY REPORTED. THE "SURFACE ELEVATION" CORRESPONDS TO THE BARGE DECK. THE BARGE HAS AN APPROXIMATE FREEBOARD OF 2'. WATER LEVELS DURING DRILLING AT NOAA STATION "GREEN BAY EAST" RANGED FROM EL 579.3 NAVD88 (EL. 578.9 IGLD85) TO EL 581.3 NAVD88 (580.9 IGLD85). ASSUMING AN AVERAGE WATER ELEVATION OF 580.3 THE MUDLINE WOULD APPROXIMATELY BE EL 574.8. THIS IS ASSUMED FOR DEVELOPING THE SOIL PROFILE
 - LOW LAKE LEVEL ASSUMED FOR DESIGN OF THE DOCKWALL IS EL. 576.

SETTLEMENT CASE I: Immediately after dredging of existing fill material

SECTION A



ASSUMPTIONS:


- ANALYSIS BASED ON FOLLOWING BORING LOGS: BW-2-22
- NOTE BASED ON WATER LEVELS DURING DRILLING AND FIELD LOGS, THE REPORTED "SURFACE ELEVATION" APPEARS TO BE INCORRECTLY REPORTED. THE "SURFACE ELEVATION" CORRESPONDS TO THE BARGE DECK. THE BARGE HAS AN APPROXIMATE FREEBOARD OF 2'. WATER LEVELS DURING DRILLING AT NOAA STATION "GREEN BAY EAST" RANGED FROM EL 579.3 NAVD88 (EL. 578.9 IGLD85) TO EL 581.3 NAVD88 (580.9 IGLD85). ASSUMING AN AVERAGE WATER ELEVATION OF 580.3 THE MUDLINE WOULD APPROXIMATELY BE EL 574.8. THIS IS ASSUMED FOR DEVELOPING THE SOIL PROFILE
- LOW LAKE LEVEL ASSUMED FOR DESIGN OF THE DOCKWALL IS EL. 576.

SETTLEMENT CASE II:

Immediately after placement of proposed Granular Fill

- Calc immediate settlement using an initial vertical effective stress from the final vertical effective stress of Case I
- Calc consolidation using c_v and permeability
- Report time for completion of primary consolidation

SECTION A




ASSUMPTIONS:

- ANALYSIS BASED ON FOLLOWING BORING LOGS: BW-2-22
- NOTE BASED ON WATER LEVELS DURING DRILLING AND FIELD LOGS, THE REPORTED "SURFACE ELEVATION" APPEARS TO BE INCORRECTLY REPORTED. THE "SURFACE ELEVATION" CORRESPONDS TO THE BARGE DECK. THE BARGE HAS AN APPROXIMATE FREEBOARD OF 2'. WATER LEVELS DURING DRILLING AT NOAA STATION "GREEN BAY EAST" RANGED FROM EL. 579.3 NAVD88 (EL. 578.9 IGLD85) TO EL. 581.3 NAVD88 (580.9 IGLD85). ASSUMING AN AVERAGE WATER ELEVATION OF 580.3 THE MUDLINE WOULD APPROXIMATELY BE EL. 574.8. THIS IS ASSUMED FOR DEVELOPING THE SOIL PROFILE
- LOW LAKE LEVEL ASSUMED FOR DESIGN OF THE DOCKWALL IS EL. 576.

SETTLEMENT CASE III:

Immediately after placement of stockpile surcharge

- Assume 6 months from placement of fill to placement of stockpile; using primary consolidation calculation from Case II, what is S at $t = 6$ months
- Calculate immediate settlement, starting from $t = 6$ months, for placement of surcharge
- Calculate time rate of consolidation for primary consolidation





ASSUMPTIONS:

- ANALYSIS BASED ON FOLLOWING BORING LOGS: BW-2-22
- NOTE BASED ON WATER LEVELS DURING DRILLING AND FIELD LOGS, THE REPORTED "SURFACE ELEVATION" APPEARS TO BE INCORRECTLY REPORTED. THE "SURFACE ELEVATION" CORRESPONDS TO THE BARGE DECK. THE BARGE HAS AN APPROXIMATE FREEBOARD OF 2'. WATER LEVELS DURING DRILLING AT NOAA STATION "GREEN BAY EAST" RANGED FROM EL 579.3 NAVD88 (EL. 578.9 IGLD85) TO EL 581.3 NAVD88 (580.9 IGLD85). ASSUMING AN AVERAGE WATER ELEVATION OF 580.3 THE MUDLINE WOULD APPROXIMATELY BE EL 574.8. THIS IS ASSUMED FOR DEVELOPING THE SOIL PROFILE
- LOW LAKE LEVEL ASSUMED FOR DESIGN OF THE DOCKWALL IS EL. 576.

	Client	Brown County, WI			Page	
	Project	Brown County Redevelopment			Pg. Rev.	0
	By	E. Burton	Chk.		App.	
	Date	02/10/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Settlement and Time Rate of Consolidation Analysis					
Analysis Results						

q0	4000 psf
pi	3.141593
Z	56.5 FT

X	B	R^2	s.z
0	0	3192.25	0
1	0.017697	3192.25	45.06807
5	0.088266	3192.258	225.0591
10	0.175177	3192.28	448.3923
15	0.2595	3192.315	668.4275
20	0.340218	3192.363	883.8675
25	0.416581	3192.419	1093.758
30	0.488118	3192.482	1297.499
35	0.554612	3192.549	1494.813
40	0.616051	3192.619	1685.685
45	0.672579	3192.69	1870.299
50	0.724441	3192.76	2048.967
55	0.771946	3192.83	2222.084
60	0.815432	3192.897	2390.079
65	0.855243	3192.961	2553.392
70	0.891715	3193.023	2712.45
75	0.925165	3193.082	2867.657
80	0.955888	3193.139	3019.39
85	0.984152	3193.192	3167.99
90	1.010202	3193.243	3313.768
95	1.034256	3193.29	3457.003
100	1.05651	3193.336	3597.945
105	1.077139	3193.378	3736.817
110	1.096299	3193.419	3873.818
115	1.114129	3193.457	4009.123
120	1.130753	3193.494	4142.892



Case I
Evaluate vertical effective stress immediately after
dredging of existing fill material.

L.stone: 4000 psf



Layer Elevations		Unit Weights		Initial Void Ratio			P'c (psf)			C.c		C.r		
GWT:	577	ft	y.w	62.4	pcf									
Clay I:	542	ft	y.c1	130	pcf	e.0	0.9	s'p.1	6600	psf	C.c.1	0.251	C.r.1	0.064
Clay II:	532	ft	y.c2	130	pcf	e.0	1	s'p.2	6000	psf	C.c.2	0.44	C.r.2	0.07
Clay III:	517	ft	y.c3	130	pcf	e.0	1.2	s'p.3	8200	psf	C.c.3	0.409	C.r.3	0.09
Bot. Clay III:	492	ft	y.gr.f	130	pcf									
Sediment:	575	ft	y.sed	80	pcf									
Top of Wall	591	ft												
Stress (psf)														

Prior to Dredging on Active Side

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Vertical Effective Stress @ Midpoint (psf)	in situ OCR (-)
577	Water	-	-	-	-	0	0	0	0	-
576	Water	577	575	2	1	1	62.4	62.4	0	-
558.5	Sediment	575	542	33	16.5	18.5	1444.8	1154.4	290.4	-
537	Clay I	542	532	10	5	40	3414.8	2496	918.8	7.2
524.5	Clay II	532	517	15	7.5	52.5	5039.8	3276	1763.8	3.4
504.5	Clay III	517	492	25	12.5	72.5	7639.8	4524	3115.8	2.6

Immediately after Dredging on Active Side

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Vertical Effective Stress @ Midpoint (psf)	in situ OCR (-)
577	Water	-	-	-	-	0	0	0	0	-
559.5	Water	577	542	35	17.5	17.5	1092	1092	0	-
537	Clay I	542	532	10	5	40	2834	2496	338	19.5
524.5	Clay II	532	517	15	7.5	52.5	4459	3276	1183	5.1
504.5	Clay III	517	492	25	12.5	72.5	7059	4524	2535	3.2




Case II
Evaluate vertical effective stress immediately
after placing Granular Fill

L.stone: 4000 psf Poisson's Ratio: 0.49 Width, B (ft): 75

Layer Elevations		Unit Weights			Initial Void Ratio			u1	u0	P'c (psf)			C.c		Cec	C.r		Cer	E.s (ksf)	E.s (psf)
Granular Fill:	591	ft																		
GWT:	577	ft	y.w	62.4	pcf						6600									
Clay I:	542	ft	y.c1	130	pcf	e.0	0.9	0.25	1	s'p.1	6000	psf	C.c.1	0.251	0.13	C.r.1	0.064	0.034	1200	1200000
Clay II:	532	ft	y.c2	130	pcf	e.0	1	0.32	1	s'p.2	8200	psf	C.c.2	0.44	0.22	C.r.2	0.07	0.035	600	600000
Clay III:	517	ft	y.c3	130	pcf	e.0	1.2	0.41	1	s'p.3	8200	psf	C.c.3	0.409	0.19	C.r.3	0.09	0.041	1500	1500000
Bot. Clay III:	492	ft	y.gr.f	130	pcf															
Sediment:	575	ft	y.sed	80	pcf															
Top of Wall	591	ft											Stress (psf)							

Immediately after Dredging on Active Side


Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint	Vertical Effective Stress @ Midpoint (psf)	in situ OCR (-)
577	Water	-	-	-	-	0	0	0	0	-
559.5	Water	577	542	35	17.5	17.5	1092	1092	0	-
537	Clay I	542	532	10	5	40	2834	2496	338	17.8
524.5	Clay II	532	517	15	7.5	52.5	4459	3276	1183	6.9
504.5	Clay III	517	492	25	12.5	72.5	7059	4524	2535	3.2



Immediately after placement of Full Height of Granular Fill

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Full Ht after Immediate Settlement (ft)	H0 after Immediate Settlement (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint	Vertical Effective Stress @ Midpoint (psf)	Delta Vertical Stress (psf)	in situ OCR (-)	Depth from Base of Applied Load to Midpoint (ft)	Primary Consolidation (in)
591	-	-	-	-	-	-	-	0	0	0	0	0	-	-	-
584	Gr. Fill (unsat.)	591	577	14	7	-	-	0	910	0	910	-	-	-	-
559.5	Gr. Fill (sat.)	577	542	35	17.5	-	-	17.5	4095	1092	3003	-	-	-	-
537	Clay I	542	532	10	5	9.93	4.97	40	7020	2496	4524	4186	1.3	54	2.3
524.5	Clay II	532	517	15	7.5	14.83	7.42	52.5	8645	3276	5369	4186	1.5	66.5	2.0
504.5	Clay III	517	492	25	12.5	24.91	12.46	72.5	11245	4524	6721	4186	1.2	86.5	2.6
														Σ (in)	6.9

Calc:
- Immediate Settlement
- Consolidation of Clay Layers




Case III - X =10FT
Evaluate vertical effective stress immediately
after placement of Limestone Stockpile

L.stone: 4000 psf Poisson's Ratio: 0.49 Width, B (ft): 75

Layer Elevations		Unit Weights		Initial Void Ratio		u1	u0	P'c (psf)		C.c	Cec	C.r	Cer	E.s (ksf)	E.s (psf)
Granular Fill:	591	ft													
GWT:	577	ft	y.w	62.4	pcf	e.0	0.25	1	6600						
Clay I:	542	ft	y.c1	130	pcf	e.0	1	0.32	1	s'p.1 6000	psf	C.c.1 0.251	0.13	0.064	0.034
Clay II:	532	ft	y.c2	130	pcf	e.0	1	0.32	1	s'p.2 8200	psf	C.c.2 0.44	0.22	0.07	0.035
Clay III:	517	ft	y.c3	130	pcf	e.0	1.2	0.41	1	s'p.3 8200	psf	C.c.3 0.409	0.19	0.09	0.041
Bot. Clay III:	492	ft	y.gr.f	130	pcf										
Sediment:	575	ft	y.sed	80	pcf										
Top of Wall	591	ft													


Immediately after Dredging on Active Side

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Vertical Effective Stress @ Midpoint (psf)	in situ OCR (-)
577	Water	-	-	-	-	0	0	0	0	-
559.5	Water	577	542	35	17.5	17.5	1092	1092	0	-
537	Clay I	542	532	10	5	40	2834	2496	338	17.8
524.5	Clay II	532	517	15	7.5	52.5	4459	3276	1183	6.9
504.5	Clay III	517	492	25	12.5	72.5	7059	4524	2535	3.2



Immediately after placement of Full Height of Granular Fill

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Full Ht after Immediate Settlement (ft)	H0 after Immediate Settlement (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Vertical Effective Stress @ Midpoint (psf)	Delta Vertical Stress (psf)	in situ OCR (-)	Depth from Base of Applied Load to Midpoint (ft)	Primary Consolidation (in)
591	-	-	-	-	-	-	-	0	0	0	0	0	-	-	-
584	Gr. Fill (unsat.)	591	577	14	7	-	-	0	910	0	910	-	-	-	-
559.5	Gr. Fill (sat.)	577	542	35	17.5	-	-	17.5	4095	1092	3003	-	-	-	-
537	Clay I	542	532	10	5	9.93	4.97	40	7020	2496	4524	4186	1.3	54	2.3
524.5	Clay II	532	517	15	7.5	14.83	7.42	52.5	8645	3276	5369	4186	1.5	66.5	2.0
504.5	Clay III	517	492	25	12.5	24.91	12.46	72.5	11245	4524	6721	4186	1.2	86.5	2.6
														Σ (in)	6.9



Immediately after placement of Limestone Stockpile Surcharge (X = 10FT)

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Full Ht after Immediate Settlement (ft)	H0 after Immediate Settlement (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Delta Vertical Stress (psf)	Vertical Effective Stress @ Midpoint (psf)	in situ OCR (-)	Depth from Base of Applied Load to Midpoint (ft)	Primary Consolidation (in)
591	-	-	-	-	-	-	-	0	0	0	0	-	-	-	-
584	Gr. Fill (unsat.)	591	577	14	7	-	-	0	910	0	-	-	-	-	-
559.5	Gr. Fill (sat.)	577	542	35	17.5	-	-	17.5	4095	1092	-	-	-	-	-
537	Clay I	542	532	9.93	4.97	9.72	4.86	40.0	7020	2496	13584	18108	0.33		0.4
524.5	Clay II	532	517	14.83	7.42	14.39	7.19	52.4	8645	3276	11139	16508	0.50		0.8
504.5	Clay III	517	492	24.91	12.46	24.74	12.37	72.2	11245	4524	8549	15270	0.54		0.9
														Σ (in)	2.1

Semi-Infinite Uniform Load			
Clay I	Clay II	Clay III	
X 10	10	10	
Z 54	66.5	86.5	
R 54.92	66.9	87	
B 10.49	8.6	6.6	

Case III - X =35FT
Evaluate vertical effective stress immediately
after placement of Limestone Stockpile


L.stone: 4000 psf Poisson's Ratio: 0.49

Width, B (ft): 75

Layer Elevations		Unit Weights		Initial Void Ratio		u1	u0	P'c (psf)		C.c	Cec	C.r	Cer	E.s (ksf)	E.s (psf)
Granular Fill:	591	ft													
GWT:	577	ft	y.w	62.4	pcf	e.0	0.25	1	6600	psf					
Clay I:	542	ft	y.c1	130	pcf	e.0	1	0.32	1	s'p.1 6000	psf	C.c.1 0.251	0.13	0.064 0.034	1200 1200000
Clay II:	532	ft	y.c2	130	pcf	e.0	1	0.32	1	s'p.2 8200	psf	C.c.2 0.44	0.22	0.07 0.035	600 600000
Clay III:	517	ft	y.c3	130	pcf	e.0	1.2	0.41	1	s'p.3 8200	psf	C.c.3 0.409	0.19	0.09 0.041	1500 1500000
Bot. Clay III:	492	ft	y.gr.f	130	pcf										
Sediment:	575	ft	y.sed	80	pcf										
Top of Wall	591	ft													


Immediately after Dredging on Active Side

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Vertical Effective Stress @ Midpoint (psf)	in situ OCR (-)
577	Water	-	-	-	-	0	0	0	0	-
559.5	Water	577	542	35	17.5	17.5	1092	1092	0	-
537	Clay I	542	532	10	5	40	2834	2496	338	17.8
524.5	Clay II	532	517	15	7.5	52.5	4459	3276	1183	6.9
504.5	Clay III	517	492	25	12.5	72.5	7059	4524	2535	3.2



Immediately after placement of Full Height of Granular Fill

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Full Ht after Immediate Settlement (ft)	H0 after Immediate Settlement (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Vertical Effective Stress @ Midpoint (psf)	Delta Vertical Stress (psf)	in situ OCR (-)	Depth from Base of Applied Load to Midpoint (ft)	Primary Consolidation (in)
591	-	-	-	-	-	-	-	0	0	0	0	0	-	-	-
584	Gr. Fill (unsat.)	591	577	14	7	-	-	0	910	0	910	-	-	-	-
559.5	Gr. Fill (sat.)	577	542	35	17.5	-	-	17.5	4095	1092	3003	-	-	-	-
537	Clay I	542	532	10	5	9.93	4.97	40	7020	2496	4524	4186	1.326	54	2.3
524.5	Clay II	532	517	15	7.5	14.83	7.42	52.5	8645	3276	5369	4186	1.527	66.5	2.0
504.5	Clay III	517	492	25	12.5	24.91	12.46	72.5	11245	4524	6721	4186	1.220	86.5	2.6
														Σ (in)	6.9



Immediately after placement of Limestone Stockpile Surcharge (X = 35FT)

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.0 (ft)	Full Ht after Immediate Settlement (ft)	H0 after Immediate Settlement (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Delta Vertical Stress (psf)	Vertical Effective Stress @ Midpoint (psf)	in situ OCR (-)	Depth from Base of Applied Load to Midpoint (ft)	Primary Consolidation (in)
591	-	-	-	-	-	-	-	0	0	0	0	-	-	-	-
584	Gr. Fill (unsat.)	591	577	14	7	-	-	0	910	0	-	-	-	-	-
559.5	Gr. Fill (sat.)	577	542	35	17.5	-	-	17.5	4095	1092	-	-	-	-	-
537	Clay I	542	532	9.93	4.97	9.27	4.64	40.0	7020	2496	42470	46994	0.128		0.6
524.5	Clay II	532	517	14.83	7.42	13.40	6.70	52.4	8645	3276	35920	41289	0.199		1.3
504.5	Clay III	517	492	24.91	12.46	24.33	12.17	72.2	11245	4524	28454	35175	0.233		1.7
														Σ (in)	3.5

Semi-Infinite Uniform Load
X Clay I Clay II Clay III
35 35 35
Z 54 66.5 86.5
R 64.4 75.2 93.3
B 32.9 27.8 22


Case III - X =60FT
Evaluate vertical effective stress immediately after placement of Limestone Stockpile

after placement of Limestone Stockpile	L.stone:	4000	psf	Poisson's Ratio:	0.49
--	----------	------	-----	------------------	------

Layer Elevations		Unit Weights			Initial Void Ratio			u1	u0	P'c (psf)		C.c	Cec	C.r	Cer	E.s (ksf)	E.s (psf)
Granular Fill:	591	ft															
GWT:	577	ft	y.w	62.4	pcf					6600							
Clay I:	542	ft	y.c.1	130	pcf	e.0	0.9	0.25	1	s'p.1	6000						
Clay II:	532	ft	y.c.2	130	pcf	e.0	1	0.32	1	s'p.2	8200	psf					
Clay III:	517	ft	y.c.3	130	pcf	e.0	1.2	0.41	1	s'p.3	8200	psf					
Bot. Clay III:	492	ft	y.gr.f	130	pcf												
Sediment:	575	ft	y.sed	80	pcf												
Top of Wall	591	ft															
Stress (psf)																	


Immediately after Dredging on Active Side

Elevation @ Midpoint (ft)	Layer	Top of Layer (El - ft)	Bottom of Layer (El - ft)	Full Ht (ft)	H.O (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint	Vertical Effective Stress @ Midpoint (psf)	In situ OCR (-)
577	Water	-	-	-	-	0	0	0	0	-
559.5	Water	577	542	35	17.5	17.5	1092	1092	0	-
537	Clay I	542	532	10	5	40	2834	2496	338	17.8
524.5	Clay II	532	517	15	7.5	52.5	4459	3276	1183	6.9
504.5	Clay III	517	492	25	12.5	72.5	7059	4524	2535	3.2



Immediately after placement of Full Height of Granular Fill

Elevation @ Midpoint (ft)	Layer	Top of Layer (EI - ft)	Bottom of Layer (EI - ft)	Full Ht (ft)	H.O. (ft)	Full Ht after Immediate Settlement (ft)	H0 after Immediate Settlement (ft)	Ht of Pore Water @ Midpoint (ft)	Total Vertical Stress @ Midpoint (psf)	Pore Pressure @ Midpoint (psf)	Vertical Effective Stress @ Midpoint (psf)	Delta Vertical Stress (psf)	In situ OCR (-)	Depth from Base of Applied Load to Midpoint (ft)	Primary Consolidation (in)
591	-	-	-	-	-	-	-	0	0	0	0	0	-	-	-
584	Gr. Fill (unsat.)	591	577	14	7	-	-	0	910	0	910	-	-	-	-
559.5	Gr. Fill (sat.)	577	542	35	17.5	-	-	17.5	4095	1092	3003	-	-	-	-
537	Clay I	542	532	10	5	9.93	4.97	40	7020	2496	4524	4186	1.326	54	2.3
524.5	Clay II	532	517	15	7.5	14.83	7.42	52.5	8645	3276	5369	4186	1.527	66.5	2.0
504.5	Clay III	517	492	25	12.5	24.91	12.46	72.5	11245	4524	6721	4186	1.220	86.5	2.6
Σ(in)															6.9



Immediately after placement of Limestone Stockpile Surcharge (X = 60FT)

[illegible]

Calc:

- Immediate Settlement
- Consolidation of Clay Layers

	Semi-Infinite Uniform Load		
	Clay I	Clay II	Clay III
X	60	60	60
Z	54	66.5	86.5
R	80.7	89.6	105.3
B	48	42.1	34.8

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
APPENDIX F: SEISMIC EVALUATION						

		CALCULATION COVER PAGE		Page	
				Rev. No.	
Client		BROWN COUNTY WI			
Project		Port Property Development			
Project No.	2201593	Document No.	N/A		
Calc. Title	Port Property Development - Dock Wall Design				
Seismic Evaluation The purpose of this analysis was to perform a comparative analysis of the lateral loads imparted on the dockwall due to surcharge live loads and seismic activity. The Green Bay area is a low seismicity zone with mapped ground accelerations of less than 5%g. Our evaluation was based on guidance from UFC 4-152-01 Design of Piers and Wharves which provides a more appropriate means to evaluate marine terminal facilities. Ground accelerations were based on the mapped values in ASCE7-10 and amplified for Site Class E soils (soft clay). We assumed 100% of this design acceleration for this evaluation (ASCE7-10 permits the design acceleration to be 2/3 of the modified ground acceleration). Lateral earth pressures during a seismic event were based on the theory developed by Mononobe-Okabe. These equations were modified for partial submergence of the fill materials behind the wall. Based on UFC 4-152-01 Design of Piers and Wharves ASD load combinations, static load cases will govern the total lateral load on the dockwall. Therefore, only static load conditions have been included as part of the dockwall analyses.					
Signature Block & Record of Revisions					
Rev.	Description	Code	Pages/Sections	Signature	Date
0	For Internal Review	P	All	A. Gradeski	10/18/24
		C	All		
		A	All		
<i>Codes: P = Prepared; C = Checked; A = Approved</i>					

	Client	Brown County Wisconsin			Page																																																	
	Project	Port Property Development			Pg. Rev.																																																	
	By	A. Gradeski	Chk.		App.																																																	
	Date	12/13/2024	Date		Date																																																	
Project No.	2201593		Document No.																																																			
Subject	Port Property Development - Dock Wall Design																																																					
Seismic Loading References - GEI Memo - Seismic Design for Gravity Retaining Walls - UFC 4-152-01: Design Piers and Wharves - ASCE7-10 Minimum Design Loads for Buildings and Other Structures Input Data <table> <tr> <td>Top of Wall Elevation:</td> <td>TOW := 591.0ft</td> <td></td> </tr> <tr> <td>Bottom of Wall Elevation:</td> <td>BOW := 540ft</td> <td><i>Tip of sheet piles assumed</i></td> </tr> <tr> <td>Average Angle of Internal Friction:</td> <td>$\phi := 24^\circ$</td> <td><i>Minimum value for all clay layers assumed</i></td> </tr> <tr> <td>Dry Soil Thickness:</td> <td>$h_{dry} := TOW - 576.0ft = 15.00 \cdot ft$</td> <td></td> </tr> <tr> <td>Submerged Soil Thickness:</td> <td>$h_{sub} := 576.0ft - BOW = 36.00 \cdot ft$</td> <td></td> </tr> <tr> <td>Height of Backfill:</td> <td>$H := h_{dry} + h_{sub} = 51.00 \cdot ft$</td> <td></td> </tr> <tr> <td>Interface Friction Angle:</td> <td>$\delta := 0deg$</td> <td></td> </tr> <tr> <td>Unit Weight of Water:</td> <td>$\gamma_w := 62.4pcf \cdot g$</td> <td></td> </tr> <tr> <td>Unit Weight of Soil - Dry:</td> <td>$\gamma_{rf,dry} := 130pcf \cdot g$</td> <td></td> </tr> <tr> <td>Unit Weight of Soil - Submerged:</td> <td>$\gamma_{rf,sub} := 130pcf \cdot g$</td> <td></td> </tr> <tr> <td>Unit Weight of Soil - Bouyant:</td> <td>$\gamma_{rf,buy} := \gamma_{rf,sub} - \gamma_w = 67.60 \cdot pcf \cdot g$</td> <td></td> </tr> <tr> <td>Peak Ground Acceleration:</td> <td>$PGA_{Des} := 0.061$</td> <td><i>ASCE7-10 Site Class E</i></td> </tr> <tr> <td>Horizontal Seismic Coefficient:</td> <td>$k_h := PGA_{Des} = 0.061$</td> <td><i>Conservatively use 100%g</i></td> </tr> <tr> <td>Vertical Seismic Coefficient:</td> <td>$k_v := 0$</td> <td></td> </tr> <tr> <td>Back Face Batter:</td> <td>$\theta := 0^\circ$</td> <td></td> </tr> <tr> <td>Backslope Angle:</td> <td>$\beta := 0deg$</td> <td></td> </tr> </table>							Top of Wall Elevation:	TOW := 591.0ft		Bottom of Wall Elevation:	BOW := 540ft	<i>Tip of sheet piles assumed</i>	Average Angle of Internal Friction:	$\phi := 24^\circ$	<i>Minimum value for all clay layers assumed</i>	Dry Soil Thickness:	$h_{dry} := TOW - 576.0ft = 15.00 \cdot ft$		Submerged Soil Thickness:	$h_{sub} := 576.0ft - BOW = 36.00 \cdot ft$		Height of Backfill:	$H := h_{dry} + h_{sub} = 51.00 \cdot ft$		Interface Friction Angle:	$\delta := 0deg$		Unit Weight of Water:	$\gamma_w := 62.4pcf \cdot g$		Unit Weight of Soil - Dry:	$\gamma_{rf,dry} := 130pcf \cdot g$		Unit Weight of Soil - Submerged:	$\gamma_{rf,sub} := 130pcf \cdot g$		Unit Weight of Soil - Bouyant:	$\gamma_{rf,buy} := \gamma_{rf,sub} - \gamma_w = 67.60 \cdot pcf \cdot g$		Peak Ground Acceleration:	$PGA_{Des} := 0.061$	<i>ASCE7-10 Site Class E</i>	Horizontal Seismic Coefficient:	$k_h := PGA_{Des} = 0.061$	<i>Conservatively use 100%g</i>	Vertical Seismic Coefficient:	$k_v := 0$		Back Face Batter:	$\theta := 0^\circ$		Backslope Angle:	$\beta := 0deg$	
Top of Wall Elevation:	TOW := 591.0ft																																																					
Bottom of Wall Elevation:	BOW := 540ft	<i>Tip of sheet piles assumed</i>																																																				
Average Angle of Internal Friction:	$\phi := 24^\circ$	<i>Minimum value for all clay layers assumed</i>																																																				
Dry Soil Thickness:	$h_{dry} := TOW - 576.0ft = 15.00 \cdot ft$																																																					
Submerged Soil Thickness:	$h_{sub} := 576.0ft - BOW = 36.00 \cdot ft$																																																					
Height of Backfill:	$H := h_{dry} + h_{sub} = 51.00 \cdot ft$																																																					
Interface Friction Angle:	$\delta := 0deg$																																																					
Unit Weight of Water:	$\gamma_w := 62.4pcf \cdot g$																																																					
Unit Weight of Soil - Dry:	$\gamma_{rf,dry} := 130pcf \cdot g$																																																					
Unit Weight of Soil - Submerged:	$\gamma_{rf,sub} := 130pcf \cdot g$																																																					
Unit Weight of Soil - Bouyant:	$\gamma_{rf,buy} := \gamma_{rf,sub} - \gamma_w = 67.60 \cdot pcf \cdot g$																																																					
Peak Ground Acceleration:	$PGA_{Des} := 0.061$	<i>ASCE7-10 Site Class E</i>																																																				
Horizontal Seismic Coefficient:	$k_h := PGA_{Des} = 0.061$	<i>Conservatively use 100%g</i>																																																				
Vertical Seismic Coefficient:	$k_v := 0$																																																					
Back Face Batter:	$\theta := 0^\circ$																																																					
Backslope Angle:	$\beta := 0deg$																																																					

GEI



Client	Brown County Wisconsin			Page	
Project	Port Property Development			Pg. Rev.	
By	A. Gradeski	Chk.		App.	
Date	12/13/2024	Date		Date	


Project No.	2201593	Document No.	
Subject	Port Property Development - Dock Wall Design		

Weighted Average of Effective Unit Weight:
$$\gamma'_{avg} := \gamma_{rf,dry} \cdot \left(1 - \frac{h_{sub}^2}{H^2} \right) + \gamma_{rf,buy} \cdot \left(\frac{h_{sub}^2}{H^2} \right)$$

Refer to GEI Memo "Seismic Design for Gravity Retaining Walls"

$$\gamma'_{avg} = 98.91 \cdot \text{pcf} \cdot g$$

Design Horizontal Seismic Coefficient:
$$k_{h,des} := \frac{\gamma_{rf,dry}}{\gamma'_{avg}} \cdot k_h = 0.080$$



$$K_A = \frac{\cos^2(\phi - \theta)}{\cos^2 \theta \cos(\theta + \delta) \left[1 + \frac{\sin(\phi + \delta) \sin(\phi - \beta)}{\cos(\theta + \delta) \cos(\theta - \beta)} \right]^2}$$

Calculation of Active Earth Pressure using Coulomb Theory

Earth Pressure Coefficient:
$$K_a := \frac{(\cos(\phi - \theta))^2}{(\cos(\theta))^2 \cdot \cos(\theta + \delta) \cdot \left(1 + \sqrt{\frac{\sin(\phi + \delta) \cdot \sin(\phi - \beta)}{\cos(\theta + \delta) \cdot \cos(\theta - \beta)}} \right)^2}$$

$$K_a = 0.422$$

	Client	Brown County Wisconsin			Page	
	Project	Port Property Development			Pg. Rev.	
	By	A. Gradeski	Chk.		App.	
	Date	12/13/2024	Date		Date	
Project No.	2201593	Document No.				
Subject	Port Property Development - Dock Wall Design					
Static Soil Pressures: <i>Effective Vertical Earth Pressures...</i> At Grade: $\sigma'_{v1} := 0 \text{ psf}$ At Waterline: $\sigma'_{v2} := h_{\text{dry}} \cdot \gamma_{\text{rf,dry}} = 1950.0 \cdot \text{psf}$ At Wall Base: $\sigma'_{v3} := \sigma'_{v2} + h_{\text{sub}} \cdot \gamma_{\text{rf,buy}} = 4383.6 \cdot \text{psf}$ <i>Lateral Earth Pressures...</i> At Grade: $\sigma'_{h1} := \sigma'_{v1} \cdot K_a = 0.0$ At Waterline: $\sigma'_{h2} := \sigma'_{v2} \cdot K_a = 822.4 \cdot \text{psf}$ At Wall Base: $\sigma'_{h3} := \sigma'_{v3} \cdot K_a = 1848.7 \cdot \text{psf}$ Static Dry Soil Resultant Load: $P_1 := 0.5 \cdot \sigma'_{h2} \cdot h_{\text{dry}}$ $P_1 = 6.2 \cdot \text{klf}$ Static Submerged Resultant Load: $P_2 := 0.5 \cdot (\sigma'_{h2} + \sigma'_{h3}) \cdot h_{\text{sub}}$ $P_2 = 48.1 \cdot \text{klf}$ Active Force (inclined at an angle of δ from the face): $P_a := P_1 + P_2$ $P_a = 54.2 \cdot \text{klf}$ Normal Force (normal to back face of wall): $P_{a_n} := P_a \cdot \cos(\delta)$ $P_{a_n} = 54.2 \cdot \text{klf}$ Tangential Force (tangential to back face of wall): $P_{a_t} := P_a \cdot \sin(\delta)$ $P_{a_t} = 0.0 \cdot \text{klf}$ Horizontal Component: $P_{a_h} := P_a \cdot \cos(\theta + \delta)$ $P_{a_h} = 54.2 \cdot \text{klf}$ Vertical Component: $P_{a_v} := P_a \cdot \sin(\theta + \delta)$ $P_{a_v} = 0.0 \cdot \text{klf}$						

	Client	Brown County Wisconsin			Page	
	Project	Port Property Development			Pg. Rev.	
	By	A. Gradeski	Chk.		App.	
	Date	12/13/2024	Date		Date	
Project No.	2201593	Document No.				
Subject	Port Property Development - Dock Wall Design					

Calculation of Seismic Earth Pressure using Mononobe-Okabe Equation

Angle of Resultant Acceleration (from vertical): $\Psi := \text{atan}\left(\frac{k_{h,des}}{1 - k_v}\right) \quad \Psi = 4.58^\circ$

Earth Pressure Coefficient: $K_{ae} := \frac{(\cos(\phi - \Psi - \theta))^2}{\cos(\Psi) \cdot (\cos(\theta))^2 \cdot \cos(\theta + \delta + \Psi) \cdot \left(1 + \sqrt{\frac{\sin(\phi + \delta) \cdot \sin(\phi - \Psi - \beta)}{\cos(\theta + \delta + \Psi) \cdot \cos(\beta - \theta)}}\right)^2}$

$K_{ae} = 0.478$

Total Force (Active + Earthquake)

Total Force (inclined at an angle of δ from the face): $P_{ae} := \frac{1}{2} K_{ae} \cdot \gamma'_{avg} \cdot H^2 \cdot (1 - k_v) \quad P_{ae} = 61.5 \cdot \text{klf}$

Normal Force (normal to back face of wall): $P_{ae_n} := P_{ae} \cdot \cos(\delta) \quad P_{ae_n} = 61.5 \cdot \text{klf}$

Tangential Force (tangential to back face of wall): $P_{ae_t} := P_{ae} \cdot \sin(\delta) \quad P_{ae_t} = 0.0 \cdot \text{klf}$

Horizontal Component: $P_{ae_h} := P_{ae} \cdot \cos(\theta + \delta) \quad P_{ae_h} = 61.5 \cdot \text{klf}$

Vertical Component: $P_{ae_v} := P_{ae} \cdot \sin(\theta + \delta) \quad P_{ae_v} = 0.0 \cdot \text{klf}$

Seismic Increment

Seismic Force (inclined at an angle of δ from the face): $P_e := P_{ae} - P_a \quad P_e = 7.3 \cdot \text{klf}$

Normal Force (normal to back face of wall): $P_{e_n} := P_{ae_n} - P_{a_n} \quad P_{e_n} = 7.3 \cdot \text{klf}$

Tangential Force (tangential to back face of wall): $P_{e_t} := P_{ae_t} - P_{a_t} \quad P_{e_t} = 0.0 \cdot \text{klf}$

Horizontal Component: $P_{e_h} := P_{ae_h} - P_{a_h} \quad P_{e_h} = 7.3 \cdot \text{klf}$

Vertical Component: $P_{e_v} := P_{ae_v} - P_{a_v} \quad P_{e_v} = 0.0 \cdot \text{klf}$

Resultant Location: $y := 0.6 \cdot H \quad y = 30.60 \cdot \text{ft}$



Consultants

Client	Brown County Wisconsin			Page	
Project	Port Property Development			Pg. Rev.	
By	A. Gradeski	Chk.		App.	
Date	12/13/2024	Date		Date	

Project No.	2201593	Document No.	
Subject	Port Property Development - Dock Wall Design		

Calculation of Active Load due to 500 psf surcharge load

$$P_q := K_a \cdot 500 \text{ psf} \cdot H = 10.75 \cdot \text{klf}$$

Load Combination Analysis

The load combinations provided in UFC 4-152-01 are used for this analysis in lieu of those presented in ASCE7-10. This load combinations are considered more appropriate for a marine facility and recognize all the loads which could be expected at a marine terminal (whereas ASCE7 does not)

Table 3-8 Load Combinations - Allowable Stress Design (ASD)

Load	S0	S1	S2	S3	S4	S5	S6	S7	S8	S9
D ^a	1.0	1.0	1.0	1.0	1.0	1.0	1+k'	1-k'	1.0	1.0
(L _c +I) L _u	-	1.0	-	1.0	-	1.0	0.1	-	1.0	0.75
B	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0.6	1.0	1.0
Be	-	-	1.0	-	-	-	-	-	-	-
C	-	-	1.0	1.0	1.0	1.0	-	-	1.0	1.0
H ^d	-	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Eq	-	-	-	-	-	-	0.7	0.7	-	-
W	-	-	-	-	0.6	-	-	-	-	0.6
M	-	-	-	-	-	1.0	-	-	-	-
R+S+T	-	-	-	1.0	-	-	-	-	-	-
Ice	-	-	-	0.2	-	-	-	-	0.7	0.7

Notes:

- ^a 0.9 (0.6 ASD) for checking members for minimum axial load and maximum moment.
- ^b 1.3 for the maximum outrigger float load from a truck crane.
- ^c Accidental Berthing: 1.2 support structure, 1.0 fender system components.
- ^d Where the effect of H resists the primary variable load effect, a load factor of 0.9 (0.6 for ASD) shall be included with H where H is permanent and H shall be set to zero for all other conditions.

Combination S1: $S_1 := 1.0 \cdot P_{a_h} = 54.2 \text{ klf}$

Combination S3: $S_3 := 1.0 \cdot P_{a_h} + 1.0 P_q = 65.0 \text{ klf}$

Combination S6: $S_6 := 1.0 \cdot P_{a_h} + 0.1 P_q + 0.7 \cdot P_{e_h} = 60.4 \text{ klf}$

Combination S7: $S_7 := 1.0 \cdot P_{a_h} + 0.7 \cdot P_{e_h} = 59.3 \text{ klf}$

Lateral load on the dockwall is governed by the static load combinations (S1 and S3). Additionally note that the lateral load due the 500 PSF surcharge load is nearly 50% greater than lateral seismic load. Only static load cases/combinations will be considered for design of the dockwall.


GEI



Client	Brown County Wisconsin			Page	
Project	Port Property Development			Pg. Rev.	
By	A. Gradeski	Chk.		App.	
Date	12/13/2024	Date		Date	

Project No.	2201593	Document No.	
Subject	Port Property Development - Dock Wall Design		

Calculation of weighted average γ for partial submergence:



$$A_{tot} = \frac{1}{2}(H)(H \tan \theta) = \frac{1}{2} H^2 \tan \theta$$

$$A_{sub} = \frac{1}{2}(H_w)(H_w \tan \theta) = \frac{1}{2} H_w^2 \tan \theta$$

$$A_{dry} = \frac{1}{2} H^2 \tan \theta - \frac{1}{2} H_w^2 \tan \theta = \frac{1}{2} (H^2 - H_w^2) \tan \theta$$

$$\frac{A_{dry}}{A_{tot}} = \frac{\frac{1}{2} (H^2 - H_w^2) \tan \theta}{\frac{1}{2} H^2 \tan \theta} = 1 - \frac{H_w^2}{H^2}$$

$$\frac{A_{sub}}{A_{tot}} = \frac{\frac{1}{2} H_w^2 \tan \theta}{\frac{1}{2} H^2 \tan \theta} = \frac{H_w^2}{H^2}$$

$$\gamma'_{b-av} = \gamma_d \left(1 - \frac{H_w^2}{H^2}\right) + \gamma_b \left(\frac{H_w^2}{H^2}\right) = \gamma_d \left(1 - \frac{12.5^2}{16^2}\right) + \gamma_b \left(\frac{12.5^2}{16^2}\right)$$

$$= 0.390 \gamma_d + 0.610 \gamma_b$$

$$= 0.39(18.0) + 0.61(10.5)$$

$$= 13.43$$

$$\gamma'_{t-av} = 0.39(\gamma_d) + 0.61(\gamma_{sat}) = 0.39(18.0) + 0.61(20.5) = 19.53$$

ASCE Hazards Report

Address:

No Address at This Location

Standard:

ASCE/SEI 7-10

Risk Category: II

Soil Class:

E - Soft Clay Soil

Latitude:



44.53877

Longitude:

-88.007404

Elevation:

583.9394583546972 ft
(NAVD 88)



Wind

Results:

Wind Speed	115 Vmph
10-year MRI	75 Vmph
25-year MRI	84 Vmph
50-year MRI	90 Vmph
100-year MRI	96 Vmph

Data Source:

ASCE/SEI 7-10, Fig. 26.5-1A and Figs. CC-1–CC-4, and Section 26.5.2,
incorporating errata of March 12, 2014

Date Accessed:

Fri Dec 13 2024



Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is not in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2.

Site Soil Class: E - Soft Clay Soil

Results:

S_S :	0.052	S_{D1} :	0.078
S_1 :	0.033	T_L :	12
F_a :	2.5	PGA :	0.024
F_v :	3.5	PGA_M :	0.061
S_{MS} :	0.131	F_{PGA} :	2.5
S_{M1} :	0.117	I_e :	1
S_{DS} :	0.087		



Data Accessed: Fri Dec 13 2024

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

Ice

Results:

Ice Thickness: 0.50 in.

Concurrent Temperature: -5 F

Gust Speed 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Fri Dec 13 2024

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Snow

Results:

Ground Snow Load, p_g : 40 lb/ft²

Mapped Elevation: 583.9 ft

Data Source: ASCE/SEI 7-10, Fig. 7-1.

Date Accessed: Fri Dec 13 2024

Values provided are ground snow loads. In areas designated "case study required," extreme local variations in ground snow loads preclude mapping at this scale. Site-specific case studies are required to establish ground snow loads at elevations not covered.

Snow load values are mapped to a 0.5 mile resolution. This resolution can create a mismatch between the mapped elevation and the site-specific elevation in topographically complex areas. Engineers should consult the local authority having jurisdiction in locations where the reported 'elevation' and 'mapped elevation' differ significantly from each other.

Results:

Flood Zone Categorization: X (unshaded)

Base Flood Elevation: Refer to map for local elevations and interpolate according to the Authority Having Jurisdiction.

Data Source: FEMA National Flood Hazard Layer - Effective Flood Hazard Layer for US, where modernized (<https://msc.fema.gov/portal/search>)

Date Accessed: Fri Dec 13 2024

FIRM Panel: If available, download FIRM panel [here](#)

Insurance Study Note: Download FEMA Flood Insurance Study for this area [here](#)



The ASCE Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.


ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE Hazard Tool.

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
ATTACHMENT 1: NUCOR SKYLINE STEEL CUTSHEET						

TECHNICAL PRODUCT MANUAL


2024 EDITION



NUCOR®
SKYLINE

PIPE COMBINED WALLS

Pipe-Z with E22 Connector System*



Pipe Diameter	Wall Thickness	Intermediary Sheet Pile	Sheet Pile Connector	System Width	Moment of Inertia	Section Modulus	Weight (NZ Length / Pipe Length)			Cross Sectional Area
							100%	80%	60%	
in mm	in mm			in mm	in ⁴ /ft cm ⁴ /m	in ³ /ft cm ³ /m	lb/ft ² kg/m ²	lb/ft ² kg/m ²	lb/ft ² kg/m ²	in ² /ft cm ² /m
36 914	0.375 9.5	NZ 14	E22	99.19 2519.4	911 124341	50.6 2720	32.2 1575	29.3 142.8	26.3 128.2	8.99 190.3
36 914	0.438 11.1	NZ 19	E22	93.68 2379.4	1158 158082	64.3 3458	37.2 181.5	34.0 166.1	30.8 150.6	10.43 220.7
42 1067	0.500 12.7	NZ 14	E22	105.19 2671.8	1700 232167	81.0 4353	39.4 192.5	36.6 178.7	33.8 164.9	11.13 235.5
42 1067	0.563 14.3	NZ 19	E22	99.68 2531.8	2051 280023	97.6 5250	44.9 219.3	41.9 204.8	39.0 190.2	12.73 269.5
48 1219	0.563 14.3	NZ 14	E22	111.19 2824.2	2641 360648	110.0 5916	44.2 215.7	41.5 202.6	38.8 189.6	12.54 265.5
48 1219	0.625 15.875	NZ 19	E22	105.68 2684.2	3112 424898	129.6 6970	50.0 244.1	47.2 230.4	44.4 216.7	14.25 301.6
54 1372	0.625 15.9	NZ 19	E22	111.68 2836.6	4150 566773	153.7 8265	51.6 252.0	49.0 239.0	46.3 226.1	14.75 312.2
54 1372	0.688 17.5	NZ 26	E22	111.68 2836.6	4607 629086	170.6 9173	58.9 287.4	55.5 271.1	52.2 254.7	16.86 356.9
60 1524	0.688 17.5	NZ 19	E22	117.68 2989.0	5882 803218	196.1 10541	57.1 278.8	54.6 266.5	52.1 254.2	16.38 346.8
60 1524	0.750 19.1	NZ 26	E22	117.68 2989.0	6445 880060	214.8 11550	64.3 314.1	61.1 298.6	58.0 283.1	18.49 391.3
66 1676	0.750 19.1	NZ 19	E22	123.68 3141.4	8066 1101454	244.4 13141	62.8 306.5	60.4 294.7	58.0 283.0	18.07 382.4
66 1676	0.813 20.7	NZ 26	E22	123.68 3141.4	8769 1197480	265.7 14287	70.1 342.2	67.1 327.4	64.0 312.7	20.20 427.6
72 1829	0.813 20.7	NZ 26	E22	129.68 3293.8	10838 1479947	301.0 16185	71.7 349.9	68.8 335.8	65.9 321.8	20.68 437.8
72 1829	0.875 22.2	NZ 26	E22	129.68 3293.8	11621 1586893	322.8 17355	76.0 371.0	73.1 356.9	70.2 342.8	21.95 464.6
78 1981	0.875 22.2	NZ 26	E22	135.68 3446.2	14114 1927403	361.9 19457	77.6 378.8	74.8 365.4	72.1 351.9	22.44 475.0
78 1981	0.938 23.8	NZ 26	E22	135.68 3446.2	15082 2059540	386.7 20791	82.1 401.0	79.4 387.5	76.6 374.1	23.77 503.2
84 2134	0.938 23.8	NZ 26	E22	141.68 3598.6	18045 2464133	429.6 23099	83.7 408.9	81.1 396.0	78.5 383.1	24.26 513.6
84 2134	1.000 25.4	NZ 26	E22	141.68 3598.6	19184 2619754	456.8 24558	88.3 431.4	85.7 418.5	83.1 405.6	25.62 542.2

* Additional combinations are available upon request.

PIPE COMBINED WALLS

SPECIFICATIONS

Manufacturing Specifications	Yield Strength		PIPE	NZ, PZ, & WF
	ksi	MPa		
A252 Grade 3 (50 ksi)	50	345	✓	
A252 Grade 3 (60 ksi)	60	415	✓	

Steel Specifications	Yield Strength		PIPE	NZ, PZ, & WF
	ksi	MPa		
A572 Grade 60	60	415	✓	✓
A690	50	345	✓	✓

For a complete list of steel grades see page 46. For availability of other yield strengths please, contact Nucor Skyline.

DELIVERY CONDITIONS & TOLERANCES

SHEET PILE	ASTM A6	EN10248			
Mass	± 2.5%	± 5%			
Length	+ 5 in.	± 200 mm			
Height		± 7 mm			
Thickness		≤ 8.5 mm > 8.5 mm			
Width		± 2%			
Double Pile Width		± 3%			
Straightness		0.2% of the length			
Ends out of Square		2% of the width			

PIPE	A139	A252	A500	A1085	AWWA C200
Outside Diameter	± 1%	± 1%	± 0.75%	± 0.75%	+1/8" / -1/16"
Thickness	- 12.5%	- 12.5%	±10%	+10% / -5%	+10% [§]
Weight	+10% / -5%	+10% / -5%	±10%	+10% / -3.5%	+10% / -5%
Length	± 1/2"	± 1"	+3/4" / -1/4"	+3/4" / -1/4"	± 2"


**Different conditions and tolerances vary based on diameter, length, and project requirements. Please inquire for additional information.

§ Lowest of value of applicable ASTM tolerance, 0.01 inch, or 6% percent of the nominal thickness.


MAXIMUM ROLLED LENGTHS†

E22	59 ft.	18.0 m		
NZ & PZ	105 ft.	32.0 m		
	12" OD and Under		12.75" OD and Over	
Spiralweld / Rolled & Welded	90 ft.	27.4 m	115 ft.	31.1 m

† All sections are readily spliced for longer lengths.





SECTION	THICKNESS				Cross Sectional Area	WEIGHT		SECTION MODULUS			COATING AREA	
	Width (w)	Height (h)	Flange (tf)	Web (tw)		Single Pile	Wall Area	Elastic	Plastic	Moment of Inertia	Both Sides	Wall Surface
	in	in	in	in	in ² /ft	lb/ft	lb/ft ²	in ³ /ft	in ³ /ft	in ⁴ /ft	ft ² /ft of single	ft ² /ft ²
	mm	mm	mm	mm	cm ² /m	kg/m	kg/m ²	cm ³ /m	cm ³ /m	cm ⁴ /m	m ² /m	m ² /m ²
NZ 14	30.31	13.39	0.375	0.375	6.40	55	21.77	25.65	30.50	171.7	6.10	1.20
	770	340	9.5	9.5	135.4	81.26	106.30	1379	1640	23447	1.86	1.20
NZ 19	27.56	16.14	0.375	0.375	7.07	55	24.05	35.08	41.33	283.1	6.18	1.35
	700	410	9.5	9.5	149.6	81.85	117.40	1886	2222	38659	1.88	1.35
NZ 20	27.56	16.16	0.394	0.394	7.34	57	24.82	36.24	42.80	292.8	6.18	1.35
	700	411	10.0	10.0	155.4	85.37	122.00	1948	2301	39984	1.88	1.35
NZ 21	27.56	16.20	0.433	0.433	7.80	61	26.56	38.69	45.85	313.4	6.18	1.35
	700	412	11.0	11.0	165.2	90.78	129.70	2080	2465	42797	1.88	1.35
NZ 22	27.56	16.25	0.480	0.480	8.57	67	29.20	41.47	49.34	336.9	6.18	1.35
	700.0	413.0	12.20	12.20	181.4	99.71	142.44	2230	2653	46006	1.88	1.35
NZ 26	27.56	17.32	0.500	0.500	9.08	71	30.99	48.50	57.01	419.9	6.49	1.41
	700	440	12.7	12.7	192.2	105.66	151.30	2608	3065	57340	1.98	1.41
NZ 28	27.56	17.38	0.560	0.560	9.98	78	33.96	52.62	62.16	457.4	6.49	1.41
	700	441	14.2	14.2	211.2	116.08	165.82	2829	3342	62461	1.98	1.41
NZ 38	27.56	19.69	0.689	0.500	11.00	86	37.45	70.84	81.57	697.3	6.58	1.43
	700	500	17.5	12.7	232.9	127.99	182.83	3809	4386	95214	2.01	1.43
NZ 40	27.56	19.73	0.735	0.551	11.77	92	40.06	74.97	86.75	739.6	6.58	1.43
	700.0	501.0	18.70	14.00	249.1	136.91	195.59	4031	4664	100997	2.01	1.43
NZ 42	27.56	19.77	0.769	0.589	12.41	97	42.24	78.17	90.80	772.5	6.58	1.43
	700.0	502.0	19.50	15.0	262.7	144.36	206.23	4203	4881	105490	2.01	1.43



SECTION	THICKNESS				Cross Sectional Area	WEIGHT		SECTION MODULUS			COATING AREA	
	Width (w)	Height (h)	Flange (tf)	Web (tw)		Single Pile	Wall Area	Elastic	Plastic	Moment of Inertia	Both Sides	Wall Surface
	in	in	in	in	in ² /ft	lb/ft	lb/ft ²	in ³ /ft	in ³ /ft	in ⁴ /ft	ft ² /ft of single	ft ² /ft ²
	mm	mm	mm	mm	cm ² /m	kg/m	kg/m ²	cm ³ /m	cm ³ /m	cm ⁴ /m	m ² /m	m ² /m ²
PZ 22	22.00	9.0	0.375	0.375	6.47	40.3	22.0	18.1	21.79	84.38	4.48	1.22
	559	229	9.50	9.50	136.9	60.0	107.4	973	1171.4	11500	1.37	1.22
PZ 27	18.00	12.0	0.375	0.375	7.94	40.5	27.0	30.2	36.49	184.20	4.48	1.49
	457	305	9.50	9.50	168.1	60.3	131.8	1620	1961.9	25200	1.37	1.49
PZ 35	22.64	14.9	0.600	0.500	10.29	66.0	35.0	48.5	57.17	361.22	5.37	1.42
	575	378	15.21	12.67	217.8	98.2	170.9	2608	3073.5	49300	1.64	1.42
PZ 40	19.69	16.1	0.600	0.500	11.77	65.6	40.0	60.7	71.92	490.85	5.37	1.64
	500	409	15.21	12.67	249.1	97.6	195.3	3263	3866.7	67000	1.64	1.64

REINFORCING STEEL GRADE / COLD ROLLED FULLY THREADED BAR



Grade 80 ksi Yield Strength / 100 ksi Ultimate Strength									
Bar Designation	Nominal Diameter	Grade	Min. Net Area Thru Threads	Min. Ultimate Strength	Min. Yield Strength	Nominal Weight	Approx. Major Thread Diameter	Thread Orientation	Max. Length
	in mm		in ² mm ²	kip kN	kip kN	lbs/ft kg/m	in mm		ft m
#18	2 1/4 55	80	4.000 2581.0	400.0 1779	320.0 1423	13.60 20.2	2.438 62.0	Right Hand	60 18.3
#20	2 1/2 64	80	4.910 3168.0	491.0 2184	392.8 1747	16.69 24.8	2.750 70.0	Right Hand	60 18.3
#24	3 76	80	7.070 4561.0	707.0 3145	565.6 2516	24.10 35.9	3.250 82.6	Right Hand	60 18.3
#28	3 1/2 89	80	9.610 6200.0	961.0 4275	768.8 3420	32.70 48.7	3.750 95.3	Right Hand	60 18.3
#32	4 102	80	12.57 8107.0	1257.0 5590	1005.3 4472	42.75 63.6	4.125 104.8	Right Hand	40 12.2

Cold rolled threaded bars conform to the physical and chemical requirements of ASTM A615 Grade 80 ksi "Standard Specification for Deformed Carbon Steel Bars for Concrete Reinforcement".

Contact your sales representative for information on hot dip galvanized and epoxy coated bars.

Please note: As we continuously improve the design of our products, product details are subject to change.

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
ATTACHMENT 2: AISC, 14TH EDITION DENSITIES OF COMMON MATERIALS						

STEEL CONSTRUCTION



MANUAL

AMERICAN INSTITUTE
OF
STEEL CONSTRUCTION

FOURTEENTH EDITION

Substance	Weight lb per ft ³	Substance	Weight lb per ft ³
ASHLAR, MASONRY		River mud	90.0
Granite, syenite, gneiss	143 – 187	Soil	70.0
Limestone, marble	143 – 174	Stone riprap	65.0
Sandstone, bluestone	131 – 150		
MORTAR RUBBLE MASONRY		MINERALS	
Granite, syenite, gneiss	137 – 174	Asbestos	131 – 174
Limestone, marble	137 – 162	Barytes	280
Sandstone, bluestone	125 – 137	Basalt	168 – 199
DRY RUBBLE MASONRY		Bauxite	159
Granite, syenite, gneiss	118 – 143	Borax	106 – 112
Limestone, marble	118 – 131	Chalk	112 – 162
Sandstone, bluestone	112 – 118	Clay, marl	112 – 162
BRICK MASONRY		Dolomite	181
Pressed brick	137 – 143	Feldspar, orthoclase	156 – 162
Common brick	112 – 125	Gneiss, serpentine	150 – 168
Soft brick	93.5 – 106	Granite, syenite	156 – 193
CONCRETE MASONRY		Greenstone, trap	174 – 199
Cement, stone, sand	137 – 150	Gypsum, alabaster	143 – 174
Cement, slag, etc.	118 – 143	Hornblende	187
Cement, cinder, etc.	93.5 – 106	Limestone, marble	156 – 174
VARIOUS BUILDING MATERIALS		Magnesite	187
Ashes, cinders	40.0 – 45.0	Phosphate rock, apatite	199
Cement, portland, loose	90.0	Porphyry	162 – 181
Cement, portland, set	168 – 199	Pumice, natural	23.1 – 56.1
Lime, gypsum, loose	53.0 – 64.0	Quartz, flint	156 – 174
Mortar, set	87.2 – 118	Sandstone, bluestone	137 – 156
Slags, bank slag	67.0 – 72.0	Shale, slate	168 – 181
Slags, bank screenings	98 – 117	Soapstone, talc	162 – 174
Slags, machine slag	96.0		
Slag, slag sand	49.0 – 55.0	STONE, QUARRIED, PILED	
EARTH, ETC., EXCAVATED		Basalt, granite, gneiss	96.0
Clay, dry	63.0	Limestone, marble, quartz	95.0
Clay, damp, plastic	110	Sandstone	82.0
Clay and gravel, dry	100	Shale	92.0
Earth, dry, loose	76.0	Greenstone, hornblende	107
Earth, dry, packed	95.0	BITUMINOUS SUBSTANCES	
Earth, moist, loose	78.0	Asphaltum	68.5 – 93.5
Earth, moist, packed	96.0	Coal, anthracite	87.2 – 106
Earth, mud, flowing	108	Coal, bituminous	74.8 – 93.5
Earth, mud, packed	115	Coal, lignite	68.5 – 87.2
Riprap, limestone	80.0 – 85.0	Coal, peat, turf, dry	40.5 – 53
Riprap, sandstone	90.0	Coal, charcoal, pine	17.4 – 27.4
Riprap, shale	105	Coal, charcoal, oak	29.3 – 35.5
Sand, gravel, dry, loose	90.0 – 105	Coal, coke	62.3 – 87.2
Sand, gravel, dry, packed	100 – 120	Graphite	118 – 143
Sand, gravel, wet	118 – 120	Paraffine	54.2 – 56.7
EXCAVATIONS IN WATER		Petroleum	54.2
Sand or gravel	60.0	Petroleum, refined	49.2 – 51.1
Sand or gravel and clay	65.0	Petroleum, benzine	45.5 – 46.7
Clay	80.0	Petroleum, gasoline	41.1 – 43
		Pitch	66.7 – 71.6
		Tar, bituminous	74.8
		COAL AND COKE, PILED	
		Coal, anthracite	47.0 – 58.0
		Coal, bituminous, lignite	40.0 – 54.0

Substance	Weight lb per ft ³	Substance	Weight lb per ft ³
Coal, peat, turf	20.0 – 26.0	Starch	95.3
Coal charcoal	10.0 – 14.0	Sulphur	120 – 129
Coal coke	23.0 – 32.0	Wool	82.2
METALS, ALLOYS, ORES		TIMBER, U.S. SEASONED	
Aluminum, cast, hammered	159 – 171	Moisture content by weight:	
Brass, cast, rolled	523 – 542	Seasoned timber 15 to 20%	
Bronze, 7.9 to 14% Sn	461 – 554	Green timber up to 50%	
Bronze, aluminum	480	Ash, white, red	38.6 – 40.5
Copper, cast, rolled	548 – 561	Cedar, white, red	19.9 – 23.7
Copper ore, pyrites	255 – 268	Chestnut	41.1
Gold, cast, hammered	1200–1210	Cypress	29.9
Iron, cast, pig	449	Fir, Douglas spruce	31.8
Iron, wrought	473 – 492	Fir, eastern	24.9
Iron, speigel-eisen	467	Elm, white	44.9
Iron, ferro-silicon	417 – 455	Hemlock	26.2 – 32.4
Iron ore, hematite	324	Hickory	46.1 – 52.3
Iron ore, hematite in bank	160 – 180	Locust	45.5
Iron ore, hematite loose	130 – 160	Maple, hard	42.4
Iron ore, limonite	224 – 249	Maple, white	33.0
Iron ore, magnetite	305 – 324	Oak, chestnut	53.6
Iron slag	156 – 187	Oak, live	59.2
Lead	710	Oak, red, black	40.5
Lead ore, galena	455 – 473	Oak, white	46.1
Magnesium, alloys	108 – 114	Pine, Oregon	31.8
Manganese	449 – 498	Pine, red	29.9
Manganese ore, pyrolusite	231 – 287	Pine, white	25.5
Mercury	847	Pine, yellow, long-leaf	43.6
Monel Metal	548 – 561	Pine, yellow, short-leaf	38.0
Nickel	554 – 573	Poplar	29.9
Platinum, cast, hammered	1310 – 1340	Redwood, California	26.2
Silver, cast, hammered	648 – 668	Spruce, white, black	24.9 – 28.7
Steel, rolled	490	Walnut, black	38.0
Tin, cast, hammered	449 – 467	Walnut, white	25.5
Tin ore, cassiterite	399 – 436	VARIOUS LIQUIDS	
Zinc, cast, rolled	430 – 449	Alcohol, 100%	49.2
Zinc, ore, blende	243 – 262	Acids, muriatic 40%	74.8
		Acids, nitric 91%	93.5
VARIOUS SOLIDS		Acids, sulphuric 87%	112
Cereals, oats, bulk	32.0	Lye, soda 66%	106
Cereals, barley, bulk	39.0	Oils, vegetable	56.7 – 58.6
Cereals, corn, rye, bulk	48.0	Oils, mineral, lubricants	56.1 – 57.9
Cereals, wheat, bulk	48.0	Water, 4°C max. density	62.3
Hay and Straw, bales	20.0	Water, 100°C	59.7
Cotton, Flax, Hemp	91.6 – 93.5	Water, ice	54.8 – 57.3
Fats	56.1 – 60.4	Water, sea water	63.5 – 64.2
Flour, loose	24.9 – 31.2	GASES	
Flour, pressed	43.6 – 49.8	Air, 0°C 760 mm	0.0871
Glass, common	150 – 162	Ammonia	0.0478
Glass, plate or crown	153 – 169	Carbon dioxide	0.123
Glass, crystal	181 – 187	Carbon monoxide	0.078
Leather	53.6 – 63.5	Gas, illuminating	0.028–0.036
Paper	43.6 – 71.6	Gas, natural	0.038–0.039
Potatoes, piled	42.0	Hydrogen	0.00559
Rubber, caoutchouc	57.3 – 59.8	Nitrogen	0.0784
Rubber goods	62.3 – 125	Oxygen	0.0892
Salt, granulated, piled	48.0		
Saltpeter	67.0		

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
ATTACHMENT 3: WALLAP ANALYSIS INPUT PARAMETERS						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	E. Burton	Chk.		App.	
	Date	10/22/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Wallap Analysis - Inputs					
WALLAP ANALYSIS - INPUT PARAMETERS References adfad - Nucor Skyline Technical Product Manual (2024) - Waterfront Facilities Inspection and Assessment (ASCE, 2nd Edition) Structural Wall Inputs Yield Stress of Steel: $F_Y := 60\text{ksi}$ Modulus of Elasticity of Steel: $E_S := 29000\text{ksi}$ $E_S = 4176000000 \frac{\text{lb}}{\text{ft}^2}$ Dockwall: 54"x11/16" Pipes w/ NZ26 Steel Sheet Piles King Pile: King Pile Outside Diameter: $OD := 54\text{in}$ King Pile Wall Thickness: $t_W := 0.688\text{in}$ King Pile Inside Diameter: $ID := OD - 2 \cdot t_W = 52.62 \cdot \text{in}$ King Pile Spacing: $S_{KP} := 111.68\text{in} = 9.31 \cdot \text{ft}$ Elastic Section Modulus: $S_{X_KP} := \frac{\pi \cdot (OD^4 - ID^4)}{32 \cdot OD} = 1516.5 \cdot \text{in}^3$ Moment of Inertia: $I_X := \frac{\pi \cdot (OD^4 - ID^4)}{64} = 40945 \cdot \text{in}^4$ Per Foot Moment of Inertia $I_{KP} := I_X \div S_{KP}$ $I_{KP} = 0.21217 \cdot \frac{\text{ft}^4}{\text{ft}}$ $I_{KP} \cdot E_S = 8.86 \times 10^8 \text{ lb} \cdot \frac{\text{ft}^2}{\text{ft}}$ Composite Wall Section: Elastic Section Modulus: $S_{X_comb} := 170.6 \frac{\text{in}^3}{\text{ft}}$ Moment of Inertia: $I_{comb} := 4607 \frac{\text{in}^4}{\text{ft}}$ $I_{comb} = 0.22217 \cdot \frac{\text{ft}^4}{\text{ft}}$ <i>Note: Composite wall section properties are based on the composite wall properties provided in the 2024 Nucor Technical Product Manual (shown below).</i> $I_{comb} \cdot E_S = 927798611 \text{ lb} \cdot \frac{\text{ft}^2}{\text{ft}}$						

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	E. Burton	Chk.		App.	
	Date	10/22/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Wallap Analysis - Inputs					
Capacities: $M_{a_comb} := 0.6 \cdot S_{x_comb} \cdot F_y = 511.8 \cdot \text{kip} \cdot \frac{\text{ft}}{\text{ft}}$ $M_{a_KP} := 0.6 \cdot S_{x_KP} \cdot F_y \div S_{KP} = 488.8 \cdot \text{kip} \cdot \frac{\text{ft}}{\text{ft}}$ <u>Allowable Utility Considering Corrosion (ASCE Reports on Engineering Practice No. 130)</u> Design Life: $Des_l := 50\text{yr}$ Frontside Corrosion: $C_{fs} := 0.0006 \frac{\text{in}}{\text{yr}} \cdot Des_l = 0.03 \text{ in}$ <i>Common Fresh Water</i> Frontside Corrosion: $C_{is} := \frac{1}{2} \cdot 0.0005 \frac{\text{in}}{\text{yr}} \cdot Des_l = 0.0125 \text{ in}$ <i>Undisturbed Nat'l Soils</i> $OD_{corr} := OD - 2(C_{fs}) = 53.94 \text{ in}$ $ID_{corr} := ID + 2(C_{is}) = 52.65 \text{ in}$ Corroded Elastic Section Modulus $S_{x_corr} := \frac{\pi(OD_{corr}^4 - ID_{corr}^4)}{32 \cdot OD_{corr}} = 1422.94 \text{ in}^3$ Allowable Utilization Considering Corrosion $Util_{all} := \frac{S_{x_corr}}{S_{x_KP}} = 0.94$ Tierod Wallap Input Diameter: $d_{tie} := 3.5 \text{ in}$ Area: $A_{tie} := 9.61 \text{ in}^2$ <i>(Minimum net area thru threads)</i>						

GEI




Consultants

Client	BROWN COUNTY WI			Page	
Project	Port Property Development			Pg. Rev.	X
By	E. Burton	Chk.		App.	
Date	10/22/2025	Date		Date	

Project No.	2201593	Document No.	N/A
Subject	Wallap Analysis - Inputs		

PIPE COMBINED WALLS

Pipe-Z with E22 Connector System*



Pipe Diameter in mm	Wall Thickness in mm	Intermediate Sheet Pile	Sheet Pile Connector	System Width in mm	Moment of Inertia in ⁴ /ft cm ⁴ /m	Section Modulus in ³ /ft cm ³ /m	Weight (NZ Length / Pipe Length)			Cross Sectional Area in ² /ft ² cm ² /m
							100%	80%	60%	
36 914	0.375 9.5	NZ 14	E22	99.19 2519.4	911 124341	50.6 2700	32.2 1575	29.3 140.8	26.3 128.2	8.99 190.3
36 914	0.438 11.1	NZ 19	E22	93.68 2379.4	1158 160362	64.3 3069	37.2 1813	34.0 1661	30.8 150.6	10.43 223.7
42 1067	0.500 12.7	NZ 14	E22	106.19 2678.8	1700 232167	81.0 4353	39.4 192.5	36.6 178.7	33.8 164.9	11.83 235.5
42 1067	0.563 14.3	NZ 19	E22	99.68 2519.8	2051 281103	97.6 5050	40.9 200.3	41.9 204.8	39.0 190.2	12.73 269.5
48 1219	0.563 14.3	NZ 14	E22	111.19 2824.2	2641 360548	110.0 5056	44.2 215.7	41.5 202.6	38.8 189.6	12.54 265.5
48 1219	0.625 15.875	NZ 19	E22	106.68 2694.2	3112 424998	129.6 6070	50.0 2443	47.2 230.4	44.4 216.7	14.25 318.6
54 1372	0.625 15.9	NZ 19	E22	111.68 2836.6	4150 566773	153.7 8265	51.6 252.0	49.0 239.9	46.3 226.1	14.75 320.2
54 1372	0.688 17.5	NZ 26	E22	111.68 2836.6	4607 629086	170.6 9713	58.9 2874	55.5 2719	52.2 254.7	16.86 356.9
60 1524	0.688 17.5	NZ 19	E22	117.68 2989.0	5882 803278	196.1 10541	571 278.8	54.6 266.5	52.1 254.2	16.38 346.8
60 1524	0.750 19.1	NZ 26	E22	117.68 2989.0	6445 880260	214.8 11530	64.3 3143	61.1 296.6	58.0 283.1	18.49 391.2
66 1676	0.750 19.1	NZ 19	E22	123.68 3161.4	8066 107434	244.4 12147	62.8 306.5	60.4 296.7	58.0 283.0	18.07 382.4
66 1676	0.813 20.7	NZ 26	E22	123.68 3161.4	8769 119780	265.7 14387	70.3 342.2	67.9 3274	64.0 312.7	20.20 4276
72 1829	0.813 20.7	NZ 26	E22	129.68 3293.6	10838 1479947	301.0 16085	71.7 349.9	68.8 336.8	65.9 321.8	20.68 437.8
72 1829	0.875 22.2	NZ 26	E22	129.68 3293.6	11621 1588893	322.8 17255	76.0 371.0	73.1 356.9	70.2 342.8	21.95 464.6
78 1981	0.875 22.2	NZ 26	E22	135.68 3446.2	14114 1937403	361.9 19497	77.6 378.8	74.8 365.4	72.1 351.9	22.44 475.0
78 1981	0.938 23.8	NZ 26	E22	135.68 3446.2	15082 2099540	386.7 20791	82.1 401.0	79.4 3873	76.6 3743	23.77 503.2
84 2134	0.938 23.8	NZ 26	E22	141.68 3588.6	18045 2447133	429.6 23049	83.7 408.8	81.1 396.0	78.5 3833	24.26 513.6
84 2134	1.000 25.4	NZ 26	E22	141.68 3588.6	19184 2687754	456.8 24558	88.3 429.4	85.7 418.3	83.1 405.6	25.62 542.2

* Additional combinations are available upon request.

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	X
	By	E. Burton	Chk.		App.	
	Date	10/22/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Wallap Analysis - Inputs					

REINFORCING STEEL GRADE / COLD ROLLED

FULLY THREADED BAR




Approx. Major Thread Diameter

Grade 80 ksi Yield Strength / 100 ksi Ultimate Strength									
Bar Designation	Nominal Diameter	Grade	Min. Net Area Thru Threads	Min. Ultimate Strength	Min. Yield Strength	Nominal Weight	Approx. Major Thread Diameter	Thread Orientation	Max. Length
	in mm		in ² mm ²	kips kN	kips kN	lbs/ft kg/m	in mm		ft m
#18	2 ¼ 55	80	4.000 2581.0	400.0 1779	320.0 1423	13.60 20.2	2.438 62.0	Right Hand	60 18.3
#20	2 ½ 64	80	4.910 3168.0	491.0 2184	392.8 1747	16.69 24.8	2.750 70.0	Right Hand	60 18.3
#24	3 76	80	7.070 4561.0	707.0 3145	565.6 2516	24.10 35.9	3.250 82.6	Right Hand	60 18.3
#28	3 ¼ 89	80	9.610 6200.0	961.0 4275	768.8 3420	32.70 48.7	3.750 95.3	Right Hand	60 18.3
#32	4 102	80	12.57 8107.0	1257.0 5590	1005.3 4472	42.75 63.6	4.125 104.8	Right Hand	40 12.2

Cold rolled threaded bars conform to the physical and chemical requirements of ASTM A615 Grade 80 ksi "Standard Specification for Deformed Carbon Steel Bars for Concrete Reinforcement".
Contact your sales representative for information on hot dip galvanized and epoxy coated bars.

	Client	BROWN COUNTY WI			Page	
	Project	Port Property Development			Pg. Rev.	0
	By	E. Burton	Chk.	C. Englert	App.	A. Pepin
	Date	08/19/2025	Date		Date	
Project No.	2201593	Document No.	N/A			
Subject	Port Property Development – Dock Wall Design					
ATTACHMENT 4: UNDRAINED AND DRAINED ELASTIC MODULI						

Soil Mechanics

T. William Lambe • Robert V. Whitman

Massachusetts Institute of Technology

1969

JOHN WILEY & SONS, New York • Chichester • Brisbane • Toronto • Singapore




Fig. 12.7 Results of high-stress, confined compression tests on several sands (data from Roberts, 1964).

The stress-strain curve for an initial loading generally resembles a parabola. Hence the stress-strain relationship may be expressed as

$$\sigma_v = C(\epsilon_v)^n \quad (12.13)$$

The coefficient C varies with the type of soil and its initial void ratio. For a wide variety of soils, however, the

exponent n has been found to be very close to 2. For a perfect packing of elastic spheres, this exponent would be 3. The difference between the theoretical and actual values for the exponent is the result of sliding among and rearrangement of the particles within an actual soil. Equation 12.13 implies that both secant modulus from zero stress and the tangent modulus should increase as $\sqrt{\sigma_v}$.

Table 12.2 Relations Between Various Stress-Strain Parameters for Confined Compression

	Constrained Modulus	Coefficient of Volume Change	Coefficient of Compressibility	Compression Index
Constrained modulus	$D = \frac{\Delta \sigma_v}{\Delta \epsilon_v}$	$D = \frac{1}{m_v}$	$D = \frac{1 + e_0}{a_v}$	$D = \frac{(1 + e_0)\sigma_{va}}{0.435C_c}$
Coefficient of volume change	$m_v = \frac{1}{D}$	$m_v = \frac{\Delta \epsilon_v}{\Delta \sigma_v}$	$m_v = \frac{a_v}{1 + e_0}$	$m_v = \frac{0.435C_c}{(1 + e_0)\sigma_{va}}$
Coefficient of compressibility	$a_v = \frac{1 + e_0}{D}$	$a_v = (1 + e_0)m_v$	$a_v = -\frac{\Delta e}{\Delta \sigma_v}$	$a_v = \frac{0.435C_c}{\sigma_{va}}$
Compression index	$C_c = \frac{(1 + e_0)\sigma_{va}}{0.435D}$	$C_c = \frac{(1 + e_0)\sigma_{va}m_v}{0.435}$	$C_c = \frac{a_v\sigma_{va}}{0.435}$	$C_c = -\frac{\Delta e}{\Delta \log \sigma_v}$

Note. e_0 denotes the initial void ratio. σ_{va} denotes the average of the initial and final stresses.

DRAINED ELASTIC MODULUS BASED ON CONSOL TESTS -- C_c

**Virginia Polytechnic Institute
And State University**

**The Charles E. Via, Jr.
Department of Civil Engineering**

**CENTER FOR
GEOTECHNICAL PRACTICE AND RESEARCH**

Engineering Manual for Settlement Studies

by


J. Michael Duncan

and

A. L. Buchignani

**Report of a study performed by the Virginia Tech Center for
Geotechnical Practice and Research**

**Revised October 1987
CGPR #2**



Center for
Geotechnical Practice and Research
200 Patton Hall
Blacksburg, VA 24061



AN ENGINEERING MANUAL FOR
SETTLEMENT STUDIES

by


J. M. Duncan

and

A. L. Buchignani

June, 1976

Revised October, 1987



UNDRAINED ELASTIC MODULUS

$$E = 600 * S_u$$

$$E_u = K S_u$$

E_u = UNDRAINED MODULUS OF CLAY

K = FACTOR FROM CHART ABOVE

S_u = UNDRAINED SHEAR STRENGTH OF CLAY

Fig. 5 CHART FOR ESTIMATING UNDRAINED MODULUS OF CLAY